# **Federal Operating Permit** Article 1

This permit is based upon the requirements of Title V of the Federal Clean Air Act and Chapter 80, Article 1, of the Commonwealth of Virginia Regulations for the Control and Abatement of Air Pollution. Until such time as this permit is reopened and revised, modified, revoked, terminated or expires, the permittee is authorized to operate in accordance with the terms and conditions contained herein. This permit is issued under the authority of Title 10.1, Chapter 13, §10.1-1322 of the Air Pollution Control Law of Virginia. This permit is issued consistent with the Administrative Process Act, and 9 VAC 5-80-50 through 9 VAC 5-80-300 of the State Air Pollution Control Board Regulations for the Control and Abatement of Air Pollution of the Commonwealth of Virginia.

Authorization to operate a Stationary Source of Air Pollution as described in this permit is hereby granted to:

Permittee Name: General Shale Brick, Inc. Facility Name: General Shale Brick, Inc. Facility Location: 770 Webster Road, Blue Ridge, Virginia 24064 AIRS ID: 51-023-0006 Permit Number: VA-20447

June 14, 2001 Issue Date June 14, 2001 Effective Date June 14, 2006 **Expiration Date** Amended: October 4, 2001 Significant Modification: March 1, 2005 September 20, 2005 **Current Minor Modification Date** Signature Date

Robert G. Burnley, Director, Department of Environmental Quality Table of Contents, (2 pages), Permit Conditions, 40 pages inclusive

# **Table of Contents**

I.	Permittee Permittee	
	Responsible Official	
	Facility Contacts	
	Virginia DEQ Registration Number	
	AIRS Identification Number.	
	Facility Description.	
TT	European Hatte	,
II	Emission Units	
	Plant 35 Brick Making & Texturing (02)	
	Plant 36 Brick Making & Texturing (02)	
	Plant 35 "A" Dryer/Kiln (04) and "B" Dryer/Kiln (05)	
	Plant 36 Dryer/Kiln (06)	
	Flant 30 Diyer/Kim (00)	/
III	Process Equipment Requirements - Existing Equipment	
	A. Limitations	
	B. Monitoring	
	C. Record keeping	
	D. Testing	
	E. Reporting	11
IV	Process Equipment Requirements - New / Modified Equipment	11
	A. Limitations	
	B. Monitoring	18
	C. Record keeping	20
	D. Testing	22
	E. Reporting	23
V	Facility Wide Conditions	24
	A. Limitations	
	B. Monitoring	25
	C. Record keeping	
	<b>D.</b> Testing	
	E. Reporting	
VI	Insignificant Emission Units	28
VII	[ Compliance Plan	28
	II Permit Shield & Inapplicable Requirements	
V 11	11 - 1 & 11111 MICIU & 1114PPIICANIC NCYUN CHICHO	

# Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 3

IX	General Conditions	29
	A. Federal Enforceability	29
	<b>B.</b> Permit Expiration	29
	C. Record Keeping and Reporting	
	D. Annual Compliance Certification	31
	E. Permit Deviation Reporting	32
	F. Failure/Malfunction Reporting	32
	G. Severability	32
	H. Duty to Comply	
	I. Need to Halt or Reduce Activity not a Defense	33
	J. Permit Action for Cause	33
	K. Property Rights	34
	L. Duty to Submit Information	34
	M. Duty to Pay Permit Fees	34
	N. Fugitive Dust Emission Standards	34
	O. Startup, Shutdown, and Malfunction	35
	P. Alternative Operating Scenarios	35
	Q. Inspection and Entry Requirements	35
	R. Reopening For Cause	36
	S. Permit Availability	36
	T. Transfer of Permits	37
	U. Malfunction as an Affirmative Defense	37
	V. Permit Revocation or Termination for Cause	38
	W. Duty to Supplement or Correct Application	38
	X. Stratospheric Ozone Protection	38
	Y. Accidental Release Prevention	38
	<b>Z.</b> Changes to Permits for Emissions Trading - <i>Not Applicable</i>	38
	AA Emissions Trading - Not Applicable	38
X	State-Only Enforceable Requirements	30
∠ <b>\</b>	A. Limitations	
	B. Monitoring	
	C. Record keeping	
	D. Testing	
	E. Reporting	
	L. Roporting	

**ATTACHMENT A** - 40 CFR 63 Subpart JJJJJ, the Maximum Achievable Control Technology (MACT) Standard for Brick and Structural Clay Products, and 40 CFR 60 Subpart OOO, Standards of Performance for Non-Metallic Mineral Processing Plants.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 4

# I. Facility Information

Permittee

General Shale Brick, Inc. P. O. Box 3547 Johnson City, TN 37602

**Facility Contacts** 

General Shale Brick, Inc., Plants 35 & 36 770 Webster Road Blue Ridge, Virginia 24064

Virginia DEQ Registration Number: 20447

AIRS Identification Number: 51-023-0006

**Responsible Official** 

Dave McNees
Director of Environment

Dave McNees - Director of Environment (423) 282-4661 Martha West - Environmental Engineer (423) 952-4240

**Facility Description:** SIC Code 3251 - Face Brick / Structural Manufacture of brick from shale. The manufacturing process involves mining, grinding, screening, and blending of the raw materials followed by forming, cutting or shaping, drying, firing (or curing), cooling, storage, and shipping of the final product.

General Shale Brick, Inc. is the current owner of what was previously known as Webster Brick. The plant was registered and permitted in 1973 for the addition of Plant 36, an Interkiln natural gas-fired Dryer/Kiln - 18 "brick" x 389' long – rated at approximately 14.8 tons per hour input. Plant 35 was the existing "grandfathered" portion of the facility, which consisted of shale mining, crushing & screening, handling, and 2 kilns. Records show the Plant 35 kilns "A" and "B" as being installed in 1954. Webster Brick had been in existence at this site since 1928. The source has recently received a permit to modify and operate Plant 35 by installing a coal processing / handling system (Unit # 01-07) and to fire Kilns 35 "A" and "B" with a coal / natural gas blend.

The brick-making process is as follows: the raw shale is generally loaded by truck or front-end loader into an existing primary crusher for initial size reduction. The inherent moisture content of the raw shale ranges from 3 - 15%. The material is then conveyed to an enclosed grinding room, which houses several grinding mills and banks of screens that produce a fine material that is suitable for forming brick or other products. The shale is conveyed to an enclosed storage area, where it is then used to form bricks in the forming area.

The bricks are formed using a stiff mud extrusion process. The ground raw material is mixed with water and possibly other additives in a pug mill, then the raw material is discharged into a vacuum chamber. The moisture content of the material entering the vacuum chamber at General Shale is typically between 15% and 20%. The vacuum chamber removes air from the material, which is then augered or extruded into continuous columns of soft, formed mud. The columns are then treated with various friction or setting materials, and wire-cut into soft bricks. Various sands, slurries and engobes used as coloring and texturing

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 5

agents are also prepared and applied to the surface of the brick. The green bricks at both plants are mechanically set into kiln cars.

The formed raw, or "green" bricks which are loaded onto kiln cars are then sent to a pre-dryer which utilizes waste heat from the kilns, then to one of three kilns at General Shale. Kilns "A" & "B" at Plant 35 are tunnel-type kilns that measure 8 "brick" wide by 417 feet long, and have been modified to fire coal and natural gas with a vaporized propane backup fuel capacity. These two kilns are identical, parallel units. Plant #36 tunnel kiln measures 18 "brick" wide by 389 feet long, fueled by natural gas with a vaporized propane backup. Each include a preheat zone, a firing zone, and a cooling zone. Firing of the green bricks involves six steps: the evaporation of free water, dehydration, oxidation, vitrification, flashing, and cooling.

Stoker-sized coal is charged into the coal processing system at Plant 35 by a wheel loader. The continuous, enclosed system dries and pulverizes the coal to the proper size graduation and distributes it to both Plant 35 kilns.

Uncontrolled PM and  $PM_{10}$  emissions occur from the raw material grinding, screening, handling & storage, as well as fugitive emissions from paved/unpaved roads, or storage piles. Emissions from the brick texturing equipment are controlled by Enviro-systems pulse-jet baghouses 02 and 03 for plants 35 & 36 respectively. Particulate emissions from the Coal Processing System at Plant 35 are controlled by a fabric filter baghouse. Products of combustion at Plant 35 are managed by proper operation and combustion practices, use of low sulfur and ash coal, and are exhausted through a common dry lime adsorption system (DLA).

Emissions that occur during kiln firing and cooling are PM, PM<sub>10</sub>, SO<sub>2</sub>, SO<sub>3</sub>, CO & CO<sub>2</sub>, NOx, TOC, VOC, and various HAPs, including HCl and HF. Plant 36 Natural gas combustion emissions, SO<sub>2</sub>, NOx, CO, CO<sub>2</sub> and VOCs, are produced in small amounts, and SO<sub>2</sub> emissions may increase slightly due to higher sulfur content of the brick material. Coal combustion at Plant 35 produce emissions of PM, PM<sub>10</sub>, SO<sub>2</sub>, NOx, CO, and VOCs. Pollutant emissions are calculated using appropriate emission factors which take into consideration both fuel usage, fuel and throughput limitations, add-on or inherent controls, and raw material constituents.

General Shale Brick, Inc. is subject to Title V permitting requirements due to its potential to emit more than 100 tons per year of particulate (PM<sub>10</sub>), sulfur dioxide (SO<sub>2</sub>), carbon monoxide (CO) and more than 10 tons per year of an individual hazardous air pollutant, namely hydrogen fluoride (HF) and hydrochloric acid (HCl). Underlying minor NSR permits that are in effect for the facility are: Permit to Construct and Operate dated August 2, 1973, Permit to Construct and Operate dated January 4, 1999 as amended September 25, 2001, Permit to Modify and Operate dated July 1, 2005 and Permit to Modify and Operate dated Dec. 30, 2003 as amended July 5, 2005.

Title V Permit Number: VA-20447

# Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 6

**II. Emission Units** – This table is a representation of all regulated equipment at the facility. The table is included as a reference to be used for informational purposes only, and does not include applicable requirements.

Equipment to be operated consists of:

Emission Unit ID	Stack ID	Emission Unit Description	Size/Rated Capacity	Pollution Control Device Description (PCD)	PCD ID	Pollutant Controlled	Applicable Permit Date	
Shale Prep	Shale Preparation (01)							
01-01	01	(2) Steele Primary Crushers - 1973	75 tons/hr each	Wet Material (15-20% inherent moisture) & Enclosure)	Not Applicable	Not Applicable	August 2, 1973	
01-02	01	Steele Hammermill- Model 36-24 (1994)	100 tons/hr	Wet Material (15-20% inherent moisture) & Enclosure	01	PM/PM <sub>10</sub>	July 1, 2005	
01-03	01	#1 Cage Mill (1994)	75 - 80 tons/hr	Wet Material (15-20% inherent moisture) & Enclosure	01	PM/PM <sub>10</sub>	July 1, 2005	
01-04	01	(8) 4' x 10' Leahy Screen(s), inside	75 tons/hr total	Wet Material (15-20% inherent moisture) & Enclosure	01	PM/PM <sub>10</sub>	Not Applicable	
01-05	01	(11) Custom belt conveyors Various capacities, inside	75 tons/hr each maximum	Wet Material (15-20% inherent moisture) & Enclosure	01	PM/PM <sub>10</sub>	Not Applicable	
01-06	01A	Bulk Material Storage Silo 33' 7" x 10' (1999)	20,000 lb/hr (10 tons/hr); 60 Yd <sup>3</sup> / 75 tons capacity	Bin Vent Filter - Ultra Model BB-1684	01A	PM/PM <sub>10</sub>	January 4, 1999 (amended Sept. 25, 2001)	
01-07	N/A	C.E. Raymond / Custom Coal Processing System	2.6 tons/hr	Pulse-Jet Baghouse	07	PM/PM <sub>10</sub>	December 30, 2003;(amended July 5, 2005)	

Title V Permit Number: VA-20447

# Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 7

Emission Unit ID	Stack ID	Emission Unit Description	Size/Rated Capacity	Pollution Control Device Description (PCD)	PCD ID	Pollutant Controlled	Applicable Permit Date
Plant 35 B	rick Makiı	ng & Texturing (02)					
02-01	02	Steele Brick Machine (for ground shale) – 1954	70 tons/hr	None (building capture)	02	PM/PM <sub>10</sub>	Not Applicable
02-02	02	Custom-built brick texturing equipment – 1954	2 tons/hr	Enviro-Systems, BU-80 Pulse- Jet Baghouse	02	PM/PM <sub>10</sub>	Not Applicable
Plant 36 B	rick Makiı	ng & Texturing (03)					
03-01	03	Steele Brick Machine (for ground shale) – 1973	65 tons/hr	Baghouse - Gold Series Collector, Model GS-12	03	PM/PM <sub>10</sub>	August 2, 1973
03-02	03	Custom-built brick texturing equipment – 1973	2 tons/hr	Enviro-Systems, BU-136 Pulse-Jet Baghouse	03	PM/PM <sub>10</sub>	August 2, 1973
Plant 35 "A	A" Dryer/I	Kiln (04) and "B" Dryer/Kiln (05)					
04	04	35 "A" Dryer/Kiln - Harrop Dryer/ Kiln 8 "brick" wide x 417' long-1954	8.2 tons/hr input 6.5 tons/hr output 16.7 MMBtu/hr	None	Not Applicable	Not Applicable	December 30, 2003; (amended July 5, 2005)
05	05	35 "B" Dryer/Kiln - Harrop Dryer/ Kiln 8 "brick" x 417' long - 1955	8.2 tons/hr input 6.5 tons/hr output 16.7 MMBtu/hr	None	Not Applicable	Not Applicable	December 30, 2003; (amended July 5, 2005)
Plant 36 D	ryer/Kiln (	(06)					
06	06	Interkiln Dryer/Kiln - 18 "brick" x 389' long – 1973	14.8 tons/hr input 11.8 tons/hr output 25 MMBtu/hr	None	Not Applicable	Not Applicable	August 2, 1973

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 8

# III. Process Equipment Requirements - Existing Equipment

**Unit # 01-04 - (8) Leahy Screens (75 tons/hr)** 

**Unit # 01-05 - (11) Custom Conveyors (7 tons/hr)** 

Unit # 02-01 - Steele Brick Machine (Plant 35) (65 tons/hr)

Unit # 02-02 - Custom-built brick texturing equipment (Plant 35) (2 tons/hr)

#### A. Limitations

1. Control Equipment - Particulate emissions from the Custom-built brick texturing equipment facility (Unit #02-02) shall be controlled by the use of a fabric filter baghouse. (9 VAC 5-80-110)

# 2. Existing Source Standard for Particulate Matter for Sand and Gravel Processing Operations and Stone Quarrying and Processing Operations -

No owner or other person shall cause or permit any material to be produced, handled, stockpiled or transported without taking measures to reduce to a minimum any particulate matter from becoming airborne. Where it is practical to measure the emission, the emission shall not exceed the limits established by Table 4-14 of 9 VAC 5-40-1840. All such airborne particulate matter emanating from the yards, sidings or roads of such operations shall be considered fugitive dust and shall be controlled as stipulated in 9 VAC 5-40-1860. All crushers shall be fitted with liquid sprays or other appropriate systems that effectively limit the escape of airborne dust. Vibrating and shaker screens handling dry materials shall be enclosed or fitted with a collector system that will prevent the release of more than 0.05 grains per standard cubic foot. All feeders, elevators, conveyors, transfer points, discharge points and loading points shall be equipped with collectors, sprays or other means when necessary to minimize the escape of dust. This standard is applicable to the following emission units: (Unit # 01-04, # 01-05)

Stone/Sand & Gravel Processing particulate emissions based on Table 4-14 of 9 VAC 5-40-1840 are limited to the following:

Existing Source ID #	Description	Rated Capacity	PM / PM10 Limit lb/hr	PM / PM10 Limit tons/yr
01-04	Leahy Screen (8)	75 tons/hr total	48.45	100.77
01-05	Custom Conveyors (11)	75 tons/hr total	48.45	100.77

Compliance with the particulate emission standard may be demonstrated using the following equation: particulate emission rate (lbs/hr) = bricks produced (tons/hr) x particulate emission factor (lbs/ton). The emission factor shall be based on the results of a stack test of this facility or similar facilities, or, if these are not available the appropriate emission factor given in Section

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 9

11.3 AP-42 (8/97) may be used. Annual emissions are to be calculated monthly as the sum of each consecutive 12-month period (9 VAC 5-80-110 and 9 VAC 5-40-1840)

3. Existing Source Standard for Particulate Matter (AQCR 1-6) - General Process Operations - Interpolation of the data in Table 4-4A of 9 VAC 5-40-260 for process weight rates up to 60,000 lb/hr shall be accomplished by use of the following equation:  $E = 4.10 P^{0.67}$ , where E = emission rate in lb/hr, and P = process weight rate in tons/hr. This standard is applicable to the following existing emission units: (Unit # 02-01, # 02-02).

General Process particulate emissions based on Table 4-4A of 9 VAC 5-40-260 are limited to the following:

Source ID	Description	Rated Capacity	PM / PM10 Limit lb/hr	PM / PM10 Limit tons/yr
02-01	Steele Brick Machine & Custom Texture equipment (Plant 35)	65 tons/hr	47.05	48.93
02-02	Custom built brick texturing equipment (Plant 35)	2 tons/hr	6.52	6.78

Compliance with the particulate emission standard may be demonstrated using the following equation: particulate emission rate (lbs/hr) = bricks produced (tons/hr) x particulate emission factor (lbs/ton). The emission factor shall be based on the results of a stack test of this facility or similar facilities, or, if these are not available, the appropriate emission factor given in Table 11.3-2 of AP-42 (8/97) may be used. Annual emissions are to be calculated monthly as the sum of each consecutive 12-month period.

(9 VAC 5-80-110 and 9 VAC 5-40-260 C)

4. Existing Source Standard for Visible Emissions - Unless otherwise specified in this part, no owner or other person shall cause or permit to be discharged into the atmosphere from any affected facility any visible emissions which exhibit greater than 20% opacity, except for one six-minute period in any one hour of not more than 60% opacity. Failure to meet the requirements of this section because of the presence of water vapor shall not be a violation of this section. This standard is applicable to the following emission units: existing screens (Unit # 01-04), existing conveyors (Unit # 01-05) and the Steele Brick Machine & Custom Texture equipment for Plant 35 (Unit # 02-01 and # 02-02).

(9 VAC 5-80-110 and 9 VAC 5-40-90)

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 10

5. Operation and Maintenance - Emissions from existing sources shall be controlled by proper operation and maintenance. Operators shall be trained in the proper operation of all such equipment. Training shall consist of a review and familiarization of the manufacturer's operating instructions, at minimum. This standard is applicable to the following emission units: existing screens (Unit # 01-04), existing conveyors (Unit # 01-05), and the Steele Brick Machine & Custom Texture equipment for Plant 35 (Unit # 02-01 and # 02-02). (9 VAC 5-80-110)

#### B. Monitoring

1. Control Equipment - The fabric filter controlling the custom-built brick texturing equipment (Unit # 02-02) shall be equipped with a device to continuously measure the differential pressure drop across the fabric filter. The device shall be constructed in an accessible location and shall be maintained by the permittee such that it is in proper working order. (9 VAC 5-80-110)

#### C. Record keeping

- 1. Data The permittee shall maintain records of all emission data and operating parameters necessary to demonstrate compliance with this permit. The content of and format of such records shall be arranged with the Director, West Central Regional Office. These records shall include, but are not limited to:
  - a. The annual throughput of shale, calculated monthly as the sum of each consecutive twelve (12) month period.
  - b. The annual production of brick for each kiln, calculated monthly as the sum of each consecutive twelve (12) month period.

These records shall be available on site for inspection by the DEQ and shall be current for the most recent five (5) years. (9 VAC 5-80-110)

2. Training – Operation & Maintenance - The permittee shall maintain records of the required training including a statement of time, place and nature of training provided. The permittee shall have available good written operating procedures and a maintenance schedule for all existing equipment located at the facility as listed in Condition III of this permit. These procedures shall be based on the manufacturer's recommendations, at minimum. All records required by this condition shall be kept on site and made available for inspection by the DEQ. (9 VAC 5-80-110)

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 11

#### D. Testing

1. **Ports** / **Methods** - Upon request from the Department, test ports will be provided at the appropriate locations. If testing is conducted in addition to the monitoring specified in this permit, the permittee shall use test methods in accordance with procedures approved by the DEO.

(9 VAC 5-40-30 and 9 VAC 5-80-110)

## E. Reporting

The reporting requirements for this section are satisfied by the record keeping requirements in this section and by the General Permit Conditions in the Facility-Wide and General Requirements section.

# IV. Process Equipment Requirements - New / Modified Equipment

- Unit # 01-01 (2) Steele Primary Crushers (75 tons/hr)
- Unit # 01-02 Steele Hammermill-Model 36-24 (100 tons/hr) (NSPS OOO)
- Unit # 01-03 #1 Cage Mill (75 80 tons/hr) (NSPS OOO)
- Unit # 01-06 Bulk Material Storage Silo (10 tons/hr, 75 ton capacity)
- Unit # 03-01 Steele Brick Machine (Plant 36) (65 tons/hr)
- Unit # 03-02 Custom built brick texturing equipment (Plant 36) (2 tons/hr)
- Unit # 04 Plant 35 "A" Dryer / Kiln Harrop 8 (brick) wide x 417 feet long fired with coal and natural gas rated at 18.2 MMBtu/hr
- Unit # 05 Plant 35 "B" Dryer / Kiln Harrop 8 (brick) wide x 417 feet long fired with coal and natural gas rated at 18.2 MMBtu/hr
- Unit # 06 Plant 36 InterKiln Tunnel/Dryer/Kiln 18 (brick) wide x 389 feet long fired with natural gas rated at 25 MMBtu/hr
- Unit # 07 C.E. Raymond / Custom Coal Processing System rated at 2.6 tons/hr

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 12

#### A. Limitations

- 1. Plant 35 Plantwide Production Plant 35, which is comprised of Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B"), shall produce no more than 143,664 tons of brick per year, calculated monthly as the sum of each consecutive 12 month period.

  (9 VAC 5-80-110, 9 VAC 5-80-1180, 9 VAC 5-50-260 and C. 10 of the 12/30/03 minor source permit, as amended 7/5/05)
- 2. Fuel: Plant 35 The approved fuels for Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") at Plant 35 are coal and natural gas (with propane backup). The kilns may be fired with 100% natural gas, or a mix of coal with natural gas supplement. A change in the approved fuels may require a permit to modify and operate.

  (9 VAC 5-80-110, 9 VAC 5-80-1180, 9 VAC 5-50-260 and C. 11 of the 12/30/03 minor source permit, as amended 7/5/05)
- **3. Fuel: Plant 36 -** The approved fuels for the Plant 36 kiln (Unit # 06) are natural gas and propane as a backup fuel. A change in the fuels may require a permit to modify and operate. (9 VAC 5-80-110)
- **4. Fuel Throughput** For optimum kiln combustion, Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") shall <u>each</u> consume no more than 1,020 lbs/hr (0.51 tons/hr) of coal, calculated monthly as total pounds (tons) of coal divided by total kiln operating hours; and 4,468 tons of coal per year, calculated monthly as the sum of each consecutive 12 month period. (9 VAC 5-80-110, VAC 5-80-1180, 9 VAC 5-50-260 and C. 12 of the 12/30/03 minor source permit, as amended 7/5/05)
- **5. Fuel Specifications** The coal, natural gas, and propane used for fuel in Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") shall meet the specifications below:

#### COAL:

Maximum sulfur content per shipment: 1.0%
Maximum ash content per shipment: 6.0%

NATURAL GAS:

Minimum heat content: 1,000 BTU/cf

LPG, including butane and propane, which meets ASTM specification D1835

(9 VAC 5-80-110, 9 VAC 5-80-1180, 9 VAC 5-50-260 and C. 13 of the 12/30/03 minor source permit, as amended 7/5/05)

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 13

- **6. Emission Controls** Sulfur dioxide emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") at Plant 35 shall be controlled by a single Ohlmann type dry lime adsorber (DLA). The shared dry lime adsorber shall be provided with adequate access for inspection and shall be in operation when one/both of the associated kiln(s) is/are operating. (9 VAC 5-80-110, 9 VAC 5-50-260 and C. 3 of the 12/30/03 minor source permit, as amended 7/5/05)
- 7. **Emission Controls** Particulate and sulfur dioxide emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") at Plant 35 shall be controlled by:
  - a. Installation of target firing reducing solid fuel requirements;
  - b. Operating the dryer/kilns under reduced draft conditions;
  - c. Use of supplemental fuel (natural gas) to reduce solid fuel requirement.
  - d. Fuel specifications to include low sulfur and ash content of coal.

(9 VAC 5-80-110, 9 VAC 5-50-260 and C. 4 of the 12/30/03 minor source permit, as amended 7/5/05)

- **8. Emission Controls** Particulate emissions from Unit # 07 (Coal Processing System) shall be controlled by a fabric filter baghouse. The baghouse shall be provided with adequate access for inspection and shall be in operation when Unit # 07 (Coal Processing System) is operating. (9 VAC 5-80-110, 9 VAC 5-50-260 and C. 5 of the 12/30/03 minor source permit, as amended 7/5/05)
- 9. Control Efficiency The dry lime adsorber (DLA) controlling emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") shall demonstrate a control efficiency by stack test for sulfur dioxide of no less than 10 percent (10%). Subsequent to the initial stack test, this permit may be modified to require the DLA to meet or exceed the control efficiencies established by initial stack test, using similar fuels, operating practices, and lime.

  (9 VAC 5-80-110, 9 VAC 5-50-260 and C. 6 of the 12/30/03 minor source permit, as amended 7/5/05)
- **10. Fugitive Dust Emission Controls -** Fugitive dust emission controls shall include the following, or equivalent, as a minimum:
  - a. Dust from material handling and load-outs, shall be controlled by wet suppression or equivalent (as approved by the DEQ). The wet suppression spray systems shall be operated at optimum design, and shall be installed with adequate access for inspection.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 14

- b. All material being stockpiled shall be kept adequately moist to control dust during storage and handling or covered at all times to minimize emissions.
- c. Dust from haul roads and traffic areas shall be controlled by the application of asphalt, water, suitable chemicals, or equivalent methods approved by the DEQ.
- d. Reasonable precautions shall be taken to prevent deposition of dirt on public roads and subsequent dust emissions. Dirt, product, or raw material spilled or tracked onto paved surfaces shall be promptly removed to prevent particulate matter from becoming airborne.

(9 VAC 5-80-110, 9 VAC 5-50-260, 9 VAC 5-50-20, 9 VAC 5-50-90, C. 4 of the 7/1/05 minor source permit and C. 7 of the 12/30/03 minor source permit, as amended 7/5/05)

- 11. Emission Control Particulate emissions from the Custom-built brick texturing equipment (Unit # 03-02) shall be controlled by the use of a fabric filter baghouse. The baghouse shall be provided with adequate access for inspection.

  (9 VAC 5-50-260, 9 VAC 5-80-110 and General Condition of August 2, 1973 Permit)
- **12. Emission Control** Particulate emissions from Unit # 01-02 the Steele Hammermill Model 36-24 A and Unit # 01-03 the #1 Cage Mill shall be controlled by wet suppression. The wet suppression spray systems shall be provided with adequate access for inspection. (9 VAC 5-50-260, 9 VAC 5-80-110 and C. 5. of the 7/1/05 minor source permit)
- 13. Emission Control Particulate emissions from the bulk material storage silo (Unit # 01-06) shall be controlled by a fabric filter. The fabric filter shall be provided with adequate access for inspection.
  - (9 VAC 5-80-110, 9 VAC 5-50-260 and Condition 3 of January 4, 1999 Permit, amended September 25, 2001)
- 14. Emission Control No owner or other person shall cause or permit to be discharged into the atmosphere from any affected facility any emissions in excess of that resultant from using best available control technology, as reflected in any condition that may be placed upon the permit approval for the facility. This standard is applicable to the following emission units: # 01-01 (Steele Primary Crushers), # 01-02 (Steele hammermill), # 01-03 (#1 Cage Mill), # 03-01(Steele Brick Machine-Plant 36), # 03-02 (Custom-built brick texturing equipment-Plant 36), # 04 (Kiln 35 "A") and # 05 (Kiln 35 "B"), and # 06 (Plant 36 Interkiln Dryer/Kiln).
  - (9 VAC 5-50-260, 9 VAC 5-80-110 and General Condition of August 2, 1973 Permit)
- **15. Production** The yearly production of crushed stone from Unit #01-02 the Steele Hammermill Model 36-24 A and Unit # 01-03 the #1 Cage Mill shall not exceed 285,000 tons, calculated monthly as the sum of each consecutive 12-month period.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 15

(9 VAC 5-80-110, and Condition 6 of the 7/1/05 minor source permit)

**16. Emission Limits** – Particulate emissions from the operation of the Unit #01-02 – the Steele Hammermill-Model 36-24 A shall not exceed the limits specified below:

Particulate Matter 3.0 lbs/hr 4.27 tons/yr PM-10 2.76 lbs/hr 3.94 tons/yr

These emissions are derived from the estimated overall emission contribution from operating limits. Exceedance of the operating limits shall be considered credible evidence of the exceedance of emission limits. Compliance with the particulate emission standard may be demonstrated by compliance with the emission controls stated in Condition IV. A 12, production limit stated in Condition IV. A. 15, the visible emission limitations as stated in Condition IV. A. 22 and IV. A. 23 and by using the following equation: particulate emission rate (lbs/hr) = bricks produced (tons/hr) x particulate emission factor (lbs/ton). The appropriate emission factor given in Section 11.3 of AP-42 (8/97) may be used. Annual emissions are to be calculated monthly as the sum of each consecutive 12-month period. (9 VAC 5-80-110, 9 VAC 5-50-260, and Condition 7 of the 7/1/05 minor source permit)

17. Emission Limits - Emissions from the operation of Unit # 01-03 - the #1 Cage Mill shall not exceed the limits specified below:

Particulate Matter 2.4 lbs/hr 4.27 tons/yr PM-10 2.21 lbs/hr 3.94 tons/yr

These emissions are derived from the estimated overall emission contribution from operating limits. Exceedance of the operating limits shall be considered credible evidence of the exceedance of emission limits. Compliance with the particulate emission standard may be demonstrated by compliance with the emission controls stated in Condition IV. A 12, production limit stated in Condition IV. A. 15, the visible emission limitations as stated in Condition IV. A. 22 and IV. A. 23 and by using the following equation: particulate emission rate (lbs/hr) = bricks produced (tons/hr) x particulate emission factor (lbs/ton). The appropriate emission factor given in Section 11.3 of AP-42 (8/97) may be used. Annual emissions are to be calculated monthly as the sum of each consecutive 12-month period. (9 VAC 5-80-110, 9 VAC 5-50-260, and Condition 8 of the 7/1/05 minor source permit)

**18. Emission Limits: Plant 36** – Total emissions from the operation of Plant 36 - Unit # 06 (Interkiln Dryer/Kiln) - shall not exceed the limits specified below:

Particulate Matter	14.68	lbs/hr	64.32	tons/yr
PM-10	13.01	lbs/hr	57.00	tons/vr

General Shale Brick, Inc.

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 16

Sulfur Dioxide	9.49	lbs/hr	41.55	tons/yr
Nitrogen Oxides (as NO <sub>2</sub> )	4.96	lbs/hr	21.71	tons/yr
Carbon Monoxide	16.99	lbs/hr	74.42	tons/yr
Volatile Organic Compounds	0.34	lbs/hr	1.49	tons/yr

Annual emissions calculated monthly as the sum of each consecutive 12-month period.

These emissions are derived from the estimated overall emission contribution from operating limits. Exceedance of the operating limits shall be considered credible evidence of the exceedance of emission limits. Compliance with these emission limits may be determined as stated in Condition numbers IV. A. 3, 14 and 21.

(9 VAC 5-80-110, 9 VAC 5-50-260 and 9 VAC 5-50-180)

**19. Emission Limits: Plant 35** – Total emissions from the operation of Plant 35 kilns - Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") - shall not exceed the limits specified below:

Particulate Matter	26.76 lbs/hr	117.23 tons/yr
PM-10	21.22 lbs/hr	92.95 tons/yr
Sulfur Dioxide	38.92 lbs/hr	170.46 tons/yr
Nitrogen Oxides (as NO <sub>2</sub> )	7.84 lbs/hr	34.34 tons/yr
Carbon Monoxide	19.68 lbs/hr	86.20 tons/yr
Volatile Organic Compounds	1.13 lbs/hr	4.94 tons/yr

Annual emissions calculated monthly as the sum of each consecutive 12-month period.

These emissions are derived from the estimated overall emission contribution from operating limits. Exceedance of the operating limits shall be considered credible evidence of the exceedance of emission limits. Compliance with these emission limits may be determined as stated in Condition numbers IV. A. 1, 2, 4, 5, 6, 7, 9, 14, 25 and IV B. 1 and 2. (9 VAC 5-80-110, 9 VAC 5-50-260, 9 VAC 5-50-180 and C. 16 of the 12/30/03 minor source permit, as amended 7/5/05)

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 17

**20. Emission Limits** – Baghouse exhaust emissions from the operation of the Unit # 07 (Coal Processing System) shall not exceed the limits specified below:

Particulate Matter 0.02 gr/dscf 0.37 lb/hr 1.62 tons/yr  $PM_{10}$  0.02 gr/dscf 0.37 lb/hr 1.62 tons/yr

Annual emissions calculated monthly as the sum of each consecutive 12-month period.

These emissions are derived from the estimated overall emission contribution from operating limits. Exceedance of the operating limits shall be considered credible evidence of the exceedance of emission limits. Compliance with these emission limits may be determined as stated in Condition numbers IV. 8 and 26.

(9 VAC 5-80-110, 9 VAC 5-50-260, 9 VAC 5-50-180 and C. 17 of the 12/30/03 minor source permit, as amended 7/5/05)

- 21. New / Modified Source Standard for Visible Emissions Unless otherwise specified in this part, no owner or other person shall cause or permit to be discharged into the atmosphere from any affected facility any visible emissions which exhibit greater than 20% opacity, except for one six-minute period in any one hour of not more than 30% opacity. Failure to meet the requirements of this section because of the presence of water vapor shall not be a violation of this section. This standard is applicable to the following emission units: Unit # 01-01 (Steele Primary Crushers), # 03-01 (Steele Brick Machine-Plant 36), # 03-02 (Custom-built brick texturing equipment-Plant 36), # 06 (Plant 36 Interkiln Dryer/Kiln).

  (9 VAC 5-50-80, 9 VAC 5-80-110 and General Condition of August 2, 1973 Permit)
- 22. New / Modified Source Visible Emission Limit Visible emissions from Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill shall not exceed seven percent (7%) opacity as determined by EPA Method 9 (reference 40 CFR 60, Appendix A). (9 VAC 5-50-80, 9 VAC 5-80-110, Condition 9 of the 7/1/05 minor source permit, and section 60.672 a.1. of 40 CFR 60, Subpart OOO)
- 23. New / Modified Source Visible Emission Limit Visible emissions from other fugitive emission points associated with Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill shall not exceed ten percent (10%) opacity as determined by EPA Method 9 (reference 40 CFR 60, Appendix A).
  - (9 VAC 5-50-260, 9 VAC 5-80-110, Condition 10 of the 7/1/05 minor source permit, and section 60.672 b. of 40 CFR 60, Subpart OOO)
- 24. New / Modified Source Visible Emission Limit Visible emissions from the bulk material storage silo (Unit # 01-06) fabric filter shall not exceed five percent (5%) opacity as determined by EPA Method 9 (reference 40 CFR 60, Appendix A).

  (9 VAC 5-80-110, 9 VAC 5-50-260 and Condition 4 of January 4, 1999 Permit)

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 18

- 25. New / Modified Source Visible Emission Limit Visible emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") exhaust stacks shall not exceed ten percent (10%) opacity except during one six-minute period in any one hour in which visible emissions shall not exceed twenty percent (20%) opacity as determined by the EPA Method 9 (reference 40 CFR 60, Appendix A).
  - (9 VAC 5-80-110, 9 VAC 5-50-260 and C. 18 of the 12/30/03 minor source permit, as amended 7/5/05)
- **26.** New / Modified Source Visible Emission Limit Visible emissions from Unit #07 (coal processing system) baghouse exhaust stack shall not exceed five percent (5%) opacity except during one six-minute period in any one hour in which visible emissions shall not exceed ten percent (10%) opacity as determined by the EPA Method 9 (reference 40 CFR 60, Appendix A).
  - (9 VAC 5-80-110, 9 VAC 5-50-260 and C. 19 of the 12/30/03 minor source permit, as amended 7/5/05)
- **27. Requirements by Reference NSPS:** Except where this permit is more restrictive than the applicable requirement, the NSPS designated equipment shall be operated in compliance with the requirements of 40 CFR 60, Subpart OOO. This standard is applicable to the following emission units: # 01-02 (Steele hammermill) and # 01-03 (#1 Cage Mill). (9 VAC 5-50-400, 9 VAC 5-50-410, 9 VAC 5-50-80, 9 VAC 5-80-110 and Condition 12 of the 7/1/05 minor source permit)
- **28. Requirements by Reference MACT:** Except where this permit is more restrictive than the applicable requirement, Plant 36 Kiln (Unit ID #06) shall comply with the control or operational requirements of 40 CFR 63 Subpart JJJJJ: *National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing* by the compliance date according to regulation. This regulation was promulgated on May 16, 2003. (9 VAC 5-80-110, 9 VAC 5-60-90, 9 VAC 5-60-100, and 40 CFR 63 Subpart JJJJJ)
- **29. Reactivation** Existing #2 cage mill and 7 existing belt conveyors have been removed and replaced with the Steele Hammermill Model 36-24 A. Reactivation of the old replaced units may require a permit.

(9 VAC 5-50-80, 9 VAC 5-80-110 and Condition 3 of the 7/1/05 minor source permit)

#### **B.** Monitoring

- **1. Fuel Certification** The permittee shall obtain a certification from the fuel supplier with each shipment of coal. Each fuel supplier certification shall include the following:
  - a. The name of the fuel supplier;

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 19

- b. The date on which the coal shipment was received;
- c. The volume of coal delivered in the shipment;
- d. The sulfur content (% sulfur) and ash content (% ash) of the coal.
- e. The method(s) used to determine the sulfur content and ash content of the coal.

(9 VAC 5-80-110, 9 VAC 5-80-1180 and C. 14 of the 12/30/03 minor source permit, as amended 7/5/05)

- 2. Coal/Coke Sulfur Content: If the fuel supplier certification as required in Condition IV. B. 1. of this permit (also C. 14 of the 12/30/03 minor source permit as amended 7/5/05) does not contain sufficient data for coal sulfur content and ash content, a sample of the coal delivered to the kiln burner(s) shall be collected at least once per week and composited for a monthly analysis. The composite shall be analyzed for percent (%) sulfur by weight and percent (%) ash by weight. The analyses shall meet the requirements of ASTM Methods D3177 or D4239 (sulfur content) and ASTM Methods D2795 or D3174 (ash content) or a DEQ approved equivalent method. The approved procedure for collecting the samples shall list all pertinent information regarding sample size and number, where sample is taken, etc. (9 VAC 5-80-110, 9 VAC 5-80-1180 and C. 15 of the 12/30/03 minor source permit, as amended 7/5/05)
- 3. **Emission Control Fabric filters:** The fabric filter controlling the particulate emissions from the Plant 36 Mill room (Unit # 03-01) and the Custom-built brick texturing equipment (Unit # 03-02) shall be equipped with a device to continuously measure the differential pressure drop across the fabric filter. The device shall be installed in an accessible location and shall be maintained by the permittee such that it is in proper working order at all times. (9 VAC 5-80-110, 9 VAC 5-50-260 and General Condition of August 2, 1973 Permit.)
- **4. Monitoring Devices / Observations** The permittee shall monitor the operational parameters listed below for the dry lime adsorber (DLA) controlling emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B"):
  - a. Maintain pressure drop at or above average pressure established during the initial performance test.
  - b. Visually verify limestone hopper and storage bin contains adequate limestone daily.
  - c. Record limestone feeder setting daily and maintain at or above level established during the initial performance test.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 20

- d. Use same grade limestone established during the initial performance test. Retain purchase records.
- e. Record visible emissions from the DLA exhaust stack weekly during normal operation of the kiln(s). The visible emissions evaluation (VEE) shall be conducted using 40 CFR 60 Appendix A Method 9 for at least six (6) minutes. 40 CFR 60 Appendix A Method 9 requires the observer to have a Method 9 certification that is current at the time of the VEE. All visible emission observations, VEE results, and corrective actions taken shall be recorded.

Monitoring device(s) shall be installed, maintained, calibrated and operated in accordance with approved procedures that shall include, as a minimum, the manufacturer's written requirements or recommendations. Each monitoring device shall be provided with adequate access for inspection and shall be in operation when the dry lime adsorber is operating. (9 VAC 5-80-110, 9 VAC 5-80-1180, 9 VAC 5-50-20 C and C. 8 of the 12/30/03 minor source permit, as amended 7/5/05)

- **5. Monitoring Device** / **Observation** The fabric filter baghouse controlling PM /  $PM_{10}$  emissions from Unit # 07 (Coal Processing System) shall be equipped with a magnehelic gauge to continuously measure the differential pressure drop across the fabric filter. The gauge shall be installed, maintained, calibrated and operated in accordance with approved procedures which shall include, as a minimum, the manufacturer's written requirements or recommendations. The magnehelic gauge shall be provided with adequate access for inspection and shall be in operation when the baghouse is operating. The gauge shall be observed by the permittee weekly to ensure good performance of the baghouse. The permittee shall keep a log of the observations from the magnehelic gauge.
  - (9 VAC 5-80-110, 9 VAC 5-80-1180, 9 VAC 5-50-20 C, 9 VAC 5-50-50-H and C. 9 of the 12/30/03 minor source permit, as amended 7/5/05)
- **6. Requirements by Reference: MACT Monitoring Requirements** Except where this permit is more restrictive, the permittee shall meet all monitoring requirements of 40 CFR 63 Subpart JJJJJ: *National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing* by the compliance date according to regulation. This regulation is applicable to Unit #06 (Plant 36 Kiln).
  - (9 VAC 5-60-90, 9 VAC 5-60-100, 9 VAC 5-80-110 and 40 CFR 63 subpart JJJJJ)

#### C. Record keeping

1. On Site Records - The permittee shall maintain records of emission data and operating parameters as necessary to demonstrate compliance with this permit. The content and format of such records shall be arranged with the Director, West Central Regional Office. These records shall include, but are not limited to:

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 21

- a. Daily, monthly and annual production of brick for Plants 35 and 36. Annual production shall be calculated monthly as the sum of each consecutive 12 month period.
- b. The monthly and annual throughput of shale processed through Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill. Annual throughput shall be calculated monthly as the sum of each consecutive 12-month period.
- c. Daily, monthly and hourly total operating hours of Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B"). Annual operating hours shall be calculated monthly as the sum of each consecutive 12 month period.
- d. Hourly and annual consumption of coal and natural gas (or propane as backup fuel) for Plants 35 and 36. Annual consumption shall be calculated monthly as the sum of each consecutive 12- month period.
- e. All records showing coal specifications for sulfur and ash content of 1% and 6% respectively for use in sulfur dioxide emission calculations, including records of any fuel supplier certifications and fuel analyses.
- f. All records and analyses of representative sulfur content (%) in shale.
- g. Emission records of PM, PM<sub>10</sub> from Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill using calculation methods approved by the Director, West Central Regional Office to verify compliance with the lb/hr and ton/yr emissions limitations in Condition IV. A. 17 and 18.
- h. Hourly and annual records of PM, PM<sub>10</sub>, SO<sub>2</sub>, NOx, CO and VOC and emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") using calculation methods approved by the Director, West Central Regional Office to verify compliance with the lb/hr and ton/yr emissions limitations in Condition IV. A. 19.
- i. Records identifying the relevant, pollutant-specific emission factors used in calculating emissions and the equations used in the calculations.
- j. Daily limestone feeder settings of the DLA, purchase records for limestone used in DLA.
- k. Operation and control device monitoring records for the baghouse which controls Unit #07 (coal processing system).
- 1. Scheduled and unscheduled maintenance, and operator training.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 22

m. Results of all stack tests, visible emission evaluations and performance evaluations.

These records shall be available for inspection by the DEQ and shall be current for the most recent five years.

(9 VAC 5-50-50, 9 VAC 5-80-110, C. 24 of the 12/30/03 minor source permit, as amended 7/5/05, C. 13 of the 7/1/05 minor source permit and General Condition of August 2, 1973 Permit)

- 2. Training The permittee shall maintain records of the required training including a statement of time, place and nature of training provided. The permittee shall have available good written operating procedures and a maintenance schedule for the three (3) kilns. These procedures shall be based on the manufacturer's recommendations, at minimum. All records required by this condition shall be kept on site and made available for inspection by the DEQ. (9 VAC 5-80-110)
- 3. Requirements by Reference: MACT Recordkeeping Requirements Except where this permit is more restrictive, the permittee in accordance with 40 CFR 63 Subpart JJJJJ: National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing shall, beginning at the compliance date according to regulation, record and retain all information necessary to determine that the operation of Unit #06 (Plant 36 Kiln) is in compliance with 40 CFR 63 Subpart JJJJJ.

(9 VAC 5-60-90, 9 VAC 5-60-100, 9 VAC 5-80-110 and 40 CFR 63 Subpart JJJJJ)

## **D.** Testing

- 1. Stack Tests: Continuing Compliance Determination for New/Modified Sources Upon request by the DEQ, the permittee shall conduct additional performance tests to demonstrate compliance with the emission limits and/or control efficiency requirements contained in this permit. The details of the tests shall be arranged with the Director, West Central Regional Office.
  - (9 VAC 5-50-30 G and C. 22 of the 12/30/03 minor source permit, as amended 7/5/05)
- **2. Visible Emissions Evaluation: Continuing Compliance Determination for New/Modified Sources** Upon request by the DEQ, the permittee shall conduct additional visible emission evaluations to demonstrate compliance with the visible emission limits contained in this permit. The details of the tests shall be arranged with the Director, West Central Regional Office. (9 VAC 5-50-30 G, C 11 of the 7/1/05 minor source permit, and C. 23 of the 12/30/03 minor source permit, as amended 7/5/05)
- **3. Testing/Monitoring Ports** The permitted facility shall be constructed so as to allow for emissions testing and monitoring upon reasonable notice at any time, using appropriate methods. This includes constructing the facility such that volumetric flow rates and pollutant

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 23

emission rates can be accurately determined by applicable test methods and providing stack or duct that is free from cyclonic flow. Test ports shall be provided when requested in accordance with the applicable performance specification (reference 40 CFR Part 60, Appendix B). If testing is conducted in addition to the monitoring specified in this permit, the permittee shall use test methods in accordance with procedures approved by the DEQ.

(9 VAC 5-50-30 , C. 14 of the 7/1/05 minor source permit and C. 25 of the 12/30/03 minor source permit, as amended 7/5/05)

- **4. Ports** / **Methods** Upon request from the Department, test ports will be provided at the appropriate locations. If testing is conducted in addition to the monitoring specified in this permit, the permittee shall use test methods in accordance with procedures approved by the DEQ.
  - (9 VAC 5-50-30 and 9 VAC 5-80-110)
- **5. Requirements by Reference: MACT Testing Requirements -** The permittee shall conduct all testing as required in 40 CFR 63 Subpart JJJJJ: *National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing (effective compliance date of May 16, 2006).* This regulation is applicable to Unit #06 (Plant 36 Kiln). (9 VAC 5-60-90, 9 VAC 5-60-100, 9 VAC 5-80-110 and 40 CFR 63 Subpart JJJJJ)

#### E. Reporting

- **1. Initial Notifications** The permittee shall furnish written notification to the Director, West Central Regional Office:
  - a. The actual date on which modification of Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill commenced within 30 days after such date.
  - b. The anticipated start-up date of the Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill postmarked not more than 60 days nor less than 30 days prior to such date.
  - c. The actual start-up date of the modified Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill within 15 days after such date.
  - d. The anticipated date of performance tests of Unit #01-02 the Steele Hammermill-Model 36-24 A and Unit #01-03 the #1 Cage Mill postmarked at least 30 days prior to such date.

Copies of the written notification referenced in items a through d above are to be sent to:

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 24

Associate Director
Office of Air Enforcement (3AP10)
U.S. Environmental Protection Agency
Region III
1650 Arch Street
Philadelphia, PA 19103-2029

(9 VAC 5-50-50, VAC 5-50-400, 9 VAC 5-50-410 and C. 15 of the July 1, 2005 minor NSR permit)

2. Requirements by Reference: MACT Reporting Requirements - Except where this permit is more restrictive, the permittee in accordance with 40 CFR 63 Subpart JJJJJ: National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing shall comply with all applicable reporting requirements of 40 CFR 63 Subpart JJJJJ by the compliance date according to regulation. This requirement is applicable to Unit # 06 (Plant 36 Kiln).

(9 VAC 5-60-90, 9 VAC 5-60-100, 9 VAC 5-80-110 and 40 CFR 63 Subpart JJJJJ)

Further reporting requirements for this section are satisfied by the record keeping requirements in this section and by the General Permit Conditions in the Facility-Wide and General Requirements section.

#### V. Facility Wide Conditions

#### A. Limitations

- 1. Fugitive Dust Unless otherwise specified, dust emission controls shall include the following or equivalent as a minimum:
  - a. Dust from drills, shot piles, material handling, screens, crushers, load-outs and traffic areas shall be controlled by wet suppression or equivalent as approved by the DEQ. There shall be no exemption from this requirement due to cold weather. The wet suppression spray systems shall be operated at optimum design.
    - b. All material being stockpiled shall be kept moist to control dust during storage and handling or covered at all times to minimize emissions.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 25

- c. Haul roads shall be controlled by wet suppression.
- d. Reasonable precautions shall be taken to prevent deposition of dirt on public roads and subsequent dust emissions. Dirt spilled or tracked onto paved surfaced shall be promptly removed to prevent particulate matter from becoming airborne.
- (9 VAC 5-80-10 H, 9 VAC 5-50-90, 9 VAC 5-80-110, Condition 4 of the 7/1/05 minor source permit, C. 7 of the 12/30/03 minor source permit, as amended 7/5/05 and General Condition August 2, 1973 Permit)
- 2. Violation of Ambient Air Quality Standard The permittee shall, upon request of the DEQ, reduce the level of operation or shut down a facility, as necessary to avoid violating any primary ambient air quality standard and shall not return to normal operation until such time as the ambient air quality standard will not be violated.
  - (9 VAC 5-20-180 I, 9 VAC 5-80-110, Condition 31 of the 7/1/05 minor source permit, C. 20 of the 12/30/03 minor source permit, as amended 7/5/05)

#### **B.** Monitoring

1. Visible Emissions - Each emissions unit with a visible emissions requirement in this permit shall be observed visually at least once each calendar week in which the emissions unit operates. The visual observations shall be conducted using 40 CFR 60 Appendix A Method 22 techniques (condensed water vapor/steam is not a visible emission) for at least a brief time to only identify the presence of visible emissions. Each emissions unit in the observation having visible emissions shall be evaluated by conducting a 40 CFR 60 Appendix A Method 9 visible emissions evaluation (VEE) for at least six (6) minutes, unless corrective action is taken that achieves no visible emissions. 40 CFR 60 Appendix A Method 9 requires the observer to have a Method 9 certification that is current at the time of the VEE. If any of these six (6) minute VEE averages exceed the unit's opacity limitation, a VEE shall be conducted on these emissions for at least 3 six minute periods (at least 18 minutes). All visible emission observations, VEE results, and corrective actions taken shall be recorded. (9 VAC 5-80-110 E)

# C. Record keeping

- 1. Maintenance/Operating Procedures In order to minimize the duration and frequency of excess emissions due to malfunctions of process equipment or air pollution control equipment, the permittee shall:
  - a. Develop a maintenance schedule and maintain records of all scheduled and non-scheduled maintenance. These records shall be maintained on site for a period of five (5) years and shall be made available to DEQ personnel upon request.

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 26

- b. Maintain an inventory of spare parts that are needed to minimize the duration of air pollution control equipment breakdowns.
- c. Have available written operating procedures for equipment. Those procedures shall be based on the manufacturer's recommendations, at a minimum.
- d. Train operators in the proper operation of all such equipment and familiarize the operators with the written operating procedures. The permittee shall maintain records or the training provided including the names of trainees, the date of training and the nature of the training.
   (9 VAC 5-80-110, C. 32 of the 12/30/03 minor source permit, as amended 7/5/05, C. 21 of the 7/1/05 minor source permit and C. 9 of the 1/4/99 minor source permit as amended 9/25/01)
- **2. Monitoring Information** All records of monitoring information maintained to demonstrate compliance with the terms and conditions of this permit shall contain, where applicable, the following:
  - a. The date, place as defined in the permit, and time of sampling or measurements.
  - b. The date(s) analyses were performed.
  - c. The company or entity that performed the analyses.
  - d. The analytical techniques or methods used.
  - e. The results of such analyses.
  - f. The operating conditions existing at the time of sampling or measurement.

(9 VAC 5-80-110 F)

#### D. Testing

Testing requirements have been addressed in individual source category sections of this permit as well as in Section IX - General Conditions.

#### E. Reporting

1. Notification for Control Equipment Maintenance - The permittee shall furnish notification to the Director, West Central Regional Office of the intention to shut down or bypass, or both, air pollution control equipment for necessary scheduled maintenance, which results in excess emissions for more than one hour, at least 24 hours prior to the shutdown. The notification shall include, but is not limited to, the following information:

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 27

- a. Identification of the air pollution control equipment to be taken out of service, as well as its location, and registration number;
- b. The expected length of time that the air pollution control equipment will be out of service;
- c. The nature and quantity of emissions of air pollutants likely to occur during the shutdown period;
- d. Measures that will be taken to minimize the length of the shutdown or to negate the effect of the outage.

(9 VAC 5-20-180 B, 9 VAC 5-80-110, C. 29 of the 12/30/03 minor source permit, as amended 7/5/05, C. 18 of the 7/1/05 minor source permit)

2. Notification for Facility or Control Equipment Malfunction - The permittee shall furnish notification to the Director, West Central Regional Office of malfunctions of the affected facility or related air pollution control equipment that may cause excess emissions for more than one hour, by facsimile transmission, telephone or telegraph. Such notification shall be made as soon as practicable but no later than four daytime business hours after the malfunction is discovered. The permittee shall provide a written statement giving all pertinent facts, including the estimated duration of the breakdown, within two weeks of discovery of the malfunction. When the condition causing the failure or malfunction has been corrected and the equipment is again in operation, the permittee shall notify the West Central Regional Office in writing. (9 VAC 5-20-180 C, 9 VAC 5-80-110, C. 30 of the 12/30/03 minor source permit, as amended 7/5/05, C. 19 of the 7/1/05 minor source permit and C. 8 of the 1/4/99 minor source permit as amended 9/25/01)

General plantwide reporting conditions are contained in Section IX - General Conditions.

#### VI. Insignificant Emission Units

The following emission units at the facility are identified in the application as insignificant emission units under 9 VAC 5-80-720:

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 28

Emission Unit No.	Emission Unit Description	Citation	Pollutant(s) Emitted (5-80-720 B)	Rated Capacity (5-80-720 C)
07	Texture Sand Processing	5-80-720 B	$PM_{10}$	5 ton/hr
08	35 Kiln Car Vacuum Cleaner	5-80-720 B	$PM_{10}$	N/A
09	36 Kiln Car Vacuum Cleaner	5-80-720 B	PM <sub>10</sub>	N/A
10	Oil (Lubricating) Tank	5-80-720 B	VOC	18,000 Gallon
11	Diesel Fuel Tank	5-80-720 B	VOC	2,000 Gallon
12	Sand Storage Silo	5-80-720 B	$PM_{10}$	100 Ton Capacity.

These emission units are presumed to be in compliance with all requirements of the federal Clean Air Act as may apply. Based on this presumption, no monitoring, record keeping, or reporting shall be required for these emission units in accordance with 9 VAC 5-80-110.

# VII. Compliance Plan

This facility is currently in compliance with all current requirements.

# VIII. Permit Shield & Inapplicable Requirements

Compliance with the provisions of this permit shall be deemed compliant with all applicable requirements in effect as of the permit issuance date as identified in this permit. This permit shield covers only those applicable requirements covered by terms and conditions in this permit and the following requirements that have been specifically identified as being not applicable to this permitted facility:

Citation	Title of Citation	Description of applicability
40 CFR 60 Subpart UUU (40 CFR 60.730 through 60.737)	Standards of Performance for Calciners and Dryers in Mineral Industries	40 CFR 60.730 (c) definitions: applies to facilities constructed, modified or reconstructed after April 23, 1986. This subpart does not apply to General Shale Brick, Inc. Tunnel kilns generally are not subject to this Subpart.

Nothing in this permit shield shall alter the provisions of § 303 of the federal Clean Air Act, including the authority of the administrator under that section, the liability of the owner for any violation of applicable requirements prior to or at the time of permit issuance, or the ability to obtain information by the administrator pursuant to § 114 of the federal Clean Air Act, (ii) the Board pursuant to § 10.1-1314

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 29

or § 10.1-1315 of the Virginia Air Pollution Control Law or (iii) the Department pursuant to § 10.1-1307.3 of the Virginia Air Pollution Control Law. (9 VAC 5-80-140)

#### IX. General Conditions

#### A. Federal Enforceability

All terms and conditions in this permit are enforceable by the administrator and citizens under the federal Clean Air Act, except those that have been designated as only state-enforceable. (9 VAC 5-80-110 N)

#### **B.** Permit Expiration

This permit shall become invalid five years from the date of issuance. The permittee shall submit an application for renewal of this permit no earlier than 18 months and no later than six months prior to the date of expiration of this permit. Upon receipt of a complete and timely application for renewal, this source may continue to operate subject to final action by the DEQ on the renewal application. (9 VAC 5-80-110 D and 9 VAC 5-80-80 F)

#### C. Record keeping and Reporting

- 1. All records of monitoring information maintained to demonstrate compliance with the terms and conditions of this permit shall contain, where applicable, the following:
  - a. The date, place as defined in the permit, and time of sampling or measurements.
  - b. The date(s) analyses were performed.
  - c. The company or entity that performed the analyses.
  - d. The analytical techniques or methods used.
  - e. The results of such analyses.
  - f. The operating conditions existing at the time of sampling or measurement.

(9 VAC 5-80-110 F)

2. Records of all monitoring data and support information shall be retained for at least five years from the date of the monitoring sample, measurement, report, or application. Support

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 30

information includes all calibration and maintenance records and all original strip-chart recordings for continuous monitoring instrumentation, and copies of all reports required by the permit. (9 VAC 5-80-110 F)

- 3. The permittee shall submit the results of monitoring contained in any applicable requirement to DEQ no later than March 1 and September 1 of each calendar year. This report must be signed by a responsible official, consistent with 9 VAC 5-80-80 G, and shall include:
  - a. The time period included in the report. The time periods to be addressed are January 1 to June 30 and July 1 to December 31.
  - b. All deviations from permit requirements. For purposes of this permit, deviations include, but are not limited to:
    - (1) exceedance of emissions limitations or operational restrictions;
    - (2) excursions from control device operating parameter requirements, as documented by continuous emission monitoring, periodic monitoring, or compliance assurance monitoring which indicates an exceedance of emission limitations or operational restrictions; or
    - (3) failure to meet monitoring, record-keeping, or reporting requirements contained in this permit.

(9 VAC 5-80-110 F)

- c. For each opacity limit exceedance or malfunction as prescribed by 40 CFR 60 Subpart OOO, the report shall include for each period of excess emissions the commencement and completion dates and times, and the magnitude of excess emissions. Specifically identify each period of excess emissions that occurs during startups, shutdowns, malfunctions, and the cause of any malfunction (if known) and the corrective action and preventative measures taken.
- d. The weekly records required for the visible emissions observations utilizing 40 CFR 60 Appendix A, Method 22 techniques shall consist of a written log of dates, times, sources, and result of each visible emission observation, as well as a records of the person or persons performing the periodic observations. These records shall be retained on site for the most recent five (5) year period and made available to the DEQ upon request.
- e. Report recipients: The semi-annual reports required by this Title V operating permit shall be sent to the Director, West Central Regional Office. The reports additionally required by 40 CFR 60.676 et seq. NSPS Subpart OOO for the hammermill and No. 1 Cage Mill shall be

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 31

sent to the Director, West Central Regional Office, and unless directed otherwise, to EPA at the following address:

Chief Air Enforcement Branch (3AP13) U. S. Environmental Protection Agency Region III 1650 Arch Street Philadelphia, PA 19103

(9 VAC 5-80-110 F, Condition 13 of March 16, 1994 Permit, 9 VAC 5-50-360, 9VAC 5-50-50, 9 VAC 5-50-410, 40 CFR 60.676)

## **D.** Annual Compliance Certification

Exclusive of any reporting required to assure compliance with the terms and conditions of this permit or as part of a schedule of compliance contained in this permit, the permittee shall submit to EPA and DEQ no later than March 1 each calendar year a certification of compliance with all terms and conditions of this permit including emission limitation standards or work practices. The compliance certification shall comply with such additional requirements that may be specified pursuant to §114(a)(3) and §504(b) of the federal Clean Air Act. This certification shall be signed by a responsible official, consistent with 9 VAC 5-80-80 G, and shall include:

- 1. The time period included in the certification. The time period to be addressed is January 1 to December 31.
- 2. A description of the means for assessing or monitoring the compliance of the source with its emissions limitations, standards, and work practices.
- 3. The identification of each term or condition of the permit that is the basis of the certification.
- 4. The compliance status.
- 5. Whether compliance was continuous or intermittent, and if not continuous, documentation of each incident of non-compliance.
- 6. Consistent with subsection 9 VAC 5-80-110 E, the method or methods used for determining the compliance status of the source at the time of certification and over the reporting period.
- 7. Such other facts as the Board may require to determine the compliance status of the source.

One copy of the annual compliance certification shall be sent to EPA at the following address:

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 32

Clean Air Act Title V Compliance Certification (3AP00) U.S. Environmental Protection Agency, Region III 1650 Arch Street Philadelphia, PA 19103-2029.

(9 VAC 5-80-110 K.5)

#### E. Permit Deviation Reporting

The permittee shall report by the next business day any deviations from permit requirements or any excess emissions, including those attributable to upset conditions as defined in this permit, the probable cause of such deviations, and any corrective actions or preventive measures taken. (9 VAC 5-80-110 F.2)

## F. Failure/Malfunction Reporting

If, for any reason, the affected facilities or related air pollution control equipment fails or malfunctions and may cause excess emissions for more than one hour, the owner shall notify the Director, West Central Regional Office, within four (4) daytime business hours of the occurrence. In addition, the owner shall provide a written statement, within 14 days, explaining the problem, corrective action taken, and the estimated duration of the breakdown/shutdown. (9 VAC 5-80-250)

#### G. Severability

The terms of this permit are severable. If any condition, requirement or portion of the permit is held invalid or inapplicable under any circumstance, such invalidity or inapplicability shall not affect or impair the remaining conditions, requirements, or portions of the permit. (9 VAC 5-80-110 G.1)

#### H. Duty to Comply

The permittee shall comply with all terms and conditions of this permit. Any permit noncompliance constitutes a violation of the federal Clean Air Act or the Virginia Air Pollution Control Law or both and is grounds for enforcement action; for permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application.

(9 VAC 5-80-110 G.2)

#### I. Need to Halt or Reduce Activity not a Defense

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 33

It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.

(9 VAC 5-80-110 G.3)

#### J. Permit Action for Cause

- 1. This permit may be modified, revoked, reopened, and reissued, or terminated for cause as specified in 9 VAC 5-80-110 L, 9 VAC 5-80-240 and 9 VAC 5-80-260. The filing of a request by the permittee for a permit modification, revocation and reissuance, or termination, or of a notification of planned changes or anticipated noncompliance does not stay any permit condition. (9 VAC 5-80-110 G.4)
- 2. Such changes that may require a permit modification and/or revisions include, but are not limited to, the following:
  - a. Erection, fabrication, installation, addition, or modification of an emissions unit (which is the source, or part of it, which emits or has the potential to emit any regulated air pollutant), or of a source, where there is, or there is the potential of, a resulting emissions increase;
  - b. Reconstruction or replacement of any emissions unit or components thereof such that its capital cost exceeds 50% of the cost of a whole new unit;
  - c. Any change at a source which causes emission of a pollutant not previously emitted, an increase in emissions, production, throughput, hours of operation, or fuel use greater than those allowed by the permit, or by 9 VAC 5-80-11, unless such an increase is authorized by an emission cap; or any change at a source which causes an increase in emissions resulting from a reduction in control efficiency, unless such an increase is authorized by an emissions cap;
  - d. Any reduction of the height of a stack or of a point of emissions, or the addition of any obstruction which hinders the vertical motion of exhaust;
  - e. Any change at the source which affects its compliance with conditions in this permit, including conditions relating to monitoring, record keeping, and reporting;
  - f. Addition of an emissions unit which qualifies as insignificant by emissions rate (9 VAC 5-80-720 B) or by size or production rate (9 VAC 5-80-720 C);
  - g. Any change in insignificant activities, as defined by 9 VAC 5-80-90 D.1.a(1) and by 9 VAC 5-80-720 B and 9 VAC 5-80-720 C.

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 34

(9 VAC 5-80-110 G, 9 VAC 5-80-110 J, 9 VAC 5-80-240, and 9 VAC 5-80-260)

#### K. Property Rights

The permit does not convey any property rights of any sort, or any exclusive privilege. (9 VAC 5-80-110 G.5)

#### L. Duty to Submit Information

- 1. The permittee shall furnish to the board, within a reasonable time, any information that the board may request in writing to determine whether cause exists for modifying, revoking and reissuing, or terminating the permit or to determine compliance with the permit. Upon request, the permittee shall also furnish to the board copies of records required to be kept by the permit and, for information claimed to be confidential, the permittee shall furnish such records to the board along with a claim of confidentiality.
  - (9 VAC 5-80-110 G.6)
- 2. Any document (including reports) required in a permit condition to be submitted to the board shall contain a certification by a responsible official that meets the requirements of 9 VAC 5-80-80 G.

(9 VAC 5-80-110 K.1)

#### M. Duty to Pay Permit Fees

The owner of any source for which a permit under 9 VAC 5-80-50 through 9 VAC 5-80-305 was issued shall pay permit fees consistent with the requirements of 9 VAC 5-80-310 through 9 VAC 5-80-355.

(9 VAC 5-80-110 H)

#### N. Fugitive Dust Emission Standards

During the operation of a stationary source or any other building, structure, facility or installation, no owner or other person shall cause or permit any materials or property to be handled, transported, stored, used, constructed, altered, repaired, or demolished without taking reasonable precautions to prevent particulate matter from becoming airborne. Such reasonable precautions may include, but are not limited, to the following:

- 1. Use, where possible, of water or chemicals for control of dust in the demolition of existing buildings or structures, construction operations, the grading of roads, or the clearing of land;
- 2. Application of asphalt, water, or suitable chemicals on dirt roads, materials stockpiles, and other surfaces which may create airborne dust; the paving of roadways and the maintaining of them in a clean condition;

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 35

- 3. Installation and use of hoods, fans, and fabric filters to enclose and vent the handling of dusty material. Adequate containment methods shall be employed during sandblasting or other similar operations;
- 4. Open equipment for conveying or transporting material likely to create objectionable air pollution when airborne shall be covered or treated in an equally effective manner at all times when in motion; and
- 5. The prompt removal of spilled or traced dirt or other materials from paved streets and of dried sediments resulting from soil erosion.

(9 VAC 5-40-90 or 9 VAC 5-50-90)

#### O. Startup, Shutdown, and Malfunction

At all times, including periods of startup, shutdown, soot blowing, and malfunction, owners shall, to the extent practicable, maintain and operate any affected facility including associated air pollution control equipment in a manner consistent with air pollution control practices for minimizing emissions. Determination of whether acceptable operating and maintenance procedures are being used will be based on information available to the board, which may include, but is not limited to, monitoring results, opacity observations, review of operating and maintenance procedures, and inspection of the source.

(9 VAC 5-50-20)

#### P. Alternative Operating Scenarios

Contemporaneously with making a change between reasonably anticipated operating scenarios identified in this permit, the permittee shall record in a log at the permitted facility a record of the scenario under which it is operating. The permit shield described in 9 VAC 5-80-140 shall extend to all terms and conditions under each such operating scenario. The terms and conditions of each such alternative scenario shall meet all applicable requirements including the requirements of 9 VAC 5 Chapter 80 Article 1.

(9 VAC 5-80-110 J)

#### Q. Inspection and Entry Requirements

The permittee shall allow DEQ, upon presentation of credentials and other documents as may be required by law, to perform the following:

- 1. Enter upon the premises where the source is located or emissions-related activity is conducted, or where records must be kept under the terms and conditions of the permit.
- 2. Have access to and copy, at reasonable times, any records that must be kept under the terms and conditions of the permit.

Title V Permit Number: VA-20447

## Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 36

- 3. Inspect at reasonable times any facilities, equipment (including monitoring and air pollution control equipment), practices, or operations regulated or required under the permit.
- 4. Sample or monitor at reasonable times substances or parameters for the purpose of assuring compliance with the permit or applicable requirements.

(9 VAC 5-80-110 K.2)

#### **R.** Reopening For Cause

The permit shall be reopened by the board if additional federal requirements become applicable to a major source with a remaining permit term of three or more years. Such a reopening shall be completed not later than 18 months after promulgation of the applicable requirement. No such reopening is required if the effective date of the requirement is later than the date on which the permit is due to expire, unless the original permit or any of its terms and conditions has been extended pursuant to 9 VAC 5-80-80 F.

- 1. The permit shall be reopened if the board or the administrator determines that the permit contains a material mistake or that inaccurate statements were made in establishing the emissions standards or other terms or conditions of the permit.
- 2. The permit shall be reopened if the administrator or the board determines that the permit must be revised or revoked to assure compliance with the applicable requirements.
- 3. The permit shall not be reopened by the board if additional applicable state requirements become applicable to a major source prior to the expiration date established under 9 VAC 5-80-110 D.

(9 VAC 5-80-110 L)

#### S. Permit Availability

Within five days after receipt of the issued permit, the permittee shall maintain the permit on the premises for which the permit has been issued and shall make the permit immediately available to DEQ upon request.

(9 VAC 5-80-150 E)

#### T. Transfer of Permits

1. No person shall transfer a permit from one location to another, unless authorized under 9 VAC 5-

General Shale Brick, Inc.

Title V Permit Number: VA-20447

# Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 37

80-130, or from one piece of equipment to another. (9 VAC 5-80-160)

2. In the case of a transfer of ownership of a stationary source, the new owner shall comply with any current permit issued to the previous owner. The new owner shall notify the board of the change in ownership within 30 days of the transfer and shall comply with the requirements of 9 VAC 5-80-200.

(9 VAC 5-80-160)

3. In the case of a name change of a stationary source, the owner shall comply with any current permit issued under the previous source name. The owner shall notify the board of the change in source name within 30 days of the name change and shall comply with the requirements of 9 VAC 5-80-200.

(9 VAC 5-80-160)

### U. Malfunction as an Affirmative Defense

- 1. A malfunction constitutes an affirmative defense to an action brought for noncompliance with technology-based emission limitations if the conditions of paragraph 2 are met.
- 2. The affirmative defense of malfunction shall be demonstrated by the permittee through properly signed, contemporaneous operating logs, or other relevant evidence that show the following:
  - a. A malfunction occurred and the permittee can identify the cause or causes of the malfunction.
  - b. The permitted facility was at the time being properly operated.
  - c. During the period of the malfunction the permittee took all reasonable steps to minimize levels of emissions that exceeded the emission standards, or other requirements in the permit.
  - d. For malfunctions that occurred for one hour or more, the permittee submitted to the board by the deadlines described in Failure/Malfunction Reporting above, a notice and written statement containing a description of the malfunction, any steps taken to mitigate emissions, and corrective actions taken. The notice fulfills the requirement of 9 VAC 5-80-110 F.2. b to report promptly deviations from permit requirements.
- 3. In any enforcement proceeding, the permittee seeking to establish the occurrence of a malfunction shall have the burden of proof. The provisions of this section are in addition to any malfunction, emergency or upset provision contained in any requirement applicable to the source. (9 VAC 5-80-250)

Title V Permit Number: VA-20447

Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 38

### V. Permit Revocation or Termination for Cause

A permit may be revoked or terminated prior to its expiration date if the owner knowingly makes material misstatements in the permit application or any amendments thereto or if the permittee violates, fails, neglects or refuses to comply with the terms or conditions of the permit, any applicable requirements, or the applicable provisions of 9 VAC 5 Chapter 80 Article 1. The board may suspend, under such conditions and for such period of time as the board may prescribe any permit for any of the grounds for revocation or termination or for any other violations of these regulations. (9 VAC 5-80-260)

### W. Duty to Supplement or Correct Application

Any applicant who fails to submit any relevant facts or who has submitted incorrect information in a permit application shall, upon becoming aware of such failure or incorrect submittal, promptly submit such supplementary facts or corrections. An applicant shall also provide additional information as necessary to address any requirements that become applicable to the source after the date a complete application was filed but prior to release of a draft permit. (9 VAC 5-80-80 E)

### X. Stratospheric Ozone Protection

If the permittee handles or emits one or more Class I or II substance subject to a standard promulgated under or established by Title VI (Stratospheric Ozone Protection) of the federal Clean Air Act, the permittee shall comply with all applicable sections of 40 CFR Part 82, Subparts A to F. (40 CFR Part 82, Subparts A - F)

#### Y. Accidental Release Prevention

If the permittee has more, or will have more than a threshold quantity of a regulated substance in a process, as determined under 40 CFR 68.115, the permittee shall comply with the requirements of 40 CFR Part 68.

(40 CFR Part 68)

# Z. Changes to Permits for Emissions Trading - Not Applicable

# **AA. Emissions Trading - Not Applicable**

# X. State-Only Enforceable Requirements

The following terms and conditions are included in this permit to implement the requirements of 9 VAC 5-60-300 et seq. and are not required under the federal Clean Air Act or under any of its applicable federal requirements. Neither their inclusion in the referenced minor new/modified source review permit nor any subsequent public comment period make these terms federally enforceable.

General Shale Brick, Inc.

Title V Permit Number: VA-20447

# Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 39

#### A. Limitations

- 1. Emission Controls Hydrogen fluoride emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") shall be controlled by a single Ohlmann type dry lime adsorber (DLA). The shared dry lime adsorber shall be provided with adequate access for inspection and shall be in operation when one/both of the associated kiln(s) is/are operating. (9 VAC 5-170-160, VAC 5-80-1120 F and State-Only C. 1 of the 12/30/03 minor source permit, as amended 7/5/05)
- 2. Control Efficiency The dry lime adsorber (DLA) controlling emissions from Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") shall demonstrate a control efficiency by stack test for hydrogen fluoride of no less then 90 percent (90%). Subsequently to the initial stack test, this permit may be modified to require the DLA to meet or exceed the control efficiencies established by initial stack test, using similar fuels, operating practices, and lime. (9 VAC 5-170-160, 9 VAC 5-80-1120 F and State-Only C. 2 of the 12/30/03 minor source permit, as amended 7/5/05)
- **3. Emission Limits: Plant 35** Total phosphorous emissions from the operation of Plant 35 kilns Unit # 04 (Kiln 35 "A") and Unit # 05 (Kiln 35 "B") shall not exceed the limits specified below:

Phosphorous 0.01 lb/hr 0.42 tons/yr

Annual emissions calculated monthly as the sum of each consecutive 12-month period.

These emissions are derived from the estimated overall emission contribution from operating limits. Exceedance of the operating limits shall be considered credible evidence of the exceedance of emission limits. Compliance with these emission limits may be determined as stated in Condition numbers IV. A. 1, 2, 4, 5, 7, 19 and B. 1, 2, 5 and IV.D. 1.

(9 VAC 5-170-160, 9 VAC 5-60-320, 9 VAC 5-80-1120 F, 9 VAC 5-80-1180C F and State-Only C. 3 of the 12/30/03 minor source permit, as amended 7/5/05)

## **B.** Monitoring

Monitoring requirements for this section are satisfied by the monitoring requirements in the New/Modified Source Section (Condition IV. B.) and by the General Permit Conditions in the Facility-Wide and General Requirements section.

General Shale Brick, Inc.

Title V Permit Number: VA-20447

# Issued June 14, 2001, Amended October 4, 2001, Modified March 1, 2005 Modified September 20, 2005

Page 40

## C. Recordkeeping

- 1. On Site Records The permittee shall maintain records of emission data and operating parameters as necessary to demonstrate compliance with this permit. The content and format of such records shall be arranged with the Director, West Central Regional Office. These records shall include, but are not limited to:
  - a. Records identifying the relevant phosphorous and HF emission factors used in calculating emissions and the equations used in the calculations.
  - b. Results of stack tests for hydrogen fluoride and air dispersion modeling for phosphorous emissions.

(9 VAC 5-170-160, 9 VAC 5-60-360, 9 VAC 5-80-1120 F and State-Only C. 6 of the 12/30/03 minor source permit as amended 7/5/05)

### D. Testing

Testing requirements for this section have been satisfied and streamlined out from the Title V Permit. Testing information is included in the accompanying Statement of Basis.


## E. Reporting

Reporting requirements for this section have been satisfied and streamlined out from the Title V Permit. Reporting information is included in the accompanying Statement of Basis.

# Attachment A

40 CFR 63 Subpart JJJJJ - National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing

40 CFR 60 Subpart OOO – New Source Performance Standards for Non-metallic Mineral Processing Plants



Friday, May 16, 2003

# Part II

# **Environmental Protection Agency**

40 CFR Part 63

National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing; and National Emission Standards for Hazardous Air Pollutants for Clay Ceramics Manufacturing; Final Rule

# ENVIRONMENTAL PROTECTION AGENCY

#### 40 CFR Part 63

[OAR-2002-0054 and OAR-2002-0055, FRL-7459-9]

RIN 2060-A167 and 2060-A168

National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing; and National Emission Standards for Hazardous Air Pollutants for Clay Ceramics Manufacturing

AGENCY: Environmental Protection Agency (EPA), ACTION: Final rule.

**SUMMARY:** This action promulgates national emission standards for hazardous air pollutants (NESHAP) for new and existing sources at brick and structural clay products (BSCP) manufacturing facilities and NESHAP for new and existing sources at clay ceramics manufacturing facilities. This action will implement section 112(d) of the Clean Air Act (CAA) by requiring major sources to meet hazardous air pollutant (HAP) emission standards reflecting the application of the maximum achievable control technology (MACT). The two subparts will protect air quality and promote the public health by reducing emissions of several of the HAP listed in section 112(b)(1) of the CAA. The rules will reduce HAP emissions from existing sources by 2,300 tons per year nationwide, with hydrogen fluoride (HF) and bydrogen chloride (HCl) accounting for 2,290 tons per year 199.6 percent) of the total HAP emissions

reductions from existing sources. The associated metals (antimony, arsenic, beryllium, cadmium, chromium, cobalt, mercury, manganese, nickel, lead, and selenium) reductions from existing sources account for approximately 6 tons per year nationwide (0.4 percent). Exposure to these substances has been demonstrated to cause adverse health effects such as irritation of the lung, skin, and mucus membranes, effects on the central nervous system, and kidney damage. The EPA has classified three of the HAP as known human carcinogens, four as probable human carcinogens, and one as a possible human carcinogen. We estimate that the two subparts will reduce nationwide emissions of HAP from these facilities by approximately 2,100 megagrams per year (Mg/yr)(2.300 tons per year (tpy)). a reduction of approximately 35 percent from the current level of emissions.

**EFFECTIVE DATE:** The final rule is effective May 16, 2003.

ADDRESSES: Docket No. OAR-2002-0054 contains supporting documentation used in developing the final BSCP rule. Docket No. OAR-2002-0055 contains supporting documentation used in developing the final clay ceramics rule. The dockets are located at the Air and Radiation Docket and Information Center in the EPA Docket Center, (EPA/DC) EPA West, Room B102, 1301 Constitution Avenue, NW., Washington, DC 20460, telephone (202) 566-1744. The dockets are available for public inspection from 8:30 a.m. to 4:30 p.m., Monday through Friday, excluding Federal holidays.

FOR FURTHER INFORMATION CONTACT: For further information concerning

applicability and rule determinations, contact the appropriate State or local agency representative. If no State or local representative is available, contact the EPA Regional Office staff listed in 40 CFR 63.13. For information concerning the analyses performed in developing the final rules, contact Ms. Mary Johnson, Combustion Group. Emission Standards Division (MC—C439—01), U.S. EPA, Research Triangle Park, North Carolina 27711, telephone number (919) 541—5025, e-mail address: johnson.mary@epa.gov.

SUPPLEMENTARY INFORMATION: Regulated Entities. Entities potentially regulated by this action are those industrial facilities that manufacture BSCP and clay ceramics. Brick and structural clay products manufacturing is classified under Standard Industrial Classification (SIC) codes 3251, Brick and Structural Clay Tile: 3253, Ceramic Wall and Floor Tile; and 3259, Other Structural Clay Products. The North American Industry Classification System (NAICS) codes for BSCP manufacturing are 327121, Brick and Structural Clay Tile; 327122, Ceramic Wall and Floor Tile Manufacturing, and 327123, Other Structural Clay Products. Clay ceramics manufacturing is classified under SIC codes 3253, Ceramic Wall and Floor Tile; and 3261, Vitreous Plumbing Fixtures (Sanitaryware). The NAICS codes for clay ceramics manufacturing are 327122, Ceramic Wall and Floor Tile Manufacturing; and 327111. Vitreous China Plumbing Fixture and China and Earthenware Bathroom Accessories Manufacturing, Regulated categories and entities are shown in Table 1 of this preamble.

TABLE 1.—REGULATED CATEGORIES AND ENTITIES

Category	SIC	NAICS	Examples of potentially regulated entities
IndustrialIndustrial			Brick and structural clay tile manufacturing facilities (BSCP NESHAP)  Ceramic wall and floor tile manufacturing facilities (Clay Ceramics NESHAP) and extruded tile manufacturing facilities (BSCP NESHAP).
IndustrialIndustrial	3259 3261	327123 327111	Other structural clay products manufacturing facilities (BSCP NESHAP) Vitreous plumbing fixtures (sanitaryware) manufacturing facilities (Clay Ceramics NESHAP).

This table is not intended to be exhaustive, but rather provides a guide for readers regarding entities likely to be regulated by this action. To determine whether your facility is regulated by this action, you should examine the applicability criteria in § 63.8385 of today's final BSCP rule and § 63.8535 of today's final clay ceramics rule. If you have any questions regarding the applicability of this action to a particular entity, consult the person

# fisted in the preceding FOR FURTHER INFORMATION CONTACT SECTION.

Electronic Docket (E-Docket). The EPA has established official public dockets for this action under Docket ID No. OAR-2002-0054 for the final BSCP rate and Docket ID No. OAR-2002-0055 for the final clay coronics rule. The official public dockets are the collection of materials that is available for public viewing at the EPA Docket Center (Air Docket), EPA West, Room B102, 130)

Constitution Avenue, NW., Washington, DC 20460. The Docket Center is open from 8:30 a.m. to 4:30 p.m., Monday through Friday, excluding legal holidays. The telephone number for the Reading Room is (202) 566–1744, and the telephone number for the Air Docket is (202) 566–1742. A reasonable fee may be charged for copying docket materials.

Electronic Access, Electronic versions of the public dockets are available through EPA's electronic public docket

and comment system, EPA Dockets, You may use EPA Dockets at http:// www.epa.gov/edocket to view public comments, access the indexes of the contents of the official public dockets. and to access those documents in the public dockets that are available electronically. Once in the system, select "search" and key in the appropriate docket identification number. Although not all docket materials may be available electronically, you may still access any of the publicly available docket materials through the docket facility identified in this document.

Worldwide Web (WWW). In addition to being available in the dockets, an electronic copy of today's document also will be available on the WWW. Following the Administrator's signature, a copy of this action will be posted at илии.epa.gov/ttn/oarpg on EPA's Technology Transfer Network (TTN) policy and guidance page for newly proposed or promulgated rules. The TTN provides information and technology exchange in various areas of air pollution control. If more information regarding the TTN is needed, call the TTN HILP line at (919) 541-5384.

Indicial Review. Under section 307(b)(1) of the CAA, judicial review of the final rule is available only by filing a petition for review in the U.S. Court of Appeals for the District of Columbia Circuit by July 15, 2003 Under section 30"(d)(")(B) of the CAA, only an objection to the final rule that was raised with reasonable specificity. during the period for public comment can be raised during judicial review. Moreover, under section 307(b)(2) of the CAA, the requirements established by the final rule may not be challenged. separately in any civil or criminal proceedings brought by EPA to enforce the requirements.

Outline. The information presented in this preamble is organized as follows:

- I Background
  - A. What Is the Source of Authority for Development of NESHAP?
  - E. What Criteria Are Used in the Development of NESHAP?
  - C. How Were the Final Rules Developed?
  - I What Are the Health Effects of Pollutants Emitted From the Brief and Caructural Clay Products Manufacturing and Clay Ceramics Manufacturing Source Categories?
- II Summary of Responser to Major Comments and Changes to the Brick and Supergrad Clay Products Managements Proposed CESHAP
  - er, en follation Control Decice:
  - Leader bourse
- C Existing Source 4450T
- To New Source MAGT

- E. Cost and Economic Impacts
- F. Test Data and Emission Limits
- G. Monitoring Requirements
- H. Startup, Shutdown and Malfunction
- Rist Based Approaches
- III Summary of the Final Brick, and Structural Clay Products Manufacturing NESHAP
  - A. What Source Category Is Regulated by the Final Rule?
  - B. What Are the Affected Sources?
  - C. When Musi I Comply With the Final Rule?
  - D. What Are the Emission Lumits?
  - E. What Are the Operating Limits?
  - F. What Are the Performance Test and Initial Compliance Requirements?
  - G What Are the Continuous Compliance Requirements?
  - H. What Are the Notification. Recordkeeping, and Reporting Requirements?
- IV. Summary of Environmental, Energy, and Economic Impacts for the Final Brick and Structural Clay Products Manufacturing NESHAP
  - A. What Are the Air Quality Impacts?
  - B. What Are the Water and Solid Waste Impacts?
  - C What Are the Energy Impacts?
  - D. Are There any Additional Environmental and Health Impacts?
  - E. What Are the Cost Impacts?
- F What Are the Economic Impacts?
- V. Summary of Responses to Major Comments and Changes to the Clay Ceramics Manufacturing Proposed NESHAP
  - A Affected Source
  - B. Existing Source MACT
  - C. New Source MACT
  - D. Cost and Economic Impacts
  - E Test Data and Emission Limits
  - F. Monitoring Requirements
  - G Starrup, Shutdown, and Malfunction
- VI Summary of the Final Clay Ceramics Manufacturing (FESHAP)
  - A. What Source Category Is Regulated by the Final Rule!
  - E. What Are the Affected Sources?
  - C. When Musi J Compry With the Final Rule?
  - D. What Are the Emission Limits?
  - E. What Are the Operating Limits?
  - F. What Are the Worl: Practice Standards '
  - G. What Are the Performance Test and Initial Compliance Requirements for Source: Sumed to Emission Limits?
  - H. What Are the Initial Compliance Requirements for Sources Subject to a Work fractice Standard?
  - I What Are the Continuous Compliance Requirements for Sources Subject to Emission Limits?
  - What Are the Continuous Compliance Leguments for Courses Subject to a Worl Practice Standard?
  - If What Are the Potentication, Records coping, and Proporting Recomments for Courses Subject to Emission Limits'
  - What was the Institution.
     Recordberping and Leporning
     Requirement, for Souther Subject to a Worl Province Standard.

- VII Summary of Environmental, Energy, and Economic Impacts for the Final Clay Ceramics Manufacturing NESHAP
  - A. What Are the Air Quality Impacts?
  - B What Are the Water and Solid Waste Impacts:
  - C. What Are the Energy Impacts?
  - D Are there any Additional Environmental and Health Impacts?
  - E. What Are the Cost Impacts?
  - F. What Are the Economic Impacts:
- VIII Statutory and Executive Order Reviews
  A. Executive Order 12866, Regulatory
  Planning and Review
  - B Paperworl, Reduction Act
  - C. Regulatory Flexibility Act
  - D. Unfunded Mandates Reform Act
  - E Executive Order 13132, Federalism
  - F. Executive Order 13175. Consultation and Coordination With Indian Tribal Governments
  - G Executive Order 13045, Protection of Children From Environmental Health & Safety Risks
  - H Executive Order 13211, Actions
    Concerning Regulations That
    Significantly Affect Energy Supply,
    Distribution, or Use
  - National Technology Transfer and Advancement Act
  - 1 Congressional Review Act

### 1. Background

A. What Is the Source of Authority for Development of NESHAP?

Section 112 of the CAA requires us to list categories and subcategories of major and area sources of HAP and to establish NESHAP for the listed source categories and subcategories. Clay products manufacturing was listed as a categor, of major sources on the initial source category list published in the Federal Register on July 16, 1992 (57 FR 315761. In the July 22, 2002 Federal Register notice (67 FR 47894) that proposed NESHAP for BSCP manufacturing and clay ceramics manufacturing, the clay products manufacturing source dategory was replaced by the BSCP manufacturing source category and the clay ceramics manufacturing source category. Today's action contains final rules for the two source dategories. Major sources of HAP are those stationary sources or groups of stationary sources that are located within a contiguous area and under common control that emit or have the potential to emit considering controls in the aggregate, 9.07 Mg/vr (10 tpy) or more of any one HAP of 22.66 Mg yr (25 the for more of any combination of HAP Area sources are those stationary nourcer that are not major sources.

F. What Coneria Are Used in the Development of DESHAP?

Section 112 of the CAA requires that we establish NEDHAP for the control of HAP from both new and existing major sources. The CAA requires the NESHAP to reflect the maximum degree of reduction in emissions of HAP that is achievable. This level of control is commonly referred to as MACT.

The MÁCT floor is the minimum control level allowed for NESHAP and is defined under section 112(d)(3) of the CAA. In essence, the MACT floor ensures that the standards are set at a level that assures that all major sources achieve the level of control at least as stringent as that already achieved by the better-controlled and lower-emitting sources in each source category or subcategory. For new sources, the MACT floor cannot be less stringent than the emission control that is achieved in practice by the bestcontrolled similar source. The MACT standards for existing sources can be less stringent than standards for new sources, but they cannot be less stringent than the average emission limitation achieved by the bestperforming 12 percent of existing sources in the category or subcategory for which the Administrator has emissions information (or the bestperforming 5 sources for which the Administrator has or could reasonably obtain emissions information for categories or subcategories with fewer than 30 sources).

In developing MACT, we also consider control options that are more stringent than the floor. We may establish standards more stringent than the floor based on the consideration of cost of achieving the emissions reductions, any health and environmental impacts, and energy

requirements.

#### C. How Were the Final Rules Developed?

We proposed standards for BSCP manufacturing and clay ceramics manufacturing on July 22, 2002 (67 FR 47894). The preamble for the proposed standards described the rationale for the proposed standards. Public comments were solicited at the time of proposal. The public comment period lasted from July 22, 2002 to September 20, 2002. Industry representatives, regulatory agencies, environmental groups, and the general public were given the opportunity to comment on the proposed rules and to provide additional information during the public comment period. We also offered at proposal the opportunity for oral presentation of data, views, or arguments concerning the proposed rules. A public hearing on the proposed BSCP rule was held on August 21, 2002. during which 21 presentations were made. Following the public hearing, we met with representatives of industry and

environmental groups on several occasions.

We received a total of 80 public comment letters on the proposed BSCP rule and 9 public comments letters on the proposed clay ceramics rule.

Comments were submitted by industry trade associations, BSCP and clay ceramics manufacturing companies, State regulatory agencies and their representatives, and environmental groups. Today's final rules reflect our consideration of all of the comments received. Major public comments on the proposed rules, along with our responses to those comments, are summarized in this preamble.

D. What Are the Health Effects of Pollutants Emitted From the Brick and Structural Clay Products Manufacturing and Clay Ceramics Manufacturing Source Categories?

Today's proposed rules protect air quality and promote the public health by reducing emissions of some of the HAP listed in section 112(b)(1) of the CAA. Emissions data collected during development of the proposed rules show that HF, HCl, and small amounts of metals (antimony, arsenic, beryllium, cadmium, chromium, cobalt, mercury, manganese, nickel, lead, and selenium) are emitted from BSCP and clay ceramics manufacturing facilities. Exposure to these HAP is associated with a variety of adverse health effects. These adverse health effects include chronic health disorders (e.g., irritation of the lung, skin, and mucus membranes, effects on the central nervous system, and damage to the kidneys), and acute health disorders (e.g., lung irritation and congestion. alimentary effects such as nausea and vomiting, and effects on the kidney and central nervous system). We have classified three of the HAP as human carcinogens, four as probable human carcinogens, and one as a possible buman carcinogen. We do not know the extent to which the adverse health effects described above occur, or if any adverse effects occur, in the populations surrounding these facilities. However, to the extent the adverse effects do occur, inday's proposed rules would reduce emissions and subsequent exposures. The majority of the emissions reductions from this rule are HF (1900) tons per year nationwide) and HCl (390 tone per year nationwide), white the rule will only reduce emissions of the HAP metals listed below by a small amount (approximately 6 tons nationwide per year).

#### 1. Hydrogen Fluoride

Acute (short-term) inhalation exposure to gaseous HF can cause severe respiratory damage in humans, including severe irritation and pulmonary edema. Chronic (long-term) exposure to fluoride at low levels has a beneficial effect of dental cavity prevention and may also be useful for the treatment of osteoporosis. Exposure to higher levels of fluoride may cause dental fluorosis or mottling, while very high exposures through drinking water or air can result in crippling skeletal fluorosis. One study reported menstrual irregularities in women occupationally exposed to fluoride. We have not classified HF for carcinogenicity.

#### 2. Hydrogen Chloride

Hydrogen chloride, also called hydrochloric acid, is corrosive to the eyes, skin, and mucous membranes. Acute (short-term) inhalation exposure may cause eye, nose, and respiratory tract irritation and inflammation and pulmonary edema in humans. Chronic (long-term) occupational exposure to HCl has been reported to cause gastritis, bronchitis, and dermatitis in workers. Prolonged exposure to low concentrations may also cause dental discoloration and erosion. No information is available on the reproductive or developmental effects of HCl in humans. In rats exposed to HCl by inhalation, altered estrus cycles have been reported in females and increased fetal mortality and decreased fetal weight have been reported in offspring. We have not classified HCl for carcinogenicity.

#### 3. Antimony

Acute (short-term) exposure to autimony by inhalation in humans results in effects on the skin and eyes. Respiratory effects, such as inflammation of the lungs, chronic bronchitis, and chronic emphysema, are the primary effects noted from chronic (long-term) exposure to antimony in humans via inhalation. Human studies are inconclusive regarding antimony exposure and cancer, while animal studies have reported lung tumors in rats exposed to antimony trioxide via inhalation. Effects of oral exposure to antimony are not well-described, but a single study has reported decreased longevity and changes in serum glucose and cholesterol in rats. We have not classified antimony for carcinogenicity.

#### 4. Arsenic

Acute (short-term) high-level inhalation exposure to arsenic dust or tumes has resulted in gastrointestinal effects (nausea, diarrhea, abdominal

pain), and central and peripheral nervous system disorders. Chronic (long-term) inhalation exposure to inorganic arsenic in humans is associated with irritation of the skin and mucous membranes. Human data suggest a relationship between inhalation exposure of women working at or living near metal smelters and an increased risk of reproductive effects. such as spontaneous abortions. lnorganic arsenic exposure in humans by the inhalation route has been shown to be strongly associated with lung cancer, while ingestion of inorganic arsenic in humans has been linked to a form of skin cancer and also to bladder. liver, and lung cancer. We have classified inorganic arsenic as a Group A, human carcinogen.

#### 5. Beryllium

Acute (short-term) inhalation exposure to high levels of beryllium has been observed to cause inflammation of the lungs or acute pneumonitis (reddening and swelling of the lungs) in humans; after exposure ends, these symptoms may be reversible. Chronic (long-term) inhalation exposure of humans to beryllium has been reported to cause chronic beryllium disease (berylliosis), in which granulomatous (noncancerous) lesions develop in the lung. Inhalation exposure to beryllium has been demonstrated to cause lung cancer in rats and monkeys. Human studies are limited, but suggest a causal relationship between beryllium exposure and an increased risk of lung cancer. Oral exposure to beryllium was found to cause stomach lesions in dogs. but effects on humans are not welldescribed. We have classified beryllium as a Group B1, probable buman carculogen when inhaled: data are inadequate to determine whether beryllium i carcinogenic when ingested

#### 6. Gadmium

The acute (short-term) effects of cadmium inhalation in humans consist mainly of effects on the lung, such as nulmonary irritation. Chronic (longterm i inhalation or oral exposure to cadmium leads to a build-up of codinium in the luggers that can cause Ladney disease Caamium lias been snown to be a developmental texticant in animals resulting in letal multormations and other effects, but to conclusive evidence exists in humanis is a association between cadmium. inhabition el posure and an increased till of ling concertiat feet reported it om lainier, studies, but the a studies are inconclusive due to confounding. factoria, unisml studie chave

demonstrated an increase in lung cancer from long-term inhalation exposure to cadmium. We have classified cadmium as a Group B1, probable human carcinogen when inhalad, data are inadequate to determine whether cadmium is carcinogenic when ingested.

#### 7. Chromium

Chromum may be emitted in two forms, trivalent chromium (chromium III) or hexavalent chromium (chromium VI). The respiratory tract is the major target organ for chromium VI toxicity. for acute (short-term) and chronic (longterm) inhalation exposures. Shortness of breath, coughing, and wheezing have been reported from acute exposure to chromium VI, while perforations and ulcerations of the septum, broughitis. decreased pulmonary function. pneumonia, and other respiratory effects have been noted from chronic exposure. Limited human studies suggest that chromium VI inhalation exposure may be associated with complications during pregnancy and childbirth, white animal studies have not reported reproductive effects from inhalation exposure to chromium VI. Human and animal studies have clearly established that inhaled chromium. VI is a carcinogen. resulting in an increased risk of lung cancer. We have classified chromium VI as a Group A, human carcinogen by the unhalation exposure route. Oral exposure of humans to chromium VI has been reported to cause sores in the mouth gastrointestinal effects, and elevated white blood cell counts. Animal studies of oral chromium \7 exposure have reported testicular degeneration and fetal damage in mice. and rats. Chromitum IV is also a potent contact sensitizer producing allergic cermatitis in previously-exposed burnuns. Data are inadequate to determine if chromium VI is carainogenic by oral exposure.

Chromium III is much less toxic than chromium VI. The respiratory tract is also the major target organ for chromium III toxicity, similar to chromium VI. Chromium III is an essential element in humans, with a daily oral intalle of 50 to 200 nacrograms per day cup diremonimended for an adult. Data on adverse effects of frich oraller pastites of chrommin III are not available for humage, but a study with more suggests. possible firmate to the male reparatuative trait. We have not els, eithert annonmum III ior. car impoemicible

#### ъ. Cobalt

Acute (short-term) exposure to high levels of cobalt by inhalation in humans. and animals results in respiratory effects. such as a significant decrease in ventilatory function, congestion, edema. and hemorrhage of the lung. Respiratory effects are also the major effects noted from chronic (long-term) exposure to cobalt by inhalation, with respiratory irritation, wheezing, asthma, pneumonia, and fibrosis noted. Cardiac. effects, congestion of the liver, kidneys, and conjunctiva, and immunological effects have also been associated with cobalt inhalation in humans. Cobalt is an essential element in humans, as a constituent of vitamin B12, but excessive oral intake has been reported. to damage the heart, and to cause gastrointestinal effects and contact dermatitis. Human and animal studies are inconclusive with respect to potential carcinogenicity of cobalt. We have not classified cobalt for carcinogenicity.

#### 9. Mercury

Mercury exists in three forms:
Elemental mercury, inorganic mercury compounds (primarily mercuric chloride), and organic mercury compounds (primarily methylmercury). Each form exhibits different health effects. Brick, structural clay products, and clay ceramics manufacturing may release elemental or inorganic mercury, but not methylmercury. However, elemental and inorganic mercury are deposited on surface water, where they are converted to methylmercury, an important food contaminant.

Acute (sbort-term) exposure to high levels of elemental mercury in humans. results in central nervous system (CNS) effects such as tremors, mood changes, and slowed sensory and motor nervefunction. High inhalation exposures can also cause liidney damage and effects on the gastrointestinal tract and respiratory. system. Chronic (long-term) inhalation. empositive to elemental mercury in human: also aftent the CUS with effects such as increased excitability, irritability, excessive shyness, and tremore. Data on toxic offects of oral exposure to elemental mercury are sparse. We have not classified elemental mercury for caromogenicity.

Acute exposure to morganic mercury by the oral route may result in effects such as naused womiting and severe andominal pair. The major effect from chronic exposure, either oral or inhabition to inorganic mercury is ladingly damage. Reproductive and developmental animal studies have reported effects such as alterations in

testicular tissue, increased embryo resorption rates, and abnormalities of development. Mercuric chloride (an inorganic mercury compound) exposure has been shown to result in forestomach, thyroid, and renal tumors in experimental animals. We have classified mercuric chloride as a Group C, possible human carcinogen.

Both acute and chronic oral exposure to methylmercury have been found to cause developmental damage to the central nervous system in fetuses and children, with effects including mental retardation, deafness, blindness, and cerebral palsy. Lower exposures may cause developmental delays and abnormal reflexes. The most important source of methylmercury exposure for most people is eating fish. Although fish is an important part of a balanced diet federal and state fish advisories recommend limiting intake of certain fish that contain elevated methylmercury levels.

#### 10. Manganese

Health effects in humans have been associated with both deficiencies and excess intakes of manganese. Chronic (long-term) exposure to low levels of manganese in the diet is considered to be nutritionally essential in humans, with a recommended daily allowance of 2 to 5 milligrams per day (mg/d). Chronic inhalation exposure to high levels of manganese by inhalation in humans results primarily in CNS effects. Visual reaction time, hand steadiness, and eye-hand coordination were affected in chronically-exposed workers. Manganism, characterized by feelings of weakness and lethargy, tremors, a masklike face, and psychological disturbances, may result from chronic exposure to higher levels. Impotence and loss of libido have been noted in male workers afflicted with manganism attributed to inhalation exposures. We have classified manganese as Group D. not classifiable as to human carcinogenicity.

### 11. Nickel

Nickel is an essential element in some animal species, and it has been suggested it may be essential for human nutrition. Nickel dermatitis, consisting of itching of the fingers, hands, and forearms, is the most common effect in humans from chronic (long-term) skin contact with nickel. Respiratory effects have also been reported in humans from inhalation exposure to nickel. No information is available regarding the reproductive or developmental effects of nickel in humans, but animal studies have reported an

increased risk of lung and nasal cancers from exposure to nickel refinery dusts and nickel subsulfide. Animal inhalation studies of soluble nickel compounds (i.e., nickel carbonyl) have reported lung tumors. Dermal exposure to nickel may produce contact dermatitis. Adverse effects of oral nickel exposure are not well-described. We have classified nickel refinery dust and nickel subsulfide as Group A, human carcinogens, and nickel carbonyl as a Group B2, probable human carcinogen, by inhalation exposure.

#### 12. Lead

Lead is a very toxic element, causing a variety of effects at low oral or inhaled dose levels. Brain damage, kidney damage, and gastrointestinal distress may occur from acute (short-term) exposure to high levels of lead in humans. Chronic (long-term) exposure to lead in humans results in effects on the blood, CNS, blood pressure, and kidneys. Children are particularly sensitive to the chronic effects of lead, with slowed cognitive development, reduced growth, and other effects reported. Reproductive effects, such as decreased sperm count in men and spontaneous abortions in women, have been associated with lead exposure. The developing fetus is at particular risk from maternal lead exposure, with low birth weight and slowed postnatal neurobehavioral development noted. Human studies are inconclusive regarding lead exposure and cancer, while animal studies have reported an increase in kidney cancer from lead exposure by the oral route. We have classified lead as a Group B2, probable human carcinogen.

#### 13. Selenium

Selenium is a naturally occurring substance that is toxic at high concentrations but is also a nutritionally essential element. Acute (short-term) exposure to elemental selenium. hydrogen selenide, and selenium dioxide by inhalation results primarily in respiratory effects, such as irritation of the mucous membranes, pulmonary edema, severe bronchitis, and bronchial pneumonia. Studies of humans chronically (long-term) exposed to high Jevels of selenium in food and water have reported discoloration of the skin. pathological deformation and loss of mails, loss of hair, excessive tooth decay and discoloration, lack of mental alertness, and listlessness. The consumption of high levels of selenium by pigs, sheep, and cattle has been shown to interfere with normal fetal development and to produce birth defects. Results of human and ammai

studies suggest that supplementation with some forms of selenium may result in a reduced incidence of several tumor types. One selenium compound, selenium sulfide, is carcinogenic in animals exposed orally. We have classified elemental selenium as a Group D, not classifiable as to human carcinogenicity, and selenium sulfide as a Group B2, probable human carcinogen.

#### II. Summary of Responses to Major Comments and Changes to the Brick and Structural Clay Products Manufacturing Proposed NESHAP

In response to the public comments received on the proposed BSCP rule, we made several changes in developing today's final BSCP rule. The major comments and our responses and rule changes are summarized in the following sections. A more detailed summary can be found in the Response-to-Comments document, which is available from several sources (see SUPPLEMENTARY INFORMATION section).

#### A. Air Pollution Control Devices

The most significant change to the proposed BSCP rule concerns our conclusions regarding the effective application of air pollution control devices (APCD) to existing kilns. The EPA received numerous comments from industry representatives, kiln manufacturers, and air pollution control device vendors on issues related to the application and performance of APCD. The MACT floor in the proposed rule was based on the use of dry lime iujection fabric filters (DIFF), dry lime scrubber/fabric filters (DLS/FF), or wet scrubbers (WS). Another technology commonly used to control emissions from brick kilns, dry limestone adsorbers (DLA), was not considered to be a MACT floor technology at the time of proposal because we had concerns with monitoring options and our data indicated that the DLA could not achieve HAP emissions reductions equivalent to the reductions achieved by DIFF, DLS/FF, or WS technologies. However, as discussed in the paragraphs below, many commenters reported disadvantages of the DIFF, DLS/FF, and WS technologies for BSCP kilns and provided information to address our concerns about DLA technology. Consequently, the final rule allows some sources to use the DLA teclinology.

Several commenters argued that DIFF, DLS/FF, and WS technologies are not proven or commercially available for DSCP kilns. Commenters pointed out that, with the exception of one facility, full-scale WS have never been used on

ESCP kilns, although some short-term pilot tests of WS have been conducted. The commenters pointed out that injection systems (such as DIFF and DLS/FF) and wet control devices need a certain airflow to operate properly and different products may require different airflows, some of which could be outside of the range within which the APCD operates properly. In addition. commenters pointed out that during kiln slowdowns (which could be caused by a situation such as an economic slowdown), the APCD may not be able to operate at all because of reduced kiln airflow.

Several commenters expressed concerns about waste disposal. Commenters stated that DIFF and DLS/ FF systems produce large amounts of solid waste that is difficult and expensive to dispose of. Commenters stated that WS would not be viable options for many BSCP plants because of wastewater treatment issues (e.g., limited or no sewer access, wastewater treatment costs). Commenters added that recycling of WS wastewater back into the brick body is not an option because of problems created by the soluble salts in the water (e.g., scumming and efflorescence) and hecause the volume of wastewater generated would exceed process water needs even if recycling were possible.

Commenters also raised concerns about retrofitting existing BSCP kilns. with DIFF, DLS FF, and WS technologies. Commenters pointed out that brick color, the primary factor in brick sales, is affected by hiln airflow. Thus, retrofitting with an APCD that changes the kiln airflow would change the recipes for the manufacture of brick in a tunnel fails. Thus, years of experience in the colors produced by the unique firing characteristics of a kiln would be lost implications are serious. if a facility cannot match its existing product line.

The commenters also charged that we did not account for other retrofitting problems associated with installing DIFF, DLS 'FF or WS on older kilms, and the costs associated with these problems. Commenters also described how attempts at retrofitting filling with these APCD have resulted in significant bas unitervob alist to standame permanent reductions in Library production capacities. As stated by the commenters none of the retroits have been entirely successful in terms of reducing emitsion, while not disrupting me production process, and several have had dramatic nesotive impacts of: the production process at one totality. that remofined two lines with DRF the capacities of the two lattic decisared.

from 13.5 cars per day to 12.2 cars per day because of changes in the kiln airflow that resulted from the retrofit. This resulted in a loss of revenue of about \$3.1 ier vear. Another ti-stage injection retrofit DI system) installation at a different facility was reported to be extremely problematic, and the cost of the APCD. which was originally estimated at \$1 million, is now over \$2 million and the system is still not operating correctly more than 2 years later. The facility has experienced numerous problems with the basic design of the unit, including improperly designed dampers and reagent feeding systems. A facility representative stated that the problems are largely due to the fact that few systems have been developed for brick Lib operations, therefore, vendors are still learning (often on the industry's nickel) how to design these systems. In the facility's public comments, they stated that they plan to never build another hot baghouse (DIFF or DLS/FF) due to the massive operating problems associated with them. A retrofit DLS/FF system, the only one that has been attempted in the U.S. to date, also was problematic. The facility stated that they have experienced maintenance and material quality problems that have resulted in him downtime. The facility added that the problems stem from the fact that the system is a prototype without a substantial operational. troubleshooting and maintenance histor, , which has left the facility in the position of having to diagnose and solve the problems as the system operates. In addition, the company that installed this system is no longer quoting systems to the BSCP industry.

Numerous commenters recommended that EFA allow use of DLA. The commenters described the operating benefits of DLA, including ease of operation, low operating cost, little down time, and the ability to handle kith fluctuations with changing throughputs. Most importantly, DLA donot impact till operation. The commenters pointed out that DLA do not remuse a minimum airflow like DJFF DLS TF or WS technologies. One commenter pointed out that once a DLA is designed for maximum airflow, any fluctuations below this maximum only areate more contact time between the hain exhaust gases and the limestone which would likely increase the offectiveness of the DLA and would not impact the operation of the Lilie The commender pointed out that LLA bave been n. - extensively in Europe for many years and also are the most prevalent - PCD used in the PSCF

industry in the United States, Many commenters stated that DLA should be allowed if they can meet the BSCP standards. The commenters indicated that plants should not have to request site-specific monitoring parameters for DLA because they are the most prevalent technology. In addition, some commenters discussed the high costs and limited additional HAP reduction associated with replacing existing DLA with a DIFF system.

Several commenters felt that EPA disregarded or "bashed" DLA and disagreed with EPA's conclusions regarding DLA in the preamble to the proposed rule Specifically, the commenters disagreed that: DLA generate particulate matter (PM) emissions; long-term test data that demonstrate DLA performance over the life of the sorbent are not available; DLA limestone is not continuously replaced; and the performance of DLA decreases. as the sorbent is re-used because the ability of the sorbent to adsorb HF and

HCl decreases.

We disagree with commenters that the use of DIFF has not been proven in the brick industry. The DIFF and DLS/FF systems are a proven control technology for kilns with a given minimum airflow rate. We do, bowever, believe that retrofitting existing kilns with DIFF or DLS/FF systems is not feasible in many cases. We recognize that WS may not be practical or low-cost for most facilities, but believe they could be a legitimate option for some facilities (e.g., facilities with sewer access). We acknowledge that retrofitting existing BSCP killns with certain APCD (particularly those that affect kiin airilowi can alter timehonored recipes for brick color, thereby changing the product. We acknowledge that DLA are used extensively around the world to control emissions from brick kilns. In developing the description of DLA technology for the preamble to the proposed rule, we used the technical data available to us at the time. We had no intention of "bashing" DLA but simily reported the data at

After consideration of the comments received regarding DIFF, DL3 FF, WS, and DLA technologies, we have come to new conclusions regarding the effective application of these devices. We now believe that DLA are the only currently available technology that can be used to retrout existing hilm; without potentially significant impacts on the production process, and we have revised today's final rule accordingly, lo addition, we believe that, because of the retrofit concerns that we have identified it is not technologically and economically teasible for an existing

small tunnel kiln that would otherwise meet the criteria for reconstruction in 40 CFR 63.2 and whose design capacity is increased such that it is equal to or greater than 9.07 Mg/hr (10 tph) of fired product (for the remainder of this preamble, these sources will be referred to as "existing small kilns that are rebuilt such that they become large kilns") to meet the relevant standards (i.e., new source MACT) by retrofitting with a DIFF, DLS/FF, or WS. In addition, we believe that it is not technologically and economically feasible for an existing large DLAcontrolled kiln that would otherwise meet the criteria for reconstruction in 40 CFR 63.2 (for the remainder of this preamble, these sources will be referred to as "existing large DLA-controlled kilns that are rebuilt") to meet the relevant (i.e., new source MACT) standards by retrofitting with a DIFF, DLS/FF, or WS. Accordingly, we have added regulatory language in 40 CPR 63.8390(i) to provide that an existing small kiln that is rebuilt such that it becomes a large kiln and an existing large DLA-controlled tunnel kiln that is rebuilt do not meet the definition of reconstruction in 40 CFR 63.2 and are not subject to the same requirements as new and reconstructed large tunnel kilns. However, it is technologically and economically feasible for both types of kilns described in 40 CFR 63.8390(i) to retrofit with a DLA (or to continue operating an existing DLA) and we have revised today's final rule to require that such kilus meet emission limits that correspond to the level of control provided by a DLA. We continue to believe that DIFF, DLS/FF, and WS are appropriate technologies for new large tunnel kilns and for reconstructed large tunnel kilns that were equipped with DIFF, DLS/FF, or WS prior to reconstruction. However, DLA are the only APCD that have been demonstrated on small tunnel kilns (which have smaller airflows than large tunnel kilns), and, therefore, the requirements for new and reconstructed small tunnel kilns are based on the level of control that can be achieved by a DLA. We note that facilities have the flexibility to select any control device or technique that ensures that emissions from their brick kilns are in compliance with the emission limits set forth in the final rule. Each of the APCD described above have advantages and disadvantages to their use, and the selection of the APCD to meet the requirements of the final ritle will be dependent on site-specific parameters.

#### B. Affected Source

#### 1. Production-Rate Limit

The proposed rule subcategorized tunnel kilns based on a 9.07 Mg/hr (10 tph) design capacity. We requested comment on the appropriate design capacity-based subcategorization level in the preamble to the proposed rule. We received numerous comments regarding subcategorization of tunnel kilns. While some commenters agreed with the 9.07 Mg/hr (10 tph) distinction among tunnel kiln subcategories, several commenters thought that the 9.07 Mg/hr (10 tph) limit was arbitrarily assigned. The commenters charged that EPA did not use all available data in determining the appropriate size cutoff. Many commenters argued that the design capacity limit should be higher based on available data (i.e., 10.1 Mg/hr (11.1 tph) or 12.1 Mg/hr (13.3 tph)). The commenters disagreed that the cutoff should be rounded down from 10.1 Mg/ hr (11.1 tph) to 9.07 Mg/hr (10 tph).

Some commenters noted that a design capacity distinction gives a competitive advantage to facilities operating smaller kilns. One commenter disagreed that there was a technological basis for differentiating among tunnel kilns producing above or below 9.07 Mg/hr (10 tph). The commenter stated that EPA may not subcategorize tunnel kilns

to reduce costs.

Through subcategorization, we are able to define subsets of similar emission sources within a source category if differences in emissions characteristics, processes, APCD viability, or opportunities for pollution prevention exist within the source category. Section 112(d)(1) of the CAA states "the Administrator may distinguish among classes, types, and sizes of sources within a category or subcategory" in establishing emission standards. Thus, we have discretion in determining appropriate subcategories based on classes, types, and sizes of sources. We used this discretion in developing subcategories for the BSCP source category. We first subcategorized kilns based on type (i.e., periodic kilns versus tunnel kilns). We then further subcategorized tunnel kilns based on kiln size. Our distinctions are based on technological differences in the equipment. For example, periodic kilns are smaller than tunnel kilns and operate in batch cycles, whereas tunnet kilns operate continuously. There are also differences in the effective application of air pollution controls. To our knowledge, HAP emissions from periodic kilns have not successfully been controlled. Similarly, we distinguished between tunnel kins with design capacities above and below 9.07 Mg/hr (10 tph) at proposal in part because the APCD we believed to be the best performers (DIFF, DLS/FF, and WS) were not demonstrated on existing tunnel kilns with design capacities below roughly 9.07 Mg/hr (10 tph). For the reasons discussed below, we revisited the appropriate subcategorization level in response to comments on the proposal when developing today's final rule. While we continue to believe that 9.07 Mg/hr (10 tph) is the appropriate subcategorization level, our reasons for choosing that level have changed since proposal in light of new information that we received during the public comment period about DLA controls and the three proposed MACT controls (DIFF, DLS/FF, and

As discussed earlier, numerous commenters pointed out serious concerns regarding retrofitting existing kilns with ΔPCD such as DIFF, DLS/FF, and WS. Therefore, we now consider DLA to be the only currently available technology that can be used to retrofit existing kilns, including existing small kilns that are rebuilt such that they become large kilns and existing large DLA-controlled kilns that are rebuilt, without potentially significant impacts

on the production process.

In response to comments suggesting that we include new data in our analyses, we updated our data base with information on new kilns, new APCD (except those controls that we consider to achieve the lowest achievable emission rate (LAER) as specified in section 112(d)(3)(A) of the CAA), changes in kiln capacities, and changes in facility ownership. We used the information submitted by commenters and made followup calls to States and individual facilities for additional clarification as necessary to update our data base.

We used our updated data base in reevaluating all aspects of the proposed standards. The smallest tunne! kiln with MACT floor controls (i.e., with DLA controls reflecting the existing source MACT floor under today's final rule) in our updated database has a capacity of 8.3 Mg/hr (9.1 tph). Rounding up to the nearest integer, based on current application of APCD to BSCP tunnel kilns, we believe that 9.07 Mg/hr (10 (ph) continues to be an appropriate subcategorization level. Commenters have stated that a smaller tunnel kiln (e.g., 4.5 Mg/hr (5 tph) capacity) isdissimilar from a larger tunnel kiln (e.g., 13.6 Mg/hr (15 tpb) capacity), especially with regard to the airflow, which is a Lay operating parameter for APCD. Auflow is particularly important for

lime injection-type systems (DIFF and DLS/FF), because the injected lime is carried through the reaction chamber (or duct) by the kilm exhaust gas. For a given lime injection rate, if a minimum exhaust flow is not maintained, the sorbent can settle in the duct work and cause APCD malfunction. Furthermore, APCD malfunctions can affect the airflow within the kiln, and can destroy product that is in the kiln. We believe that DIFF and DLS/FF systems, if attempted on smaller kilns, would experience more difficulties with respect to airflow than systems on larger kilns because as the design airflow decreases, the acceptable operating range also would be expected to decrease. Any fluctuation in airflow would be expected to have a greater impact on APCD operation as the size of the system decreases. Given the technological concerns and the capacities of currently-controlled tunnel hilns, we maintain that a design capacity-based subcategorization level of 9.07 Mg/hr (10 tph) is appropriate for existing tunnel kilns.

We acknowledge the comments suggesting that 10.1 Mg/hr (11.1 tph) should be the size cutoff based on the smallest DIFF-controlled tunnel kiln. However, because we now consider that the performance of a DLA represents the MACT floor for existing sources land DIFF, DLS/FF, and WS also can meet the emission limits), we considered the smallest non-LAER DLA-controlled kiln in setting the subcategorization level. We disagree that 12.1 Mg/hr (13.2 tph) would have been the proper level for proposal or for the final rule. We believe that consideration of technological differences and the effective application of APCD to killns of different sizes is the appropriate method of selecting a subcategorization level. We maintain that 9.07 Mg/hr (10 tph) is appropriate

We understand that, regardless of the particular subcategorization level selected there will be facilities that operate thins with throughputs slightly. above the level and some that operate Lilns at slightly below the level Facilities operating Librar slightly above the subcategorization level have the option of accepting a federally enforceable permit limit to limit their throughput to below the level Fatalities operating just below the level must make careful decisions regarding expansion of their Libra. We aremowledge that facilities operating near the sub-lategorization. Is elimust, make decisions regarding permit limits. and expansions based on facilities apecuto considerati in tele control co in import on revenues. However his some commenters have pointed ou.

cost is not an appropriate criteria for us to use in establishing subcategories, because our discretion for establishing subcategories is limited, under the CAA, to distinguishing among classes, types and sizes of sources.

#### 2 R&D Hilm Definition

One commenter requested that we change the definition of research and development (R&D) kiln so that it is consistent with the definition of R&D in section 112(c)(7) of the CAA and most other NESHAP. Therefore, today's final rule includes a revised definition of research and development kiln that is consistent with section 112(c)(7) of the CAA and other NESHAP.

### C. Existing Source MACT

 Consideration of Synthetic Area Sources in the MACT Floor Determinations for Existing Sources

In the preamble to the proposed ESCP rule, we requested comment on inclusion of synthetic area sources (also called synthetic minor sources) in the MACT floor determinations for existing tunnel kilns. For the remainder of this preamble, we will refer to these sources as synthetic minor sources. Synthetic minor sources are those facilities that emit fewer than 10 tons per year of any HAP and fewer than 25 tons per year of any combination of HAP because they use some emission control device (or devices), the operation of which is required by a Federally Enforceable State Operating Permit (FESOP). In the absence of such controls, these sources would be major.

Inclusion of symmetic minor sources in the NIACT floor determination was an issue prior to proposal because whether or not symbletic minor sources were included would affect the level of control represented by the floor determinations for existing large tunnel kiths their tunnel lillns with designcapacities equal to or greater than 9.07 f.fg/hr+16 tph+1 Had synthetic minor. source: been excluded, the MACT floor for chisting tunner talks would have been the emission; reductions 'With avaithetic minior sources included las weproposed), the NACT floor for existing tunnel lalm war based on a DIFF, DLS FF or M.J.

Industry is presentatives asserted prior to proposal, that the BSCP MACT floor determination should not include synthetic minor sources. We rejected the idea of excluding southers minor sources it and the IsACT floor determination to be retained sons do to see an in the present a to the propose or the IDE+ 67 PM 47094.

4704 (++70, 1, 141, 150, 2002)

Nevertheless, because of the industry representatives arguments, we requested comment from all interested parties on inclusion of synthetic minor sources in MACT floor determinations.

Following proposal, numerous industry representatives commented on the issue of whether to include synthetic minor sources in MACT floor determinations. The industry representatives commented that only major sources are included in the listed BSCP source category, and therefore. only major sources are to be used in the MACT floor determination. The commenters referenced section 112(a)(1). of the CAA, which defines major source as a source that "emits or has the potential to emit considering controls 10 tons per year \* \* \* " (emphasis added), and stated that by definition, synthetic minor sources are not major sources. The commenters noted that EPA did not include true area sources (or minor sources) in the MACT floor determination and stated that synthetic minor sources should be treated similarly for purposes of establishing MACT floors.

An environmental group also commented on the issue of including synthetic minor sources in MACT floor determinations. The commenter supported EPA's decision to include synthetic minor sources in the MACT floor for BSCP. The that the CAA requires EPA to include synthetic minor sources in MACT floor determinations. The commenter stated that excluding consideration of the bestcontrolled sources (which became synthetic minor sources as a result of effective controls! would contradict the CAA section 112(d) MACT floor methodology established by Congress. The commenter argued that such exclusion would wealten emission standards required for existing sources, and increase the levels of air toxics released into the environment.

Section 112(d) of the CAA directs us: to establish emission standards for each category or subcategory of major sources and minor sources of HAP listed for regulation pursuant to section 112(c) of the GAA. Each such standard must reflect a minimum level of control known as the LLACT floor. (See CAA section 112(di.) However, section 142 of the CAA doer not specifically address synthetic minor or synthetic area sources, which include those sources that emil fewer than 40 tank per read of any HAP or fewer than 25 ton, per year. of any combination of HAP be sause they use some emission control deviceis), pollution crevention techniques or other medicates (collectively, referred to and ditroit in this preamble indented.

under Federal or State regulations. If not for the enforceable controls they have implemented, synthetic minor sources would be major sources under section 112 of the CAA.

We believe that the better interpretation of the CAA's plain language and legislative history requires that synthetic minor sources be included in MACT floor determinations. First, the plain language of the statute makes clear that our MACT floor determinations are to reflect the best sources in a category. For new sources in a category or subcategory, the MACT floor shall not be less stringent than the emission control that is achieved in practice by the best-controlled similar source, as determined by EPA. (See CAA section 112(d)(3), emphasis added.) For existing sources in a category or subcategory with 30 or more sources, the MACT floor may be less stringent than the floor for new sources in the same category or subcategory but shall not be less stringent than the average emission limitation achieved by the best performing 12 percent of the existing sources (for which the Administrator has emissions information). (See CAA section 112(d)(3)(A), emphasis added.1) Thus. section 112(d)(3) of the CAA requires that MACT floors reflect what the bestcontrolled new sources and the bestperforming existing sources achieve in practice. These phrases contain no exemptions and are not limited by references to sources with or without controls. Therefore, they suggest that all of the best-controlled or best-performing sources should be considered in MACT floor determinations, regardless of whether or not such sources rely upon controls.

Furthermore, section 112(d)(3) of the CAA expressly excludes certain sources that meet LAER requirements from MACT floor determinations for existing sources. (See CAA section 112(d)(3)(A).) The fact that Congress expressly excluded such LAER sources but did not also exclude synthetic minor sources suggests that no exclusion was intended for synthetic minor sources. Indeed, nothing in the statute suggests that EPA should exclude a control technology from its consideration of the MACT floor because the technology is so effective that it reduces source emissions such that the source is no longer a major source of HAP. (See 67

FR 36,460 and 36,464, May 23, 2002, stating this rationale for including synthetic minor sources in the floor determination for the proposed NESHAP for municipal solid waste landfills.)

Some commenters argue that because the BSCP source category only includes major sources and synthetic minor sources are non-major by definition, synthetic minor sources (like true area sources) fall outside the regulated source category and should not be considered in MACT floor determinations. EPA agrees that the BSCP source category includes only major sources. (See 67 FR 47,894 and 47,898, July 22, 2002.) However, EPA disagrees that the CAA contemplates that synthetic minor sources must be treated like true area sources and excluded from MACT floor determinations. Section 112(a) of the CAA defines a major source as:

any stationary source or group of stationary sources located within a contiguous area and under common control that emits or has the potential to emit considering controls, in the aggregate, 10 tons per year or more of any hazardous air pollutant or 25 tons per year or more of any combination of hazardous air pollutants.

(See CAA section 112(a)(1).) An area source is defined as any stationary source of hazardous air pollutants that is not a major source. (See CAA section 112(a)(1).) In the major source definition, the reference to a source's potential to emit considering controls allows the interpretation that a source's potential to emit before and after controls is relevant, such that synthetic minor sources may be considered within the meaning of this definition and included in MACT floor determinations for categories of major sources.2 Some commenters appear to suggest that the reference to a source's potential to emit considering controls can only mean a source's potential to emit after controls have been implemented. While it is possible to read the phrase in this manner in isolation, this interpretation would have

the effect of excluding the bestperforming sources in a category from MACT floor determinations and therefore would be contrary to the statutory mandate that EPA set MACT floors based on the levels the bestcontrolled new sources and the bestperforming existing sources achieve in practice. We believe the statutory reference to potential to emit considering controls should be read in a manner consistent with the other requirements of section 112(d) of the CAA to allow for the consideration of synthetic minor sources in MACT floor determinations for categories of major. sources.

In addition, the legislative history suggests that synthetic minor sources should be included in MACT floor determinations. In a floor statement, Senator Durenberger stated that in implementing section 112(d)(3) of the CAA, "the [Senate] managers intend the Administrator to take whatever steps are necessary to assure that [the Administrator] has collected data on all of the better-performing sources within each category. [The Administrator] must have a data-gathering program sufficient to assure that [EPA] does not miss any sources that have superior levels of emission control " (See Environment and Natural Resources Policy Division, Congressional Research Service, 103d Cong., S.Prt. 103–38 (prepared for the U.S. Senate Committee on Environment and Public Works), A Legislative History of the Clean Air Act Amendments of 1990 at 870, Nov. 1993, emphasis added.) This statement underscores that Congress intended for MACT floor determinations to reflect consideration of all of the sources in each category with the best emission controls. We believe it would be inconsistent with Congress's intent and the plain language of the CAA to exclude synthetic minor sources—those sources with superior controls which became synthetic minor sources by implementing such controls-from MACT floor determinations.

We believe that the inclusion of synthetic minor sources in MACT floor determinations is justified because of the reasons explained above. Even if the MACT floor determination had been "no emissions reductions" we believe that a departure from the MACT floor to a beyond-the-floor standard, based on DLA technology, is viable because the benefits associated with the emissions reductions will exceed the cost of installing and operating the technology.

MACT Floors for Existing Sources.

Some commenters questioned how the MACT floor for existing sources was

If a category or subcategory has fewer than 30 courses, the floor shall be "the average emission limitation achieved by the best performing 5 courses (for which the Administrator has or could category or subcategory." (See CAA, section 112(d)(3)(B), emphasis added.)

<sup>2</sup> We believe this approach is not inconsistent with our policy that existing sources that limit their potential to emit to below the major source threshold prior to the first compliance deadline under a MACT standard will not be subject to the standard, as one commenter suggests. (See Memorandum from John S. Seitz, Director, Office of Air Quality Planning and Standards, EPA, to EPA Regions, "Potential to Emit for MACT Standards --(anidance on Timing Issues," May 16, 1995.) Including synthetic minor sources in MACT floor determinations ensures that MACT floors reflect the best performing sources, as the CAA requires. At the same line, our pulsey recognizes that some as that already achieve or perform better than the LIACT floors need not be subject to the MACT -Jandards.

set. Some commenters thought that control devices installed for sulfur oxides (SO<sub>4</sub>) control (rather than for HAP control) should not be considered in the MACT floor. Other commenters felt that costs should be a consideration.

One commenter charged that EPA has simply set MACT floors based on control technology type and that EPA did not identify the relevant best performers and set floors reflecting their average emission level. The commenter noted that factors other than control device type affect emissions and that EPA must consider all non-negligible factors in setting MACT floors and considering beyond-the-floor measures. The commenter stated that if EPA believes it is unworkable to consider all factors, then perhaps EPA should base standards on actual emissions data which reflects all the factors influencing a source's performance. The commenter also noted that EPA picked the worst performance of any source that used the chosen technology to set the floor for PM.

A detailed discussion of how we determined the MACT floor for existing large tunnel kilns (i.e., tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph)) is provided below. Although the discussion in the example below focuses on existing large tunnel kilns that exhaust directly to the atmosphere or to an APCD, the same MACT floor methodology was used for existing large tunnel kilns that exhaust to sawdust dryers prior to exhausting tothe atmosphere, existing small tunnel hilms that exhaust directly to the atmosphere or to an APCD, existing small sawdust-fired tunnel kilns that duct to sawdust dryers, and existing periodic Lilps. Details of these MACT floor determinations were discussed in the preamble to the proposed rule. (See 67 FR 47909-47912, July 22, 2001 I Section 112(d)(3) is the section of the CAA that dictates how we must establish MACT floors. Section 112(d)(3) of the CAA states that.

The maximum degree of reduction in emission; that is deemed achievable for new courses in a category or subcategor, shall not to less stringen; than the emission control that is achieved in practice by the best controlled similar source, as determined by the Administrator Entirsion standards promulgated under this consection for emisting sources in a category or subcategory may be less stringen; than standards for new courses in the same category or subcategory but shall not be less stringent and may be more stringent than—

(3.) The average emission limitation is inevent to the best performing (1 person) on the extremy sources that which the subministrator has emissions information assembling those sources that bate, within ()

months before the emission standard is proposed or within 30 months before such standard is promulgated, whichever is later, first achieved a level of emission rate or emission reduction which complies, or would comply if the source is not subject to such standard, with the lowest achievable emission rate (as defined by section 171) applicable to the source category and prevailing at the time, in the category or subcategory for categories and subcategories with 30 or more sources.

With the exception of the LAER provisions in section 112(d)(3)(A) of the CAA, the CAA requires us to base the MACT floor on the best-performing sources without consideration of why facilities decided to control emissions. Therefore, if an APCD is reducing HAP emissions (e.g., HF, HCl, or HAP metals), it is irrelevant if sources installed APCD for SO<sub>X</sub> or visible emissions control for purposes of conducting MACT floor determinations.

control level for existing sources using the following general procedure:

(1) We reviewed available data on pollution prevention techniques (including substitution of raw materials and/or fuels) and the performance of add-on control devices to determine the techniques that were viable for and effective at reducing HAP emissions;

(2) For each subcategory, we ranked the kilns from the best performing to the worst performing based on the emission reduction technique used on the kilns;

(3) For each subcategory, we then identified the 94th percentile kiln and the emission reduction technique that represented the MACT floor technology; and

14) For each subcategory, we then selected production-based or percent-reduction emission limits that correspond to the 94th percentile kiln and emission reduction technique, and we based our selections on the available data while concidering variability in the performance of a given emission reduction technique.

To identify the best-performing emussion reduction techniques, we reviewed available data on pollution prevention techniques likely substitution of raw materials and or fuels) and the nerformance of add-on control devices. We agreen med that substitution of raw materials and or fuels is not an option. he ause substitution of raw materials and/or field could affect the ability of a iozday to implicate its current product line. In addition, it is impractical for facilities to import, from a distance of more than a few miles the large. am ainte of favorierial that are regimesa (nort la ilities are located in acisse profinery to their row material.

source). With respect to use of low-HAP fuels, our available test data for the BSCP industry do not show identifiable differences in emissions based on kilnfuel type; that is, the contribution of raw materials to HAP emissions far outweighs the contribution of the fuels. In addition, fuel type can impact the color of a product, and any requirement that would require a kiln to change fuel type could cause the kiln to be unable to match an existing product line. While we agree that factors other than APCD type can affect emissions, we do not have the data to determine the specific degree of the effect of factors other than APCD on emissions, and we believe that, for the BSCP industry, factors other than APCD use are not viable MACT floor or beyond-the-floor control options. Our data show that add-on-APCD have a large effect on emissions, and further show that the presence or absence of an APCD is likely the greatest factor in determining a BSCP kiln's actual performance. It follows that the subset of BSCP kilns that are the best performers are those with add-on APCD. Therefore, our analysis focused on the performance of add-on control devices.

Prior to proposal we concluded that the best-performing add-on control devices were DIFF, DLS/FF, and WS. Based on the comments received following proposal (as discussed elsewhere in this preamble) regarding retrofit concerns with these technologies, we now believe that DLA are the only currently available technology that can be used to retrofit existing large litins without potentially significant impacts on the production process. Thus, DLA are the best-performing APCD for existing large tunnel kilns.

We ranked the kilns within each subcategory according to APCD use. Information on the number of kilns and the types of APCD was based primarily on responses to a survey of the industry and additional information gathered following the survey including public comments on the proposed rule. Equipment in use at major sources and synthetic manor source: was used in the equipment rapling in accordance with section 112(d)(3)(A) of the 0.4A. equipment at rulns that achieved LAER less than 18 months before proposal was not included in the equipment ranking When we ranked the large turnel kiths. we treated fallot equipped with DLA as the best-controlled sources, although DIFF. DL5/FF, and W Sidso can achieve the level of performance of a DUA,  $W_{\rm G}$ ranked the Allris by AFCD mither than actual unit-specific emissions serius ions betause we do not have emissions (sa data or all Lillies,

Section 112(d)(3) of the CAA specifies that we set standards for existing sources that are no less stringent than the average emission limitation achieved by the best-performing 12 percent of existing sources (for which the Administrator has emissions information) where there are 30 or more sources in the category or subcategory. Our interpretation of average emission limitation is that it is a measure of central tendency, such as the arithmetic mean or the median. If the median is used when there are at least 30 sources, then the emission level achievable by the source and its APCD that is at the bottom of the top 6 percent of the bestperforming sources (i.e., the 94th percentile) represents the MACT floor control level. We based our MACT floors for each BSCP subcategory on this interpretation. Nineteen percent (22 of 115) of the existing large tunnel kilns located at synthetic minor sources or major sources are controlled by a DLA (12), DIFF (4), DLS/FF (4), or WS (2). Because more than 6 percent of the large tunnel kilns reduce emissions by some technique, emissions reductions from these kilns are required under the CAA. We then considered which of these controls are proven to be applicable to existing tunnel kilns, and we ranked these kilns to determine the appropriate MACT emission limits. We consider the 12 DLA to be equivalent and believe that this type of control can be applied to any existing large tunnel kiln without causing potentially significant production problems. We consider the performance of all of the DLA to be equivalent because there currently are two types of DLA in the industry (supplied by two manufacturers), and we have test data for both designs that show HF removal efficiencies that are within 1 percent of one another. We excluded DIFF and DLS/FF from our ranking of controls for existing sources because of the reported problems caused by applying DIFF and DLS/FF to existing kilns. We excluded WS from our ranking of controls for existing sources because many facilities do not have proven wastewater disposal options. Therefore, we only considered DLA in our ranking, and accordingly. the 94th percentile source (the 7th bestcontrolled source) is a DLA-controlled kiln. Therefore, the MACT floors for existing large tunnel kilns are based on the level of control achieved by a DLA. We have DLA outlet test data for 7 of the 12 existing large DLA-controlled tunnel Lilns, and therefore, we are confident that our test data are within the bestcontrolled 6 percent of sources. furthermore, the single best-performing

source, based on our available DLA outlet data, is one of the three sources for which a control efficiency is available.

Section 112(d)(2) of the CAA dictates how we must establish MACT. The MACT can either be established at the MACT floor, or can be some control level more stringent than the MACT floor or beyond-the-floor. Section 112(d)(2) of the CAA states that:

Emissions standards promulgated under this subsection and applicable to new or existing sources of hazardous air pollutants shall require the maximum degree of reduction in emissions of the hazardous air pollutants subject to this section (including a prohibition on such emissions, where achievable) that the Administrator, taking into consideration the cost of achieving such emission reduction, and any non-air quality health and environmental impacts and energy requirements, determines is achievable for new or existing sources in the category or subcategory to which such emission standard applies \* \* \*.

Although section 112(d)(3) of the CAA does not allow us to consider cost when determining MACT floors, we do consider costs when we examine beyond-the-floor control options according to section 112(d)(2) of the CAA. We acknowledge the commenters' concerns regarding the cost of the proposed standards. We determined that beyond-the-floor control measures would not be appropriate for existing large BSCP kilns because of retrofit costs arising from technical difficulties in retrofitting DIFF, DLS/FF, or WS. Thus, the emission limits for existing large tunnel kilns in today's final rule are based on the level of control achievable with a DLA.

It is our goal to set emission standards that reflect the performance of the bestcontrolled sources. Once we identified the subset of the best-controlled BSCP sources (i.e., DLA-controlled kilns), we used the highest emission level associated with these best performers to set the emission standard because it was our intent to set emission limits that reflect the performance that the bestcontrolled sources continually achieve considering variability. All sources, including the best-controlled sources, have variability in emissions. For example, data (individual test runs) from two tests conducted on one DLAcontrolled kiln showed HF control officiencies that ranged from 91.6 percent to 96.4 percent. This variability may result from APCD performance, and also could result from uncertainty associated with the test methods. Commenters have agreed with our approach to setting the productionbased emission limits at or slightly

higher than the highest data point, because this approach accounts for variability in the performance of individual sources, variability that could exist across the industry, and uncertainty in the test methods used to measure emissions. Furthermore, use of the highest emission level associated with the best performers prevents sources within the best-controlled subset from having to remove their existing APCI) and replace it with a new one that may or may not achieve slightly better performance.

We believe and intend that a welloperated DLA will achieve the emission limits set forth in this rulemaking. However, concerns have recently been raised that if high concentrations of sulfur exist in the kiln exhaust gas stream, the ability of a well-operated DLA to reduce the target acid gas HAP emissions (i.e., HF and HCl) may be compromised. The data we have does not suggest that these concerns are justified. If the EPA receives information showing that they are, EPA will take prompt action to resolve the issue through rulemaking and ensure that a facility with a well-operated DLA will be in compliance with the rule. The EPA will also work with any affected facilities to ensure that they are not subject to inappropriate sanctions before we are able to complete such a rulemaking.

#### D. New Source MACT

Several commenters disagreed that a large (design capacity equal to or greater than 9.07 Mg/hr (10 tph) of fired product) tu: ed with DIFF, DLS/ e bestcontrolled similar source for all new tunnel kilns. The commenters expressed concern that the DIFF, DLS/FF or WS controls proposed for all new tunnel kilns have not been demonstrated on smaller kilns. The commenters argued that emissions from small (e.g., less than 9.07 Mg/hr (10 tph)) and large turnel kilns are different because the required airflow and pollutant loading is different. The commenters stated that controls such as DIFF, DLS/FF, or WS do not decrease in size or cost for kilns below 9.07 Mg/hr (10 tph) design capacity. The commenters thought that the proposed standards for new tunnel kilns would prevent future construction of and upgrades to smaller kilns. The commenters recommended that a throughput cutoff be provided for new and reconstructed kilns. One commenter suggested that EPA create a size-outoff for new kilns, where the bestcontrolled similar source for smaller new kilns is a DLA-controlled kiln, and DLS/FF, DIFF, or WS for the larger

Films. One commenter noted the potential of existing kilms triggering new source requirements during reconstruction. The commenter requested that the ability of small businesses to overhaul existing kilms be addressed in the final rule.

These commenters have addressed several related issues including the selection of the best-controlled similar source, differences between small and large tunnel kilns, the feasibility of the proposed MACT-level controls in controlling emissions from smaller tunnel kilns or reconstructed tunnel kiins, and the costs of new controls. In responding to these comments, we have re-evaluated our analysis of MACT for new and reconstructed tunnel Lilas. In the original MACT analysis developed for the proposed rule, we recognized the inherent differences between small and large tunnel kilns and established a subcategorization level of 9.07 Mg/hr (10 tpb). The proposed 9.07 Mg/br [10] tph) subcategorization level applied to both existing and new tunnel kilns. For new and reconstructed sources, we selected the best-controlled similar source (DIFF, DLS/FF, WS) that would be applied to all new sources regardless. of size. In re-evaluating this analysis and in light of several comments that described the inherent differences and issues with the application of DIFF, DLS/FF, and WS control technologies to small tunnel kilns or reconstructed tunnel kilns, we have revised MACT for new sources. We also have added language in 40 CFR 65.8390(i) to provide that it is not technologically and economically feasible for two types of existing kilns that would otherwise meet the criteria for reconstruction under 40 CFR 63.2 to meet the relevant standards—i.e., new source MACT—and that such kilns do not fall within the definition of reconstruction and are not rubject to new source MACT requirements. The two types of kilns are existing small kilns that are rebuilt suchthat they become large hims and aviating large DLA-controlled tunnel Libra that are rebuilt. Today's final emicsion limite for those kilms and for new and reconstructed small turnel. luting are based on the performance of DLA control technology. The final entitisi in limito for new Jarge tunnel Lilns are based on the nepformance of DIFF DEVICE and WE control rechnology in addition, existing large tunnel lame emerged viith DTFS, DLS PF or VC are re-ordering ted sources subject to new solution (ACT) requirement: if the limit the criteria for reconstruction is 40 CEL CC a Such Libre must continue to meet new source

MACT limits, which are based on the performance of DIFF, DLS/FF, and W3.

We agree with the commenters that DIFF, DLS/FF, and WS control technologies have not been demonstrated on small kilns. However, we believe that the 9.07 Mg/hr (10 tph) size represents the threshold where emission control using DIFF, DLS/FF, or WS is technically feasible and demonstrated. Smaller kilns have smaller airflow rates than larger Lilns and any fluctuations in airflow rates can have a significant impact on the ability of DIFF, DLS/FF, or WS to operate correctly. For new and reconstructed small kilns, the DLA control technology has been demonstrated to perform adequately despite the lower airflow rates; DLA control systems are not as sensitive to airflow changes as DIFF. DLS/FF, or WS control systems. In addition, existing small kilns that are rebuilt such that they become large kilns and existing large DLA-controlled kilns that are rebuilt would experience the same types of retrofit problems that we described for existing tunnel kilns, and we believe that such tunnel kilns should be subject to requirements that can be met with a DLA. The DIFF, DLS/FF, and WS control systems have been demonstrated on new large lülns. Therefore, MACT for new and reconstructed large tunnel kilns is based on DIFF, DLS/FF, and WS control and is unchanged from proposal. Finally, the determination of MACT for new sources at the floor does not take the cost of control into consideration.

Our revised standards for new and reconstructed small tunnel lollns, existing small bilns that are rebuilt such that they become large kilns, and existing large DLA-controlled bilns that are rebuilt are based on the use of a DLA, which is considerably less expensive than the other MACT controls. The revised standards should minimize the commenters contents over the cost of reconstructing older.

#### E. Cost and Economic Impacts

Humerous comments were received regarding costs of the proposed rule Commenters contended that EPA did not consider the full costs of the rule to gardest associated with problems retrofitting a using I in 1 in general, commenters indicated that the economic impacts to brink industry would be seeners. Several commenters pointed out that the brick industry is losing market share to disaper building material, is go, words that are more detrinedual to the environment. The commenters stated that me prince all the rule would have a negative area.

future of many small businesses and the communities where they are located. The commenters expressed concern that the proposed rule would limit the opportunity for continued operation or expansion of brick plants throughout the U.S. The commenters noted that increased production costs would increase brick prices, causing brick to become less competitive with other materials and brick imports to rise. putting small U.S. companies out of business. Several commenters stated that the costs of the rule as proposed would prevent their company from ever replacing, performing a major repair on, or upgrading their existing kiln. Some commenters stated that the rule as proposed would eventually cause their company to go out of business. Some commenters added that they live in an economically depressed area and other jobs are not readily available.

One commenter disagreed with the Administrator's certification that the proposed rule would not create a significant impact on a substantial number of small entities. The commenter submitted an Economic Impacts Analysis (EIA). The commenter calculated and presented the Sales Test. Cash Flow Test, and Profit Test criteria which the commenter believes shows a greater number of small businesses at risk than does EPA's EIA. In addition, the commenter provided several specific comments on EPA's EIA. The commenter argued that the rule as proposed is a significant rulemaking per Executive Order (E.O.) 12866. A few commenters provided specific comments on the monitoring, reporting, and record leeping costs in the Office of Management and Budget (OMB) 83–J form and supporting statement.

Commenters also questioned the environmental benefits of the BSCP rule as proposed. One commenter questioned why the BSCP rule is necessary if brick manufacturing emissions are not causing public health problems or adverse environmental effects. Another commenter argued that there is no enidemiological evidence that unyone in Forth America has been harmed by brick plant HF emissions and that cancer incidence in brick plant workers is not higher than for the ceneral population.

An previously mentioned in this preamble section 112(b) of the CAA contains a list of HAP identified by Congress and authorizes EPA to add to that hot pollutants that present or may present a threat of active telefield, to bottom thealth or the emirronment faction 112(c) of the CAA requires us to test all categories and automated in a to major and an a sources of PAA and to

establish NESHAP for the listed source categories and subcategories under section 112(d) of the CAA. Because BSCP manufacturing is a listed source category containing major sources of HAP, we are required by the CAA to establish NESHAP for BSCP manufacturing.

As stated previously, MACT can either be established at the MACT floor, or can be some control level more stringent than the MACT floor or beyond the floor. Section 112(d)(3) of the CAA does not allow us to consider cost when determining MACT floors. We are only allowed to consider costs when we examine beyond-the-floor control options according to section 112(d)(2) of the CAA. We acknowledge the commenters' concerns regarding the cost of the proposed rule. At proposal, we determined that beyond-the-floor control measures would not be appropriate for the BSCP industry, in

part because of costs. Following proposal, we reevaluated the MACT floors for existing tunnel kilns and have revised the standards to incorporate use of DLA on existing large tunnel kilns. We also revised the MACT standards for new and reconstructed small tunnel kilns, existing small kilns that are rebuilt such that they become large kilns, and existing large DLAcontrolled tunnel kilns that are rebuilt such that the standards are based on the level of performance that can be achieved by a DLA. (MACT requirements for existing small tunnel kilns and new and reconstructed large tunnel kilns remain unchanged.) We continue to agree that beyond-the-floor control measures are not warranted for the BSCP industry. The revised MACT standards for new and reconstructed small tunnel kilns, existing small kilns that are rebuilt such that they become large kilns, and existing large DLAcontrolled kilns that are rebuilt are the same as the revised standards for existing large tunnel kilns. These revised standards are less costly and should reduce concerns regarding cost of retrofitting or rebuilding existing kilns and starting up new small kilns. Environmental benefits of today's final BSCP rule are discussed later in this preamble.

EPA reviewed the economic impact analysis report submitted by the commenter. We have revised our EIA to identify additional small businesses affected by the rule. We have also incorporated the lower revised cost estimates into the EIA. Impacts on small businesses are considerably lower in the revised analysis and prices are predicted to rise by less than one percent on average. The results of our

revised EIA, as well as a discussion of the impact of today's final rule on small businesses, are presented later in this preamble.

Comments on the costs of monitoring, reporting, and recordkeeping were incorporated into the revised OMB 83—1 form and supporting statement as appropriate. A discussion of the OMB 83—I form and supporting statement prepared in compliance with the Paperwork Reduction Act is presented later in this preamble.

#### F. Test Data and Emission Limits

#### 1. HF and HCl Emission Limits

Commenters stated that the test data EPA used to set the HF and HCi limits are questionable. An independent consultant, hired by the BSCP industry, reviewed the data and determined that six of the seven test runs used the wrong filter media. A glass filter media was used instead of a Tellon filter. The commenter suggested that, as a result, the data could be biased. One commenter also charged that EPA removed high test runs without any technical basis even though all of these runs met the same quality control (QC) criteria as other runs. Finally, one commenter stated that EPA's use of both HF and total fluorides (TF) data to develop the average uncontrolled HF emission factor (which was used in developing the HF emission limit) was unsupported, and the commenter believes that EPA should use only the HF test data because HF is the regulated pollutant.

We have reviewed the emission tests mentioned by the commenter and agree that there are some problems with most of the available test data, and we have accounted for any potential bias by revising the emission limits. In consultation with EPA's Emission Measurement Center (EMC), we used a conservative approach to determine the possible impact of the bias on the percent reduction emission limits. The analysis showed that our available percent reduction data could be as much as about 5 percent high, and we, therefore, decreased the corresponding HF and HCl percent reduction requirements by 5 percent and adjusted the corresponding production-based emission limits accordingly. In response to the commenter's assertion that we dropped two test runs without a technical reason, we examined the test runs in question and incorporated one of the two runs back into the data set used for developing the standards. Finally, in response to the appropriateness of using I'b data in calculating the average HF emission

factor, while the average of the TF and HF data sets suggest that TF and HF measurements are similar, we recognize the inconsistencies between the few available side-by-side HF and TF tests and we, therefore, decided to remove the TF data from the HF emission factor calculation. Based on the three issues discussed above, we revised the emission limits for kilns where MACT is based on use of DIFF, DLS/FF, or WS (i.e., for new large kilns). Today's final rule requires new large kilns to limit HF emissions to 0.029 kilograms per megagram (kg/Mg) (0.057 pounds per ton (lb/ton)) of fired product or reduce HF emissions by 90 percent; and limit HCl emissions to 0.028 kg/Mg (0.056 lb/ ton) or reduce HCl emissions by 85 percent.

The revised HF and HCl emission limits for existing large tunnel kilns, new and reconstructed small tunnel kilns, existing small kilns that are rebuilt such that they become large kilns, and existing large DLA-controlled tunnel kilns that are rebuilt are based on the use of a DLA for HAP reduction. Two HF emission tests (both conducted on the same source) and two total fluorides emission test are available for DLA-controlled kilns, and the tests showed HF or TF control efficiencies of 92.3 percent (IFF), 96.4 percent (HF), 93.3 percent (TF), and 93.5 percent (TF).

we identified problems with the two HF emission tests that could have biased the control efficiencies high. To account for this uncertain bias, and considering typical vendor guarantees for DLA systems (vendors will guarantee 90 percent HF reduction unless a lesser percentage meets the customer's need, in which case the vendors typically provide lower guarantees), we selected a percent reduction emission limit of 90 percent for HF. We applied this 90 percent reduction to the revised average HF emission factor of 0.29 kg/Mg (0.57 lb/ton) to calculate a production-based HF emission limit of 0.029 kg/Mg (0.057 lb/ton). Control efficiency data for HCl are available from two tests on a single DLA-controlled kiln. The tests averaged 30.7 percent control, and we selected a percent reduction HCl emission limit of 30 percent. We applied this 30 percent reduction to the average HCl emission factor of 0.19 kg/Mg (0.37 lb/ton) to calculate a production-based HCl emission limit of 0.13 kg/Mg (0.26 lb/ ton).

Percent of HAF metals in PM. Several commenters noted that HAF metals and PM data from four facilities (0.16 percent, 0.00 percent, 2.8 percent, and 4.5 percent) were used to arrive at 1.9 percent of the PM is PM HAP. The

commenters stated that EPA included an invalid, high data point for manganese in developing the percentage of PM that is PM HAP. We have examined the test run mentioned by the commenters and agree that the run should be voided. Our revised analyses now indicate that the overall percentage of PM that is HAP metals is 0.72 percent.

PM limit. Other commenters argued that a PM limit for brick kilns is unnecessary. One commenter noted that metals occur naturally in clays or shales used to make bricks and that PM emissions from BSCP plants are clay dust. The commenter argued that metals are locked into the structure of the clay dust and are not bio-available to affect humans through respiratory adsorption. ingestion, or dermal contact. Some commenters noted that there is limited information on the amount of HAP metals in the PM emitted. Commenters pointed out that EPA is not setting a PM limit for clay refractory kilns. Some commenters disagreed that PM is an adequate surrogate for HAP metals emissions. Commenters also requested that a percent reduction alternative be allowed for the PM standard, similar to the percent reduction limits for HF and HCI.

We agree that PM emitted from BSCP facilities is largely clay dust, and that metals are naturally occurring in clays and shales used to make bricks. Many RSCP facilities apply surface coatings or body additives containing HAP metals. to their products, and these coatings are another potential source of HAP metals emissions. These types of additives and coatings are not used in the manufacture.

of clay refractories.

We have four emission tests for HAP metals from tunnel kilns and all of these. tests measured some level of HAP metals emissions including emissions of antimony, arsenic, beryllium, cadmium, chromium, cobalt, mercury manganese, nickel lead and selenium Based on these data, we believe that all lulus emit some level of HAP metals and therefore, we are regulating HAP metals. emissions. Test data for HAF metals are not available for clay refractories tiltus.

We are unaware of any information to support the idea that the HAP metals are log) ed into the structure of the clay and : are not bro-available to affect humans. In the absence of such information and in the interest of protecting public health, we assume conservatively that the HAP metals are bio-available and ould affect human neelth. Tins a sumption is consistent with the we servative approach embodied in the AA section 112/fo/2) directive man ESE, add to flutants to the statutory list

of HAP that "may" present adverse risks to human health and the environment through various exposure routes.

We used PM as a surrogate for HAP metals so that individual emission limits would not be based on the limited and variable data. We examined the available HAP metals test data and calculated that about 95 percent of the HAP metals emissions are in particulate form. Furthermore, the types of control technologies used on BSCP kilns remove PM and would indiscriminately remove particulate HAP metals. The United States Court of Appeals for the District of Columbia Circuit stated in a December 15, 2000 decision (in response to the National Lime Association (NLA) challenge of the use of PM as a surrogate for HAP metals), "if HAP metals are invariably present in cement kiln PM, then even if the ratio of metals to PM is small and variable. or simply unknown, PM is a reasonable surrogate for the metals—assuming \* \* \* that PM control technology indiscriminately captures HAP metals along with other particulates." Our use of PM as a surrogate for HAP metals in the final BSCP rule is consistent with this decision.

We typically do not include percent reduction as an alternative for PM because a percept reduction standard rewards those facilities that have high inlet PM loadings. We believe that this is different from the percent reduction standards for HP and HCl because facilities do no! typically have options for reducine the uncontrolled levels of HF or HCl. Therefore, we are not providing an alternative percent reduction standard for PM

The revised FM emission limit for existing large tunnel kilns, new and reconstructed small tunnel kilns. existing small tilbs, that are rebuilt such that they become large kilms and existing large DLA-controlled tunnel hilms that are rebuilt is based on the use. ol a DLA. Data from four tests. conducted at the outlets of DLA were available for establishing a productionbased emission limit, and we selected the highest PK! data point as the emission limit in order to account for cariability. Today', final rule contains a FIM emission limit of 0.21 lig/Mg (0.42) Ib tont of fired product for existing large funnel hilling nev and reconstructed. small tormer folios existing small lalas: that are repuilt such that they become force Limb, and evicting large DLAcontroller tunnel latus that are rebuilt. The Planemension limit for new and reconstructed large turner Films i. gi Pic i 900 01 laccio et promine de guardana. Of a letter of the constrain.

#### G Monitoring Requirements

Numerous comments were received. on the proposed monitoring requirements. Some commenters felt that the monitoring, reporting, and recordkeeping requirements were unreasonable. Commenters noted that the monitoring requirements would require additional and higher skilled personnel.

Under section 114(a)(3) of the CAA, owners or operators of major sources are required to conduct enhanced monitoring of affected sources to ensure compliance with applicable emission standards, in response to this mandate. we have incorporated continuous compliance requirements into all part 63 standards, generally in the form of continuous emissions monitoring or continuous parameter monitoring. We believe that continuous monitoring is needed to ensure that emission controls are operated properly. However, 40 CFR 63.8(f) allows owners and operators of affected sources to request approval for alternative monitoring procedures to demonstrate compliance with emission limitations

Although we have eliminated some of the proposed monitoring requirements (such as fabric filter inlet temperature monitoring) from today's final rule, we have retained most of the proposed monitoring requirements. We believe that those monitoring requirements are the minimum needed to ensure continuous compliance with the emission limits.

#### Operation, Maintenance, and Monitoring (OM&M) Plan

Some commenters felt that development of an OM&M plan was overly burdensome. One commenter thought the requirement to include OM&M procedures for kiln operation was unjustified. Another commenter noted possible contradictions of OM&M plan requirements and Table 7 of the proposed BSCP rule (the table showing applicability of the General Provisions. to part 631.

After reviewing these comments, we decided that OM&M plans do not have to include procedures for monitoring the operation and maintenance of tunnel libs, and we have written the final rule accordingly. However, we continue to believe that site-specific CMAMA plans are necessary to ensure continued proper operation of any control derice that is used to comple viith the final rule.

Regarding the apparent contradictions. between 40 GPF 63.8425/bit31 through 110° and Table 7 of the proposed rale. we aid not site the General Programs

to part A in the proposed 40 CFR 63.8425 (b)(8) through (10), but specified that OM&M plans must include operation and maintenance, quality assurance, and reporting and recordkeeping procedures that are consistent with the General Provisions. Therefore, we believe there is no contradiction between 40 CFR 63.8425 (b)(8) through (10) and Table 7 of the proposed rule. However, we did clarify in Table 7 of the final rule that 40 CFR 63.8(c)(4) does not apply to subpart [[]]] because 40 CFR 63.8425 and 63.8465 specify the requirements for continuous monitoring systems (CMS).

Some commenters requested clarification on whether OM&M plans (and startup, shutdown, and malfunction plans (SSMP)) are required for kilns that would not be subject to control requirements (e.g., existing small tunnel kilns). Another commenter questioned if an OM&M plan would be required if compliance is achieved without a control device. The BSCP NESHAP applies only to affected sources. Under today's final rule, an existing small tunnel kiln is not an affected source. Therefore, the requirements for OM&M plans, SSMP, and other monitoring, notification, reporting, and recordkeeping requirements do not apply to those kilns. Owners or operators will be required to prepare an OM&M plan and SSMP for any kiln that is an affected source even if the kiln can meet the emission limits without the use of a control device.

#### 2. Bag Leak Detectors

Commenters indicated that bag leak detectors are unnecessary, overly protective, and maintenance intensive. The commenters noted that bag failure is noticeable because PM emissions would be visible at the stack. Several commenters requested that opacity or visible emissions (VE) determinations be allowed as opposed to bag leak detectors.

We agree with the commenters that periodic VE checks should provide a reasonable alternative to bag leak detectors, and we have written the final rule accordingly. In today's final rule, owners and operators of affected kilns that are controlled with a DLS/FF or DIFF can choose between installing a bag leak detection system or performing daily VE checks. Today's final rule also includes a provision for decreasing the frequency of VE checks provided to VF are observed.

# 3. Water Injection Rate Monitoring on DLS/FF

Three commenters stated that DLS/FF water injection rate monitoring has nothing to do with HF or HCl removal (but is important for sulfur dioxide (SO<sub>2</sub>) removal) and recommended that the provision for monitoring DLS/FF water injection rate be eliminated.

After reviewing the available information, we decided to eliminate the requirement for water injection rate monitoring on affected DLS/FF-controlled kilns. Water injection is used to enhance the removal of SO<sub>2</sub> by a DLS/FF, but has little effect on removal of HF and HCl.

#### 4. Fabric Filter Inlet Temperature

Several commenters recommended that the requirement to monitor labric filter inlet temperature be eliminated from the rule as proposed. The commenters explained that it would be impractical to hold the fabric filter inlet temperature to within 25 degrees below the average established during the performance test. The fabric filter inlet temperature varies frequently, much more than 25 degrees, because of many process factors. Other commenters noted that fabric filter inlet temperature has little relevancy to acid gas control. One commenter stated that control systems using hydrated lime are generally known to have increased HCl and HF removal when temperatures

As a result of these comments, we have eliminated the requirement for monitoring fabric filter inlet temperatures on affected kilns that are controlled with a DLS/FF or DIFF. We believe that the other monitoring requirements (e.g., lime feed rate monitoring and periodic VE checks) that we have incorporated into the final rule are adequate for ensuring continuous compliance with the emission limits.

#### 5. DLA Parameter Monitoring

Many commenters suggested potential parametric monitoring requirements for DLA that could be used to demonstrate continuous compliance. Various commenters suggested documenting use, on a continuous basis, of the same limestone that was used during the performance test demonstrating compliance. Other suggestions included monitoring pressure drop (demonstrating airflow); limestone flow; and inlet and/or exhaust gas temperature.

We have incorporated parameter monitoring requirements for DLA into the final rule based on information provided by commenters and a recent

site visit to a facility operating a DLA. Today's final rule will require owners and operators of affected kilns with DLA to continuously monitor the pressure drop across the DLA; perform a daily visual check of the limestone hopper and storage bin (located at the top of the DLA), and record the limestone feeder setting daily; and perform periodic VE observations. In addition, owners and operators will be required to document the source of the limestone used during the most recent performance test and maintain records that demonstrate that the source of limestone has not changed.

# 6. Continuous Emission Monitoring Systems

In the preamble to the proposed rule, we requested comment on requiring the application of PM continuous emission monitoring systems (CEMS) as a method to assure continuous compliance with the proposed PM emission limits for BSCP tunnel kilns. While we believe there is evidence that PM CEMS should work on BSCP tunnel kilns, we received no comments in support of requiring PM CEMS. Commenters opposed use of CEMS when less expensive, but effective, parametric monitoring alternatives are available. Therefore, today's final rule does not require use of PM CEMS or any other type of CEMS. We believe that the parameter monitoring requirements specified in the final rule are adequate for ensuring continuous compliance.

# 7. Establishing/Re-Establishing Production Rate

Several commenters requested that the process weight threshold be based on average annual throughput instead of hourly or monthly throughput. One commenter pointed out that the nature of brick production does not allow for spikes in emissions. Several commenters stated that the averaging period used to determine the MACT floor applicability to existing tunnel kilns must have the same production averaging basis as the data used in setting the subcategorization level. The commenters stated that it is not reasonable to base the standard on a 12month averaging period and then enforce the floor on an instantaneous or 30-day rolling averaging period.

One commenter requested clarification as to whether EPA would require a retest if the maximum production level of a kiln would be higher than the level observed during the performance test. The commenter added that several States recognize that capacity and maximum production are difficult figures to calculate for a brick tiln because they are highly dependent

on the specific characteristics of a product (size, percent void).

We agree with the commenters that a kilm's process weight threshold (e.g., design capacity level) should be based on average annual tonnage rather than on the proposed 30-day rolling average. We have revised the final BSCP rule accordingly to require the ton per hour production capacity of a kiln to be calculated based on the maximum amount of BSCP (in tons) that can be produced in a 12-month period divided by 8,760 hours per year.

 Regarding the question of whether we will require a retest if the maximum production level of a kiln is higher than the level observed during the performance test, a retest will be required because an increase in production is likely to increase emissions, and the operating limits that are based on the performance test would no longer demonstrate continuous compliance with the emission limits.

#### 8. Test Methods

One commenter requested that we allow any of the applicable EPA Method 5 variations to demonstrate compliance with the PM standard. The commenter pointed out that a facility with high SO<sub>2</sub> could reduce the potential for SO<sub>2</sub> to be counted as PM by using EPA Method 5B. We are not including EPA Method 5B as a test method because our emission limit is based on EPA Method 5 and includes tests on sources with high SO<sub>5</sub> emissions. Individual facilities wil! have the option of requesting an alternative test method.

One commenter on the proposed clay: ceramics rule requested that the final rule provide facilities with the option to use either EPA Method 26A or EPA Method 520 for all required stack testing for HF and HCl. This comment applies for both ESGP and clay ceramics. Therefore we have modified today's final ESCP rule to include EPA Method 300 at an afternative to EPA Method ......

H. Startus, Shutdown, and Maltunation. Total P. P. E. Birpano

Deteral commenters stated that the BSCP rule as proposed, would not allow the kitracontrol nevice to be bi passed at any time. Various commonters stated that the proposed MEATT controls (DIFF, DLS, FF, or WS) meet romatam a given flow to perioral efficiently. Thus, the APCD would dictate how the Limits operated During purtial kura startup or rubsequent latic startions or struttlewing birthov temperatures and volumes would be action at PCE decien volumes. The heat

from the furnace zone could damage the kiln walls and cars if not vented. Therefore, the ability to hypass during startups, routine maintenance, and emergency shutdowns of the APCD is meeded.

Several commenters noted that brick kilns are constant flow devices that cannot just be turned off without detrimental impact to large volumes of product (e.g., character, color, and quality of brick) and the kiln itself. The commenters stated that days to weeks may be needed to properly shut down a brick kiln. One commenter noted that kilns operate continuously 2 to 3 years before being shut down for routine maintenance.

Commenters stated that short periods of bypass are necessary to conduct routine preventive maintenance inspections of APCD. Commenters pointed out that the control devices currently employed have and use bypass capability for routine maintenance and emergency repairs.

We generally agree with the commenters that some provision is needed to allow the control device on tunnel kilns to be bypassed for routine maintenance of the control device, and we have revised the rule accordingly. Under 40 CFR 63.8420(e) of today's final rule, owners and operators of an affected tunnel kiln can bypass the kiln control device for a cumulative period of up to 4 percent of the annual operating hours for the kiln. Based on the data and other information submitted by commenters on the proposed rule, we believe that the amount of time equating to 4 percent of annua! kiln operating bours is adequate for completing routine maintenance on the types of controls that are likely to be used to comply with the BSCP NESHLAP

To comply with this bypass provision, owners of operators must submit a request to us for a routine control device. maintenance exemption. The request must justify the need for the routine maintenance on the control device and the time required to complete the maintenance activities. The request also must describe the maintenance activities and the frequency of the maintenance activities, e-gdain why the maintenance cannot be accomplished during Life shutdown; and describe now emissions will be minimized during the period when the Film is operating and the compolatevice at offline Upon approval, the request for exemption must be incorporated by releterate in and attached to the affected source stude V bormit During and remodivisen the aitr of operating and the later control asymptic offline

the owner or operator must minimize HAP emissions. The duration of such periods also must be minimized.

We also note that the bypass provision included in today's final rule does not apply to startups, shutdowns, or malhunctions 40 CFF, 63.6(f)(1) explicitly states that nonopacity emission standards, such as the proposed emission limits for HF, HCl, and PM, " \* apply at all times except during periods of startup, shutdown, and malfunction \* 🔭 \*'' Startups, shutdowns, and malfunctions must be addressed in a facility's SSMP.

#### 2. Initial Startup

Commenters stated that it is impractical to meet emission standards during initial startup of a tunnel kiln. The commenters indicated that it can take from weeks to a year to bring new BSCP kilns online. In addition, APCD such as DIFF, DLS/FF, or WS cannot be brought online until adequate temperature and airflow ranges are met. The commenters indicated that roughly 75 percent of design gas flow rate or kiln production rate must be obtained before a DIFF or DLS/FF could begin to operate properly. Another commenter stated that the

deadline (180 days following the compliance date) would not provide enough time for a new kiln to come up-

to-speed.

We recognize that an extended period of time may be needed for the initial startup of a new Juln and have added a definition of initial startup to the BSCP final rule to address the concerns expressed by the commenters. The definition differentiates between DLAcontrolled kilns and DIFF-, DLS/FF-, or WS-controlled kilns, because DLA are not sensitive to airflow and only require that the hiln gases are hot enough to avoid condensation in the DLA. Avoiding condensation is necessary because water and calcium carbonate (limestone) combine to make cement. and any introduction of water in the DLA reaction chamber could cause the limestone to be comented together. In the final rule, we provided the following definition: "Initial startup" means. (1) For a new or reconstructed tunnel frin controlled with a DLA, and for a tunnel Juln that would be considered reconstructed but for 40 CFP. 63.83906H11 or 46 CFF, 63.8390GP21 the time at which the temperature in the láth firm maches 160 °C (500 °F) and the ) the contains product or (2) for a new of reconstructed tunnel hith controlled with a DIFF, DLSTF, or WS, the time at which the lab, first reaches a level of production that is equal to 75 percent or the Libe design capacity of 12 months

after the affected source begins firing BSCP, whichever is earlier. Although some commenters suggested that initial startup for DIFF-, DLS/FF-, and WScontrolled kilns be defined in terms of airflow, we defined initial startup in terms of production rate for DIFF-, DLS/ FF-, and WS-controlled kilns because the final rule requires owners and operators of affected sources to monitor production rate, whereas flowrate monitoring is not required under today's final rule. We included the stipulation for DIFF-, DLS/FF-, and WS-controlled kilns that initial startup occurs no later than 12 months after the new kiln hegins firing BSCP to prevent facilities from operating an affected new or reconstructed kiln at just less than 75 percent of the kiln design capacity long term to circumvent the final rule. A similar stipulation is not necessary for DLA-controlled kilns because the kiln temperature requirement is such that the kiln cannot produce BSCP until well after the temperature is reached.

By defining initial startup in today's final rule, we also have clarified the compliance date for new and reconstructed sources, which is specified in terms of the initial startup. Thus, new and reconstructed DIFF-, DLS/FF-, and WS-controlled tunnel kilns beginning operation after the promulgation date will be allowed to reach 75 percent of the kiln design capacity before initial startup is triggered and the APCD must come online. New and reconstructed DLAcontrolled tunnel kilns, and tunnel kilns that would be considered reconstructed but for 40 CFR 63.8390(i)(1) or 40 CFR 63.8390(i)(2), beginning operation after the promulgation date will trigger initial startup when the temperature in the kiln first reaches 260°C (500°F) and the kiln contains product. Performance testing is required 180 days following the compliance date (i.e., 180 days following initial startup). Facilities wishing to conduct performance testing to determine the level of air pollution control necessary may conduct such testing prior to achieving initial startup.

#### 3. Startup

Two commenters expressed concern with how startup is defined with respect to the proposed rule. The commenters stated that, under the proposed rule, a kiln could be considered to be operating if only one burner was operating. However, a kiln could have as many as 100 burners or more. To clarify what constitutes kiln startup we added to today's final rule a definition of "startup" that incorporates "starting the production process."

#### 4. Deviations

One commenter felt that the requirement of reporting emissions as deviations during startup, shutdown, or malfunction (SSM) is inappropriate because facilities are not required to be in compliance with the emission limitations during SSM. Another commenter requested that EPA make it clear the deviations are not necessarily an indication of noncompliance or excess emissions.

The term deviation applies to events during which an affected source fails to meet an emission limitation or comply with another requirement of the final rule. Deviations are not synonymous with violations; depending on the circumstances, a deviation may or may not be a violation of an applicable requirement. We agree with the commenter that an affected source need not be in compliance with emission limits during periods of SSM. Although we consider non-compliance with emission limits during startup, shutdown, and malfunction to be deviations from the emission limits, we do not consider these deviations to be violations of the emission limits, 40 CFR 63.7(e)(1) specifies that, "Operations during periods of startup, shutdown, and malfunction shall not constitute representative conditions for the purpose of a performance test, nor shall emissions in excess of the level of the relevant standard during periods of startup, shutdown, and malfunction be considered a violation of the relevant standard unless otherwise specified in the relevant standard or a determination of noncompliance is made under 40 CFR 63.6(e)." As indicated in Table 7 of the final rule, this language of the general provisions to part 63 does apply to subpart IIII. The definition of deviation included in today's final rule is consistent with how deviation is defined in other NESHAP, and has not been changed since proposal.

#### I. Risk-Based Approaches

The preamble to the proposed BSCP rule requested comment on whether there might be further ways to structure the BSCP rule to focus on the facilities which pose significant risks and avoid the imposition of high costs on facilities that pose little risk to public health and the environment. Specifically, we requested comment on the technical and legal viability of two risk-based approaches: (1) An applicability cutoff for threshold pollutants under the authority of CAA section 112(d)(4), and (2) subcategorization and delisting under the authority of CAA sections.

112(c)(1) and 112(c)(9). We indicated that we would evaluate all comments before determining whether either approach would be included in the final BSCP rule. Numerous commenters submitted detailed comments on these risk-based approaches. These comments are summarized in the BSCP Response-to-Comments document (see SUPPLEMENTARY INFORMATION section).

Based on our consideration of the comments received and other factors, we have decided not to include the risk-based approaches in today's final BSCP rule. The risk-based approaches described in the proposed BSCP rule and addressed in the comments we received raise a number of complex issues. In addition, we are under time pressure to complete the BSCP rule,

promulgation has passed and a deadline suit has been filed against EPA. (See Sierra Club v. Whitman, Civil Action No. 1:01CV01537 (D.D.C.).) Given the range of issues raised by the risk-based approaches and the need to promulgate a final rule expeditiously, we believe that it is appropriate not to include any risk-based approaches in today's final BSCP rule. Nonetheless, we expect to continue to consider risk-based approaches in connection with other proposed NESHAP where we have described and solicited comment on such approaches. Finally, while we are not including risk-based approaches in today's final BSCP rule, we have included a number of other measures that we expect will reduce the costs and burdens on the affected sources.

#### UI. Summary of the Final Brick and Structural Clay Products Manufacturing NESHAP

A. What Source Category Is Regulated by the Final Rule?

Today's final rule for BSCP manufacturing applies to BSCP manufacturing facilities that are, are located at, or are part of, a major source of HAP emissions. The BSCP manufacturing source category includes those facilities that manufacture brick (including, but not limited to, face brick. structural brick, and brick pavers); clay pipe, roof tile; extruded floor and wall tile; and/or other extruded, dimensional clay products. Brick and structural clay products primarily are produced from common clay and shale. Production of BSCP typically consists of processing and handling the raw materials, forming

<sup>\*</sup>See 68 FR 1276 (January 9, 2003) IPLywood and Composite Wood Froducts Proposed NESHAP) and docket number A=98-44, Hem No. II=II=525 (White papers submitted to EPA outlining the rist based approaches).

and cutting bricks and shapes, and drving and firing the bricks and shapes. One by-product of brick manufacturing is crushed brick, which is produced at some facilities by crushing reject bricks.

There are a total of 189 domestic BSCP manufacturing facilities: 170 of these facilities primarily produce brick, and 19 of these facilities primarily produce structural clay products. The 189 BSCP manufacturing facilities are located in 39 States and are owned by 89 companies. Seventy-six of the companies are small businesses, and these 76 companies own 92 of the BSCP manufacturing facilities. Thirteen of the companies are large businesses, and these 13 companies own 97 BSCP manufacturing facilities.

All ESCP are fired either in continuous (tunnel or roller) or batch (periodic) kilns. Because the vast majority of continuous kilns are tunnel kilns, continuous kilns, including roller kilns, will be referred to as tunnel kilns for the remainder of this preamble. A total of 314 permitted and operable tunnel kilns were reported by industry; 302 of these kilns are located at facilities that are estimated, based on uncontrolled emissions, to be major sources. Of the 302 tunnel kilns located at major sources, 275 are located at brick manufacturing facilities and 27 are located at structural clay products manufacturing facilities. A total of 227 permitted and operable periodic kilns were reported by industry; 164 of these kilns are located at facilities that are estimated to be major sources. Of the 164 periodic kilns located at major. sources, 81 are located at brick manufacturing facilities and 83 are located at structural clay products manufacturing facilities.

The primary HAP emissions sources at BSCP manufacturing plants are tunnel Films and periodic Eilns, which emit HF HCl, and HAP metals. Lilns also emit PM and SO<sub>5</sub>, Other sources of HAP emissions at BSCP manufacturing plants are the raw material processing and handling equipment. The APCD that are used by the industry to control emissions from Eilns module DIFF DLS FF DLA, WS, and fabric filters.

#### B. What Are the inflected Sources?

The crusting affected source which is the portion of each source in the category for vinich we are setting emission standards, it any existing large tunnel kiln. Large tunnel kilns have a design capacity equal to or greater than 9 of the fact (10 tiph) of fixed product. Such tunnel kilns have a fixed by nature, get or other fixed, including say out. Cowden fixed, including say out. Cowden fixed tipically involves us use of a saydast driver

because sawdust typically is purchased wet and needs to be dried before it can be used as fuel. Consequently, some sawdust-fired tunnel hilps have two process streams, including: A process stream that exhausts directly to the atmosphere or to an APCD, and a process stream in which the kilm exhaust is ducted to a sawdust dryer where it is used to dry sawdust before being emitted to the atmosphere.

Today's final rule focuses on those process streams from existing large tunnel kilns that exhaust directly to the atmosphere or to an APCD. For existing large tunnel kilns that do not have sawdust drivers, the kiln exhaust process stream (i.e., the only process stream) is subject to the requirements of today's final rule. In accordance with CAA section 112(d)(1), we have divided tunnel kilns that duct exhaust to sawdust dryers into two classes for purposes of regulation. For existing large tunnel kilns that ducted exhaust to sawdust dryers prior to July 22, 2002. only the process stream that is emitted directly to the atmosphere or to an APCD is subject to the requirements of today's final rule; any process stream from such kilns that is ducted to a sawdust dryer is not subject to those. requirements.

By contrast, for existing large tunnel kilns that first duct exhaust to sawdust dryers on or after July 22, 2002, all of the exhaust (i.e., both the process stream that is emitted directly to the atmosphere or to an APCD and the process stream that is ducted to a sawdust dryer) is subject to the same level of control requirement as a new tunnel kilm.

In addition, each new or reconstructed tunnel Liln is an affected source and all process streams from new or reconstructed tunnel lulus are subject. to the requirements of today is final rule. The requirements of today's final rule for new and reconstructed turnel kilns are different for small and large hilms. Small tunne! hilns have design capacitie, les that 9.07 Mg/ht 110 tph) of fired product, and large tunnel kilns. have design capacities equal to or greater than 9.07 Fig hr (10 tph) of fired product A source is a new affected sour enflagnstruction becam on or after July 22, 2002. An affected source is reconstructed if the contents defined in 40 CFR 65.2 are niet as qualified by 40. CFR (a strong) An affected course is erusting if it is not new or reconstructed.

An elacting tunnel with with a foderally enforceable permit condition, that restricts I thin operation to less than 9.07 Mg for (to sphi) of fired production an amount trends basis is risk subject to the requirement, of today is final survival.

Hilms that are used exclusively for R&D and not used to manufacture products for commercial sale, except in a deminimis manner, are not subject to the requirements of today's final rule. Finally, kilms that are used exclusively for setting glazes on previously fired products are not subject to the requirements of today's final rule.

C. When Must I Comply With the Final Rule?

Existing affected sources must comply within 3 years of May 16, 2003. New and reconstructed affected sources with an initial startup before May 16, 2003 must comply no later than May 16, 2003. New and reconstructed affected sources with an initial startup after May 16, 2003 must comply upon initial startup. Existing area sources that subsequently become major sources have 3 years from the date they become major sources to come into compliance. Any portion of existing facilities that become new or reconstructed major. sources and any new or reconstructed area sources that become major sources must be in compliance upon initial startup.

#### D. What Are the Emission Limits?

Today's final rule includes emission limits in the form of production-based mass emission limits and percent reduction requirements. In establishing the HAF emission limits, we selected PM as a surrogate for HAP metals (including mercury in particulate form). Today's final rule contains HF, HCl, and PM emission limits for existing new. and reconstructed affected sources at ESCP manufacturing facilities, as well as for the following affected sources that would be considered reconstructed but for 40 CFP 63.8390(i) Existing small tunnel kilns whose design capacity is increased such that it is equal to or greater than 9.0° Mg/hr 110 tph) of fired product or exasting large DLA-controlled lulas.

If you own or operate an existing large tunnel kiln, a new or reconstructed small tunnel bild, an existing small bild that is rebuilt such that it becomes a large failm, or an existing large DLAcontrolled bills that is rebuilt, you must meet an HF emission limit of 0.0294 g Mg (0.057 lb ton) of fired product or reduce uncontrolled HF emissions by at least 90 percent for aftected process streams. You must meet an HCl emission limit of 0.13 kg I fg (0.26 lb. tons of fired product or reduce uncontrolled HCI emissions by at least 30 percent. You are required to meet a Pisi cranssion limit of 0 2 r hg/i ig to 42 Ib tone of free product.

If you own or operate a new or reconstructed large tunnel kiln, you must meet an HF emission limit of 0.029 kg/Mg (0.057 lb/ton) of fired product or reduce uncontrolled HF emissions by at least 90 percent for all process streams. You must meet an HCl emission limit of 0.028 kg/Mg (0.056 lb/ton) of fired product or reduce uncontrolled HCl emissions by at least 85 percent. You are required to meet a PM emission limit of 0.060 kg/Mg (0.12 lb/ton) of fired product.

#### E. What Are the Operating Limits?

In addition to the emission limits, today's final rule includes operating limits that apply to APCD used to comply with the final rule. The operating limits require you to maintain certain process or APCD parameters within levels established during performance tests. Each facility affected by today's final rule is required to prepare, implement, and revise, as necessary, an OM&M plan. The OM&M plan generally specifies the operating parameters to be monitored; the frequency that parameter values will be determined; the limits for each parameter; procedures for proper operation and maintenance of APCD and monitoring equipment; procedures for responding to parameter deviations; and procedures for documenting compliance.

We have established operating limits for DLA, DIFF, DLS/FF, and WS. If you operate a DLA, you must maintain the average pressure drop across the DLA for each 3-hour block period at or above the average pressure drop established during the performance test. You also must maintain an adequate amount of limestone in the limestone hopper, storage bin (located at the top of the DLA), and DLA at all times. In addition, you must maintain the limestone feeder setting at or above the level established during the performance test and you must use the same grade of limestone from the same source as was used during the performance test. Finally, you must maintain no VE from the DLA

If you operate a DIFF or DLS/FF, you must maintain free-flowing lime in the feed hopper or silo and to the APCD at all times and maintain the feeder setting at or above the level established during your performance test. In addition, you have the option of using a bag leak detection system or monitoring VE. If you use a bag leak detection system, you must initiate corrective action within 1 hour of a bag leak detection system alarm and complete corrective actions according to your OM&M plan, and operate and maintain the labels filter

such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month reporting period. If you monitor VE, you must maintain no VE from the DIFF or DLS/ FF stack.

If you operate a WS, you are required to maintain the average scrubber pressure drop, the average scrubber liquid pH, the average scrubber liquid flow rate, and the average chemical addition rate, if applicable, for each 3-hour block period at or above the average values established during your

performance test.

If you own or operate an affected source equipped with an alternative APCD or technique not listed in the rule, you must establish operating limits for the appropriate operating parameters subject to prior written approval by the Administrator as described in 40 CFR 63.8(f). You are required to submit a request for approval of alternative monitoring procedures that includes a description of the alternative APCD or technique, the type of monitoring device or procedure that you would use, the appropriate operating parameters that you would monitor, and the frequency that the operating parameter values would be determined and recorded. You must establish site-specific operating limits during your performance test based on the information included in the approved alternative monitoring procedures request. You are required to install, operate, and maintain the parameter monitoring system for the alternative APCD or technique according to your OM&M plan.

# F. What Are the Performance Test and Initial Compliance Requirements?

We are requiring owners and operators of all affected sources to conduct an initial performance test using specified EPA test methods to demonstrate initial compliance with the emission limits. A performance test must be conducted before renewing your 40 CFR part 70 operating permit or at least every 5 years following the initial performance test, as well as when an operating limit parameter value is being revised. You must test at the outlet of the APCD and prior to any releases to the atmosphere for all affected sources. If meeting the percent reduction emission limits for HF or HCl, you must also test at the APCD inlet. You must conduct each test while operating at the maximum production level.

Under today's final rule, you are required to measure emissions of HF, HCl, and PM. You must measure HF and HCl emissions using EPA Method 26A 2Determination of Evdrogen Halide and Halogen Emissions from Stationary Sources-Isokinetic Method," 40 CFR part 60, appendix A, or any other alternative method that has been approved by the Administrator under 40 CFR 63.7(f) of the general provisions. The EPA Method 26, "Determination of Hydrogen Chloride Emissions from Stationary Sources," 40 CFR part 60, appendix A, may be used when no acid particulate matter (e.g., HF or HC) dissolved in water droplets emitted by sources controlled by a WSI is present. As an alternative to using EPA Methods 26A or 26, you may measure HF and HCl emissions using EPA Method 320 "Measurement of Vapor Phase Organic and Inorganic Emission by Extractive FTIR" 40 CFR part 63, appendix A. When using EPA Method 320, you must follow the analyte spiking procedures of section 13 of Method 320 unless you can demonstrate that the complete spiking procedure has been conducted at a similar source. Particulate matter emissions must be measured using EPA Method 5, "Determination of Particulate Emissions from Stationary Sources," 40 CFR part 60, appendix A, or any other approved alternative method.

To determine initial compliance with the production-based mass emission limits for HF, HCl, and PM, you must calculate the mass emissions per unit of production for each test run using the mass emission rates of HF, HCl, and PM and the production rate (on a fired-product basis) measured during your performance test. To determine initial compliance with any of the percent reduction emission limits, you must calculate the percent reduction for each test run using the mass emission rates, measured during your performance test, of the specific HAP (HF or HCl) entering

and exiting the APCD.

Prior to your initial performance test, you are required to install the CMS (e.g., continuous parameter monitoring system) equipment to be used to demonstrate continuous compliance with the operating limits. During your initial test, you must use the CMS to establish site-specific operating parameter values that represent your

operating limits.

If you operate a DLA, you must continuously measure the pressure drop across the DLA during the performance test and determine the 3-hour block average pressure drop. You also must maintain an adequate amount of limestone in the limestone hopper, storage bin (located at the top of the DLA), and DLA at all times. In addition, you must establish your limestone feeder setting one week prior to the performance test and maintain the feeder setting for the one-week period

that precedes the performance test and during the performance test. Finally, you are required to document the source and grade of the limestone used during

the performance test.

If you operate a DIFF or DLS/FF, you are required to ensure that lime in the feed hopper or silo and to the APCD is free-flowing at all times during the performance test, and you are required to record the feeder setting for the three test runs. If the lime feed rate varies. you are required to determine the average feed rate from the three test runs. If you use a bag leak detection system, you must submit analyses and supporting documentation demonstrating conformance with EPA guidance and specifications for bag leak detection systems.

If you operate a WS, you are required to continuously measure the scrubber pressure drop, the scrubber liquid pH. the scrubber liquid flow rate, and the chemical addition rate (if applicable). For each WS parameter, you are required to determine and record the average values for the three test runs and the 3-hour block average value.

### G. Wha! Are the Continuous Compliance Requirements?

Today's final rule requires that you demonstrate continuous compliance with each emission limitation that applies to you. You must follow the requirements in your OMEM plan and document conformance with your OM&M plan. You are required to operate a CMS to monitor the operating parameters established during your initial performance test as described in the following paragraphs. The CMS must collect data at least every 15 minutes, and you need to have at least three of four equally spaced data values for at least 75 percent if you collect more than four data values per hourt perhour that including startup, shutdown. malfunction, out-of-control periods, or periods of routine control device maintendice covered by a routine. control device maintenance exemption). to have a valid hour of data. You must operate the CMS at all times when the process in operating. You also have to conduct proper maintenance of the CMS including inspections. calibrations, and validation checks, and maintain an inventory of necessary parts. for routine repairs of the CMS. Using the segorded readings, you must calculate. and record the C-hour block average. varues of each operating parameter. To calculate the atterned for each 1-hour. averaging period is on most mave at least. \*\* neigen; of the resonant readings for ant period that including startut . sautdayn, malfanction out-of-control

periods, or periods of routine control device maintenance covered by a routine control device maintenance

exemption). If you operate a DLA, you must collect and record data documenting the DLA pressure drop and reduce the data to 3hour block averages. You must maintain the average pressure drop across the DLA for each 3-hour block period at or above the average pressure drop established during the performance test. You also must verify that the limestone hopper, storage bin (located at the topof the DLA), and DLA contain an adequate amount of limestone by performing a daily visual check of the limestone hopper and the storage bin. and if the hopper or storage bin do not contain adequate limestone you must promptly initiate and complete corrective actions according to your OM&M plan. You also must record the limestone feeder setting daily to verify that the feeder setting is being maintained at or above the level established during the performance test. You also must use the same grade of limestone from the same source as was used during the performance test and maintain records of the source and type of limestone. Finally, you must perform daily, 15-minute VE observations in accordance with the procedures of EFA Method 22, "Visual Determination of Fugitive Emissions from Material Sources and Smoke Emissions from Flares," 40 CFF, part 60, appendix A. During the VE observations, the Eiln must be operating under normal conditions. If VE are observed, you must promptly initiate and complete corrective actions according to your CIMEM plan If no VE are observed in 30 consecutive daily EPA Method 22 tests, you may decrease the frequency of EPA Method 22 testing from daily to weeldy for that kith stack. If VE are observed during any weekly test, you must promptly initiate and complete. corrective actions according to your Cikilahi plan and you must resume EPA Method 22 testing of that Libs stack on a daily hasis until no VE are observed in 34 consecutive daily tests at which time you moviagain or prease the frequency of EPA Method L2 testing to a weer,by basis.

For DIFF and DLS FF systems, you must maintain free-flowing lime in the feed hoppe; or sile and to the APCII at all times. If lime is found not to be free flowing the dupor of a load cell. carrier gas hone flow indicator, carrier cas presourciding measurement system. or other system you must promptly initiate and complete corrective actions recording it court Mataly plan. You also have to assumating the frequence setting of or

above the level established during your performance test and record the feeder setting once each shift. If you use a bag leak detection system you must initiate corrective action within 1 hour of a bag leal, detection system alarm and complete corrective actions according to your OM&M plan. You also must operate and maintain the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period. In calculating this operating time fraction, if inspection of the fabric filter demonstrates that no corrective action is required, no alarm time is counted. If corrective action is required, each alarm must be counted as a minimum of 1 hour, and if you take longer than 1 bour to initiate corrective action, the alarm time must be counted as the actual amount of time taken to initiate corrective action. As an alternative to using a bag leak detection system, you may monitor VE. If you choose to monitor VE, you must perform daily, 15-minute VE observations in accordance with the procedures of EPA Method 22. During the VE observations, the kiln must be operating under normal conditions. If VE are observed, you must promptly initiate and complete corrective actions according to your OM&M plan. If no VE are observed in 30 consecutive daily EPA Method 22 tests, you may decrease the frequency of EPA Method 22 testing from daily to weekly for that kiln stack...If VE are observed during any weekly test, you must promptly initiate and complete corrective actions according to your OM&M plan and you must resume EPA Method 22 testing of that kilm stack on a daily basis until no VE are observed. in 30 consecutive daily tests, at which time you may again decrease the frequency of EPA Method 22 testing to a weel.ly basis.

For WS, you are required to continuously maintain the 3-hour block averages for scrubber pressure dropscrubber liquid pH | scrubber liquid flow rate, and chemical addition rate (ii applicable) at or above the minimum. values established during your performance test.

#### H What Are the Notification. Recordinecting and Reporting Requirements?

We are requiring owners and operators of all affected sources to submit mittal notifications, notifications of performance tests, and nonfolations of compliance status by the specifical dates in the final rule, which may vary depending on whether the affected source in new or exacting the addition to the information specified in 40% CF.

63.9(h)(2)(i), you are required to include the following in your notification of compliance status: (1) The operating limit parameter values established for each affected source (with supporting documentation) and a description of the procedure used to establish the values. and (2) if applicable, analysis and supporting documentation demonstrating conformance with EPA guidance and specifications for bag leak detection systems.

We are requiring owners and operators of all affected sources to submit semiannual compliance reports containing statements and information concerning emission limitation deviations, out-of-control CMS, periods of startup, shutdown, or malfunction. when actions consistent with your approved SSMP were taken, and periods of routine control device maintenance for facilities obtaining a routine control device maintenance exemption. In addition, if you undertake an action that is inconsistent with your approved SSMP, then you are required to submit a startup, shutdown, and malfunction report within 2 working days of starting such action and within 7 working days of ending such action unless you have made alternative arrangements with the

permitting authority.

We are requiring owners and operators of all affected sources to maintain records for at least 5 years from the date of each record. You must retain the records onsite for at least the first 2 years but may retain the records offsite for the remaining 3 years. You are required to keep a copy of each notification and report, along with supporting documentation. You are required to keep records related to the following: (1) Records of startup, shutdown, or malfunction; (2) records of performance tests; (3) records to show continuous compliance with each emission limitation; (4) if a bag leak detection system is used, records of each bag leak detection system alarm, including the time of the alarm, the time corrective action was initiated and completed, and a description of the cause of the alarm and the corrective action taken; (5) if VE measurements are taken, records of VE observations; (6) records of each operating limit parameter value deviation, including the date, time, and duration of the deviation, a description of the cause of the deviation and the corrective action taken, and whether the deviation occurred during a period of startup, shutdown, or maifunction; (7) records of routine control device maintenance for facilities obtaining a routine control device maintenance exemption, including a copy of the approved

request for a routine control device maintenance exemption; (8) records of production rate; (9) records for any approved alternative monitoring or test procedures; and (10) current copies of your SSMP and OM&M plan, including any revisions, with records documenting conformance.

#### IV. Summary of Environmental, Energy, and Economic Impacts for the Final **Brick and Structural Clay Products** Manufacturing NESHAP

## A. What Are the Air Quality Impacts?

At the current level of control and 1996 production levels, nationwide emissions of HAP from the 169 BSCP facilities estimated to be major sources are about 6,000 Mg/yr (6,600 tpy). Under today's final rule, it is assumed that DLA will be installed on 89 tunnel kilns with production capacities equal to or greater than 9.07 Mg (10 tph)(that currently are not controlled with a DLA, DIFF, DLS/FF, or WS). This will result in an estimated reduction in nationwide HAP emissions of 2,100 Mg/yr (2,300 tpy).

Hydrogen fluoride emissions account for approximately 60 percent of the baseline HAP emissions. Hydrogen chloride emissions account for approximately 40 percent, with HAP metals comprising less than 1 percent of the baseline HAP emissions. Estimated nationwide emissions of HF, HCl, and HAP metals from existing major source BSCP facilities at the current level of control are 3,500 Mg/yr (3,900 tpy), 2,400 Mg/yr (2,600 tpy), and 24 Mg/yr (26 tpy), respectively. Implementation of today's final rule is estimated to reduce nationwide HF emissions from existing tunnel kilns by about 1,700 Mg/ yr (1,900 tpy), and HCl will be reduced by 350 Mg/yr (390 tpy). Emissions of HAP metals are estimated to be reduced by 5.4 Mg/yr (5.9 tpy). Implementation of today's final rule also is estimated to reduce PM and SO<sub>2</sub> emissions by 740 Mg/yr (820 tpy) and 2,500 Mg/yr (2,800 tpy), respectively.

To project air quality impacts for new sources, we assumed that two large model tunnel kilns (each with a 13.6 Mg/hr (15 tph) capacity and equipped with DIFF) and one medium model tunnel kiln (with an 8.2 Mg/hr (9 tph) capacity and equipped with a DLA). will begin operation at the beginning of the first year following promulgation. We estimate that by implementing today's final rule, HF emissions from new sources will be reduced by 87 Mg/ yr (96 tpy), HCI emissions will be reduced by 47 Mg/yr (52 Ipv), and HAP metals emissions will be reduced by 0.48 Mg'yr (0.53 thy). We also estimate

that PM and SO2 emissions from the new kilns will be reduced by 67 Mg/yr (74 tpy) and 170 Mg/yr (190 tpy), respectively.

Secondary air impacts associated with today's final BSCP rule are direct impacts that result from the operation of any new or additional APCD. The generation of electricity required to operate the APCD on new and existing kilns will result in 11 Mg/yr (12 tpy) of nitrogen oxides (NO<sub>x</sub>) emissions in the first year following compliance with today's final rule. The electricity is assumed to be generated by natural gasfired turbines.

#### B. What Are the Water and Solid Waste Impacts?

Because compliance with today's final rule is based on the use of DLA or DIFF, no water pollution impacts are estimated. However, facilities with available wastewater disposal options may choose to use wet scrubbers. Based on available information, each scrubberconvolled kiln could generate as much as about 5 million gallons per year of waste water (based on a 10 gallon per minute scrubber blowdown, which is the maximum permitted amount in the industry).

The solid waste disposal impacts that result from the use of DLA include the disposal of the spent limestone that is discharged from the DLA. We calculated the solid waste by taking the difference between the amount of limestone charged into the DLA and the amount of reacted limestone and then adding the amount of reaction products and PM captured. Implementation of today's final rule is estimated to increase solid waste from existing sources by 65,200

Mg/yr (71,900 tpy). To project solid waste impacts for new sources, we assumed that two large model tunnel kilns (equipped with DIFF) and one medium model tunnel kiln (equipped with a DLA) will begin operation at the beginning of the first year following promulgation of the final rule. The analysis of solid waste from DLA is discussed in the previous paragraph. The solid waste disposal impacts that result from the use of DIFF include the disposal of the spent lime (or other sorbent) that is injected into the kiln exhaust stream and subsequently captured by a fabric filter. We calculated the solid waste by taking the difference between the amount of lime injected into the system and the amount of reacted lime, and then adding the amount of reaction products and PM. captured. Stoichiometric ratios of 1.0 to 22.0 have been reported for the DIFF and DLS/FF in use in the brick manufacturing industry. The average

stoichiometric ratio of 1.35 was used in this analysis. We estimate that implementing today's final rule will result in the generation of 1.410 Mg/yr (1.550 tpy) of solid waste from new sources

#### C. What Are the Energy Impacts?

Energy impacts consist of the electricity needed to operate the APCD. Electricity requirements are driven primarily by the size of the fan needed in the APCD. We estimate the increase to electricity consumption that will result from implementation of the final rule to be 89 terajoules per year (84 billion British thermal units (Btu) per year) for existing sources

To project energy impacts for new sources, we assumed that two large model tunnel kilns (equipped with DIFF) and one medium model tunnel kiln (equipped with a DLA) will begin operation at the beginning of the first year following promulgation of the final rule. We estimate the increase in energy consumption that will result from implementation of today's final rule to be 7.8 terajoules per year (7.4 billion Btu per year) for new sources.

# D. Are There Any Additional Environmental and Health Impacts?

Reducing HAP emissions under today's final rule will lower occupational HAP exposure levels. The operation of APCD may increase occupational noise levels.

#### E. What Are the Cost Impacts?

For existing sources, nationwide total capital costs to implement today's final rule are estimated at \$62 million, with total aunualized costs of \$24 million. The capital costs include the purchase and installation of DLA and monitoring equipment on 89 existing large tunnel lilns. The annualized costs include ammualized capital costs of the control and monitoring equipment, operation and maintenance expenses, emission. testing costs, and record/teeping and reporting costs associated with installing and operating these 89 DLA., as well as the monitoring, recordkeeping. and reporting, and emission testing cost: on 20 additional APCD that currently are installed on existing large tunnel Lilas.

To project costs for new sources, we assumed that two large model tunner laths, requipped with DIFF) and one medium monel tunner, but requipped with a DLAT will begin operation at the beginning of the first year following promulgation of the final rule. We estimate the capital costs associated with implementation of teacher than one to be \$1.8 million for these three

new sources. We estimate the annualized costs associated with implementation of today's final rule to be \$1.14 million per year for new sources in the first year following promulgation of the rule.

We calculated the cost estimates using cost algorithms that are based on procedures from EPA's Office of Air Quality Planning and Standards (CAQPS) Control Cost Manual (EPA 450/3–90–006, lanuary 1990) and cost information provided by the BSCP industry. We estimated costs by developing model process units that correspond to the various sizes of kilns found at BSCP manufacturing facilities and assigning the model process units to each facility based on the kiln sizes at each facility. The facility costs were summed to determine total industry costs.

#### F. What Are the Economic Impacts?

We conducted a detailed economic impact analysis to determine the market- and industry-level impacts associated with today's final rule. The compliance costs of today's final rule are expected to increase the price of brick and reduce their domestic production and consumption. We project the price of brick to increase by just less than 1 percent and project no change in price for structural clay products. Domestic production of brick is expected to decline by close to 1 percent in addition, foreign brick imports are estimated to increase while exports decrease, both by just under 1 percent. Since there is no expected change in the price of structural clay products, we predict no change in domestic production or foreign imports of structural clay products.

In terms of industry impacts, the brid producers are projected to experience a decrease in operating profits of about 10. percent, which reflects the compliance costs associated with brief production. and the resulting reductions in revenues. due to the increase in the price of brick. and the reduced quantity purchased. Through the market impacts described above today's final rule would create both positive and negative financial emplace on facilities within the  ${
m BSGP}$ manufacturing industry. The majority of facilities, almost 71 percent are expected to experience profit increases with foday's final rule, however, there are some facilities projected to lose profits (about 20 percent). Furthermore, the economic impact analysis indicates that of the TAN EOCH manufacturing architective brick facilities are at red. of closure by automortoday's final rule whale name or the structural clasproduct fasinae are at tisk to clase

Based on the market analysis, the annual social costs of today's final rule are projected to be \$23.3 million. This differs from the annual engineering costs of today's final rule because the social costs account for producer and consumer behavior. These social costs are distributed across the many consumers and producers of brick. Since there are no price changes. occurring in the structural clay products market, the social costs of today's final rule are confined to the brick industry. The consumers of bricl, are expected to incur \$14.7 million in costs associated with today's final rule, with domestic consumers bearing \$14.6 million and foreign consumers bearing \$0.07 million. Brick producers, in aggregate, are expected to bear the remaining \$8.6 million annually in costs. Domestic producers incur \$8.67 million while foreign producers gain \$0.04 million annually.

We estimate that 15 new kilns will be built during the 5 years after promulgation of today's final rule. The total compliance costs associated with these kilns are projected to be less than 0.6 percent of the industry's value of shipments. The economic impact analysis estimated the impact of today's final rule on these new sources through a sensitivity analysis. According to that analysis, it is projected that anywhere from three to six of these new kilns will be delayed in coming on-line in the BSCP manufacturing industry due to today's final rule.

#### V. Summary of Responses to Major Comments and Changes to the Clay Ceramics Manufacturing Proposed NESHAP

In response to the public comments received on the proposed clay ceramics rule, we made several changes in developing today's final clay ceramics rule. The major comments and our responses and rule changes are summarized in the following sections. A more detailed summary can be found in the Response-to-Comments document which is available from several sources (see SUPPLEMENTARY INFORMATION section).

#### A Affected Source

#### 1. Subsisteponies of Clay Ceramics Hiller

We proposed two subcategories of clay ceramics fulno. Continuous (tunnel or roller) lulns and batch (periodic) lulns. Based on the public comments received regarding APCD applicability, as described in section V.C of this preunble, we revised the subcategorization structure for today's final rule. Today's final rule is based on

four subcategories of clay ceramics kilns: Ceramic tile or sanitaryware tunnel kilns with design capacities less than 9.07 Mg/hr (10 tph) of fired product, ceramic tile or sanitaryware tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) of fired product, ceramic tile roller kilns, and periodic kilns.

#### 2. R&D Kiln Definition

One commenter requested that we change the definition of research and development kiln so that it is consistent with the definition of R&D in section 112(c)(7) of the CAA and most other NESHAP. Therefore, today's final rule includes a revised definition of research and development kiln that is consistent with section 112(c)(7) of the CAA and other NESHAP.

#### Facilities Co-Located With Major Sources

Commenters indicated that considering a clay ceramics facility a major source because it is co-located with a major source (under a separate NESHAP) puts those facilities at a competitive disadvantage with competitors operating facilities that are not co-located. We understand these commenters' concerns. However, section 112 of the CAA requires us to regulate HAP emissions from all major source facilities, regardless of the processes or operations that make those facilities major sources. Thus, today's final rule applies for both co-located and stand-alone clay ceramics manufacturing facilities that are major

### B. Existing Source MACT

Four commenters concurred with the existing MACT floor of "no emissions reductions" for existing clay ceramics sources. To the contrary, one commenter charged that EPA has simply set MACT floors based on control technology type and that EPA did not identify the relevant best performers and set floors reflecting their average emission level. The commenter noted that factors other than control device type affect emissions and that EPA must consider all non-negligible factors in setting MACT floors and considering beyond-the-floor measures. The commenter stated that if EPA believes it is unworkable to consider all factors. then perhaps EPA should base standards on actual emissions data which reflects all the factors influencing a source's performance.

We reevaluated our existing source MACT determinations following proposal based on consideration of factors other than AFGD type. We agree

that factors other than APCD type (e.g., kiln design, fuel type, raw materials, additives and surface coatings) can affect emissions from clay ceramics kilns. We acknowledged the effect of kiln design on emissions by creating separate subcategories for periodic, roller, and tunnel kilns. We maintain that low-HAP raw material use is not a viable MACT option because, similar to the BSCP industry, all facilities use product-specific raw materials that are integral to the various products. Changes in raw materials would change the end products, and because of this, it would not be feasible for facilities to meet requirements based on the use of low-HAP raw materials. With respect to requiring kilns to fire low-HAP fuels, all clay ceramics kilns for which we have information are fired with natural gas or propane. Therefore, we are not concerned that a requirement to use natural gas (or equivalent fuel) to fire all existing kilns would have any impact on the end products of existing kilns, as would be the case in the BSCP industry. Therefore, the MACT floor for all existing clay ceramics periodic kilns, tunnel kilns, and roller kilns is based on firing the kilns with natural gas or an equivalent fuel (such as propane or other clean-hurning fuel), and we added a work practice standard to the final rule that covers this requirement. We considered developing emission limitations based on firing natural gas, but the available data are insufficient for us to determine the contribution of kiln fuel to HAP emissions, and we believe that a work practice standard is the only feasible means of addressing the commenter's concern that we did not consider options besides APCD use.

#### C. New Source MACT

At proposal, we concluded that MACT for new and reconstructed periodic kilns was "no emissions reductions." We concluded that MACT for new and reconstructed tunnel and roller kilns was the level of control achievable with a DIFF, DLS/FF, or WS because the best-controlled similar source (a BSCF turnel kiln) had this level of control.

Following proposal, several commenters argued that clay ceramics kilns are different from BSCP kilns, and that EPA should not consider BSCP tunnel kilns to be the best-controlled similar source. The commenters noted that clay ceramics kilns typically have much lower throughput than BSCP kilns and that the exhaust from clay ceramics kilns contains lower pollutant concentrations than BSCP kiln exhaust. Commenters stated that the lower pollutant concentrations in clay

ceramics kiln exhaust would result in the inability to achieve high removal efficiencies. The commenters suggested that the proposed control technologies are not transferable to clay ceramics kilns and noted that none of the technologies are currently in use on domestic clay ceramics kilns. The commenters suggested that the best-controlled similar source should come from the sources in the clay ceramics source category, which would result in a new source MACT floor of "no emissions reductions" for clay ceramics kilns.

One commenter stated that, whereas brick products are fired unglazed, most sanitaryware products have a ceramic glaze applied before firing, which melts in the kiln, evenly covering the surface of the piece, helping to seal the surface and hinder the emission of by-products typically associated with the clay raw material.

One commenter suggested that MACT for new clay ceramics kilns be applied only to large kilns (i.e., kilns with a design capacity equal to or greater than 9.07 Mg/hr (10 tph) of fired product). The commenter suggested (based on their conversation with an APCD vendor) that DIFF systems may not be readily available for small (less than 9.07 Mg/hr (10 tph)) clay ceramics kilns.

One commenter requested that EPA distinguish between ceramic tile tunnel and roller kilns. The commenter stated that the two major design differences between BSCP periodic and new BSCP tunnel kilns are the same dissimilarities exhibited between clay ceramics tunnel and roller kilns. The commenter also provided reasons why clay ceramics roller kilns are different from BSCP tunnel kilns. The commenter stated that BSCP tunnel kilns are made of brick lined with refractory materials, have a high profile (tall) design, and require setting and stacking product on rail cars which move on floor rails. Bricks are fired on a 15 to 24 hour cycle. Ceramic tile roller kilns are designed in modular units with a low (short) profile (which affects the excess airflow), have different firing curves and flow characteristics, process a single row of tile moved by roller, and utilize high velocity burners for turbulent airflow. The tiles are not stacked and are fired on a 40 to 60 minute cycle. The commenter stated that firing time has a significant effect on the evolution of HF emissions (roller kilns exhibit significantly lower HF emissions) and provided detail of firing curves/ emission estimates for the two types of Films. In addition, the commenter stated that APCD available for BSCP tunnel

kilns are not readily available for roller

We acknowledge that the control technologies (DIFF, DLS/FF, and WS) that formed the basis for the proposed emission limits for new and reconstructed clay ceramics kilns are not currently in use on any domestic clay ceramics kiln. However, section 112(d) of the CAA requires us to establish emission limits for new sources based on the performance of the best-controlled similar source. The CAA does not specify that the similar source must be within the same source category. To the contrary, our interpretation of section 112(d) of the CAA is that we are obligated to consider similar sources from other source categories in determining the bestcontrolled similar source for establishing MACT for new sources

We have reevaluated our subcategory and best-controlled similar source determinations for new and reconstructed clay ceramics kilns. We maintain that MACT for new and reconstructed periodic kilns does not require use of add-on APCD because the best-controlled similar source is uncontrolled. In addition, based on the comments received and other information, we have concluded that there are significant differences between clay ceramics tunnel kilns and roller lulns. We believe that differences in the operation of BSCP tunnel kilns and tile roller hilms, particularly with respect to the duration of firing, result in emission characteristics that are likely to be very dissimilar. As a result, we cannot assume that APCD that have been demoustrated to be effective for reducing HF and HCl emissions from BSCP tunnel kilns are feasible for tile roller Libs Therefore, we have concluded that BSCP tunnel kilns cannot be considered similar sources to tile roller hitms, and we have determined that NLACT for new and reconstructed clay ceramics tile roller. kilns doe: not include control with an add-თ. გPGD.

We disagree that there are recluiological differences between clay ceramics tunnel hilm and BSCF turnel. Films, Some tunnel Lilus actualiy produce both ceramic tile and structural clay the to structura, clay product). Regarding the effect of glazing on emissions, we cannot return that the glaces applied to sanitar twais form at seal that could prevent further release of certain pollutants from the body of the ware blowever we have no information. that indicates that the scaling becomes officialist actors HP and HD are released. To the contrary, we have data from several tests on canitaryware hims

that quantify HF emissions and the tests indicate that uncontrolled emissions are within the range emitted from BSCP kilms.

We maintain that the best-controlled similar source for a clay ceramics tunnel kiln is a BSGP tunnel kiln. As discussed in section II.D of this preamble, MACT for new and reconstructed BSCP tunnel kilns with design capacities less than 9.07 Mg/hr (10 tph) of fired product is based on use of a DLA, while MACT for new and reconstructed BSCP tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) of fired product is based on use of DIFF, DLS/ FF, or WS. Thus, we have adopted the same requirements for new and reconstructed clay ceramics tunnel kilns. New and reconstructed clay. ceramics tile and sanitaryware tunnel kilns with design capacities less than 9.07 Mg/hr (10 tph) of fired product will be required to meet emission limits based on the levels of control that can be achieved by a killo controlled with a DLA. The emission limits for HF are 0.029 kg/Mg (0.057 lb/ton) or at least 90 percent reduction. For HCl, the emission limits are 0.13 kg/Mg (0.26 lb/ ton) or at least 30 percent reduction. For PM, which is used as a surrogate for HAP metals, the emission limit is 0.21 kg/Mg (0.42 lb/ton). For new and reconstructed clay ceramics tile and sanitaryware tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) of fired product, we have revised the emission limits (based on the levels of control that can be achieved by a kiln controlled with a DIFF DLS/FF, or WS) to reflect new data that were considered in the development of the fina! BSCP rule, as discussed in section II.F of this preamble. The revised HF emission timpts are 0.029 i.g Mg (0.057 lb/ton) or at least 90 percent reduction. The revised HCI emission limits are 0.028 tig 1.4g to 056 lb from or at least 85. percent reduction. The PM emission limit remains unchanged (from proposali at trufacil g/lde tu 12 lb/toni.

Similar to the requirements for existing sources, we added a work practice standard that requires facilities to use natural gas, or an equivalent fuel. to fire all new or reconstructed clay ceramics periodic lillus, tunnel killus, and roller fallis, except during periods. of natural gar curtailment or other periodri when natiural gas is not

Similar to the requirements for BSCF turnel idlus, two types of clay cerainics tuanel him. How wome otherwise be considered in constructed do not need the definition of reconstruction in so-CFP of a We have a rate tonguage in40 CFR 63.8450(f) to provide that it is not technologically and economically feasible for these two types of existing kilns that would otherwise meet the criteria for reconstruction under 40 CFF. 63.2 to meet the relevant standardsi.e., new source MACT. The two types of kilns are existing tunnel kilns with design capacities less than 9.07 Mg/hr (10 tph) of fired product whose design capacities are increased such that they are equal to or greater than 9.07 Mg/hr (10 tpb) of fired product, and existing DLA-controlled tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) of fired product. These sources will be required to meet emission limits based on the levels of control that can be achieved by a kiln controlled with a DLA. They also will he subject to the work practice standard that requires facilities to use natural gas. or an equivalent fuel, to fire all kilms, except during periods of natural gas curtailment or other periods when

natural gas is not available.

We acknowledge that the higher airflow rates that are characteristic of clay ceramics kilns result in lower pollutant concentrations in the exhaust stream, and that control efficiency limits (or percentage reduction limits) are more difficult to achieve when exhaust gas concentrations are lower. For that reason, we proposed and are promulgating today production-based mass emission limits as alternatives to the HF and HCl percentage reduction limits. Exhaust gas concentrations have no effect on mass emission rates. provided the concentrations are above. the test method detection limit. The mass emission rate (e.g., pounds of pollutant emitted per hour) for a source. is unchanged regardless of how much dilution air is introduced. Therefore, even though a clay ceramics little with a diluted exhaust stream may not be able to meet the percentage HF and HCI reduction limits, the available data indicate that a kiln that is controlled to the new source MACT level will be able to meet the production-based emission limits for HF and HCL as well as the production-based limit for PLL

#### P. Cost and Economic Impacts

Several commenters stated that EPA underestimated the cost per top of pollutant removed at proposal. In general, the commenters left the costs were umeasonable. Commenters questions of the public health benefits of the proposed clay ceranics rule.

One continente: stated that EPA entirely musualterstood the economic state of the cecumic tile industry in the U.S., and therefore, grossly underestimated the economic impact of the proposed rule on the industry. The commenter challenged the assumptions presented in the algorithms on which the cost analysis is based, charging that they bear no reasonable relationship to reality in the industry and that the APCD strategies are not actually feasible for implementation. The commenter also argued that the economic analysis of the MACT floor for reconstructed and new ceramic clay roller kilns does not support. S/FF- or WS-based controls.

We acknowledge the commenters' statements about the high cost effectiveness of the proposed rule. As discussed previously, we have revised the rule, as proposed, such that it is now less costly. Under today's final rule, new clay ceramic roller kilns will not be subject to emission limits. In addition, we have subcategorized clay ceramics tunnel kilns by design capacity. New and reconstructed tunnel kilns with design capacities less than 9.07 Mg/hr (10 tph) of fired product and turnel kilns that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2) will be required to meet emission limits based on the levels of control that can be achieved by a DLA. In addition to the changes mentioned above, we have added a work practice standard that requires facilities to use natural gas, or an equivalent fuel, to fire all clay ceramics kilns, except during periods of natural gas curtailment or other periods when natural gas is not available. The costs associated with this change are minimal, Based on these changes, there will be no control cost for new roller kilns and the control cost for new and reconstructed tunnel kilns with design capacities less than 9.07 Mg/hr (10 tpl1) of fired product and tunnel kilns that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2) will be lower than at proposal. Most of the new tunnel kilus constructed will likely be in this smaller size category. New clay ceramics tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) are still required to meet emission limits based on the use of DIFF, DLS/FF or WS technologies. However, the HF and HCl emission limits are slightly less stringent than at proposal (due to the inclusion of new test data). The PM emission limit for new clay ceramics tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) is unchanged from the proposed requirements for all new kilns.

Public health benefits are likely to be realized due to the reduced emissions and reduced exposures to emissions as a result of today's final rule. However

we have not quantified these public health benefits because we are not required to do so under the CAA.

We disagree with the commenter's statement that the economic impacts of the rule on the ceramic tile industry have been grossly underestimated. Based on revisions to the final rule as described above, we expect minimal impacts on existing sources, based on recordkeeping and reporting costs associated with the work practice standard for existing kilns, and we estimate that only one new source will be impacted by the final rule in the first five years following promulgation. Therefore, the EIA at proposal overestimated the impacts on the industry. Thus, it is very unlikely that the one new source affected by the rule or the addition of a work practice standard that requires all kilns to be fired with natural gas (or equivalent fuel) will be able to influence industry prices or foreign competition.

#### E. Test Data and Emission Limits

One commenter implied that there are no data to suggest that HCl is emitted from ceramic tile kilns. Another commenter stated that limits for HCl and PM are irrelevant and that we should only set an emission limit for HF (the largest single HAP emitted from the kilns). The commenter believes that there is no need to establish an emission limitation for HCl or PM because any control system designed to achieve the required HF reduction will also reduce HCl and PM. One commenter disagreed that PM is an adequate surrogate for HAP metals emissions.

We are required by section 112(d) of the CAA to establish emission limits for listed HAP emitted from major sources. Section 112(b) of the CAA lists HCl and various HAP metals. We believe that PM is an adequate surrogate for HAP metals for the reasons discussed in section Il.F of this preamble.

We acknowledge that we have no test data that demonstrate that HCl is emitted from clay ceramics kilns. However, we do have data that show that chlorides are present in many clay materials, and that HCl is emitted from various types of clays when heated above a minimum temperature. The data include raw material analyses and emission test reports of HCl emissions for the BSCP manufacturing, lightweight aggregate manufacturing, and Laolin processing industries. Because of the cimilarities in raw materials used in those industries and the raw materials. used to manufacture clay ceramics, we assume that clay ceramica biles also ount HGl.

We agree that HF emission rates from clay ceramics kilns generally are greater than the corresponding emission rates for HCl or metal HAP. We also agree that emission controls that are used to meet the emission limits for HF are likely to reduce emissions of HCl and SO<sub>x</sub> as well. However, as stated previously, the CAA requires us to set emission limits for all listed HAP based on MACT. The data indicated that there are existing controls on similar sources that achieve significant reductions in emissions of HCl and PM (as a surrogate for metal HAP). Therefore, we are required to establish emission limits for HCl and metal HAP. We also note that, if HCl and PM emissions from any affected source are negligible or are automatically controlled by HF control devices, complying with the HCl and PM emission limits should not present a problem.

#### F. Monitoring Requirements

#### Fabric Filter Inlet Temperature

Two commenters disagreed with the proposed fabric filter inlet temperature monitoring requirement. One commenter stated that control systems using hydrated lime are generally known to have increased HCl and HF removal when temperatures increase. The other commenter suggested that the only limit on fabric filter inlet temperature should be based on manufacturer's specifications for protection of the equipment.

We have eliminated the requirement for monitoring fabric filter inlet temperatures on affected kilns that are controlled with a DLS/FF or DIFF. We believe that the other monitoring requirements (e.g., lime feed rate monitoring and periodic VE checks) that we have incorporated into today's final rule are adequate for ensuring continuous compliance with the

emission limits.

# 2. Bag Leak Detection Systems and Visible Emissions

One commenter suggested changes to the amount of bag leak detector alarm time that must be recorded. We have not changed the requirements for recording bag leak detection system downtime. However, we have incorporated into today's final rule an option for owners and operators of affected kilns that are controlled with a DLS/FF, or DIFF to perform daily VE checks rather than using bag leak detection systems. Visible emissions checks are required for DLA-controlled kilns. Today's final rule also includes a provision for decreasing the frequency of VE checks. provided no VE are observed.

# 3. Continuous Emissions Monitoring Systems

In the preamble to the proposed rule, we requested comment on requiring the application of PM CEMS as a method to assure continuous compliance with the proposed PM emission limits. Commenters opposed use of CEMS when less expensive, but effective, parametric monitoring alternatives are available. Therefore, today's final rule does not require use of PM CEMS or any other type of CEMS. We believe that the parameter monitoring requirements specified in the final rule are adequate for ensuring continuous compliance.

#### 4. Test Methods

One commenter requested that the final clay ceramics rule provide facilities with the option to use either EPA Method 26A or EPA Method 320 for all required stack testing for HF emissions. HCl emissions, or both. Because EPA Method 320 will provide accurate HF and HCl measurements, we have modified today's final clay ceramics rule to include EPA Method 320 as an alternative to EPA Method 26A.

#### G. Startup, Shutdown, and Molfunction

#### 1. Bypass

One commenter requested that EPA allow for use of the bypass stack during periods of APCD maintenance. Similar comments were received on the proposed BSCP rule. Therefore, today's final clay ceramics rule allows for bypass of the APCD during periods of routine control device maintenance for up to 4 percent of the annual kiln operating hours. Section II.H of this preamble presents details on use of this routine control device maintenance exemption.

#### 2. Initial Startup

Commenters on both the proposed HSGP rule and clay ceramics rule pointed out that it is impractical to meet emission standards during initial startup of a tunnel lilli. Thus, as discussed in section II.H of this preamble, we have added a definition of initial startup to today's final clay ceramics rule to address the concerns expressed by the commenters.

#### VI. Summary of the Final Clay Ceramics Manufacturing NESHAP

# A. What Source Category Is Resulated by the Final Rule!"

Today's final rule for day teramics manufact using another to also becomes more of atturing facilities that are lare retained at, or are part of a major source of HAP emissions. The clay extantics

manufacturing source category includes those facilities that manufacture pressed floor tile, pressed wall tile and other pressed tile; or sanitaryware (toilets and sinks). Clay ceramics are primarily composed of clay and shale, and may include many different additives, including silica, tale, and various high purity powders produced by chemical synthesis. Clay ceramics manufacturing generally includes raw material processing and handling and forming of the tile or sanitaryware shapes, followed by drying, glazing, and firing. Most clay ceramics are coated with a glaze prior to firing. The clay ceramics industry also includes dinnerware and pottery manufacturing, but these industry. segments are not covered by today's final rule because we determined that there are no dinnerware or pottery manufacturing facilities that are major sources of HAP.

Available information shows a total of 58 facilities that produce clay ceramics. Thirty-two of these facilities, located in 16 States, primarily produce pressed tile, while 26 of these facilities, located in 15 States, primarily produce sanitaryware. Eight of the 58 clay ceramics manufacturing facilities are estimated to be major sources. Thirteen clay ceramics facilities are owned by small businesses, and none of the small business-owned facilities are estimated to be major sources.

All clay ceramics are fired in kilns. Firing may be performed in one or more stages. Tile can be fired in either continuous (tunnel or roller) or batch (periodic) kilns, but most facilities use either tunnel or roller kilns for tile production. Periodic kilns are usually used at smaller facilities or are used primarily for second-firing a product after a glaze has been applied.

The sanitaryware industry uses either tunnel kilns or periodic Films for firing. Tunnel Lilns account for most sanitaryware firing, periodic Lilns are used primarily for refiring rejected pieces that have been repaired and reglared. Some smaller facilities use periodic kilns for all firing operations.

The primary HAP emission sources at clay deramics manufacturing plants are roller funnel and periodic filling which emit HF. HCl and HAP metals. Rulis also emit PM and SOs. Currently no APCD are used by the clay deramics industry to control emission from kins, although the industry is emission for kins, although the industry is emissions are trainfinized because the Filter fire clean forming finely, butter sources of HAP children is to be a clean terminal manufacturing points are the ray material protection and handling equipment.

#### B. What Are the Affected Sources?

The affected sources, which are the portions of each source in the category for which we are setting emission standards, include each existing, new, or reconstructed periodic kiln, tunnel kilm, and roller kiln. Each tunnel kiln that meets the description in 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2) also is an affected source. All affected sources are subject to the work practice standard in today's final rule. In addition, today's final rule contains different emission limits, based on design capacity, for new and reconstructed tunnel hilms, and also includes emission limits for tunnel kilns that would otherwise meet the criteria for reconstruction but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2). The tunnel kiln subcategories are tunnel hilms with design capacities less than 9.07 Mg/hr (10 tph) of fired product and tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) of fired product. Kilns that are used exclusively for R&D and not used to manufacture products for commercial sale, except in a de minimis manner, are not subject to the requirements of today's final rule. Hilns that are used exclusively for refiring or for setting glazes on previously fired products are not subject to the requirements of today's final rule.

A source is a new affected source if construction began on or after July 22, 2002. An affected source is reconstructed if the criteria defined in 40 CFR 63.2 are met, as qualified by 40 CFR 63.8540(f). An affected source is existing if it is not new or reconstructed and does not meet the descriptions in 40 CFP 63.8540(f). As indicated, affected sources described in 40 CFR 63.8540(f) also are subject to today's final rule.

# C. When Must I Comply With the Final Rule:

New and reconstructed affected sources and affected sources that would he considered reconstructed but for 40 CFR 63.8340(f)(1) or 40 CFR 60.8540(f)(2) with an initial starture before May 16, 2003 must comply no later than May 16, 2003. New and reconstructed affected sources and affected sources that would be considered reconstructed but for 40 CFP 63.8540(fit1) or 40 CFR 63.8540(fit1) with an initial startup after Iday 16, 2000 must comply upon initial startup. Any postion of existing facilities than become new or reconstructed imporsources and any new or reconstructed area sources that become major sources must be in compliance upon initial. Mariuj.

If you have an existing affected source, you must comply with the work practice standards within 3 years of May to, 2003.

#### D. What Are the Emission Limits?

Today's final rule includes emission limits in the form of production-based mass emission limits and percent reduction requirements. In establishing the HAP emission limits, we selected PM as a surrogate for HAP metals. including mercury in particulate form. Today's final rule includes HF, HCl, and PM emission limits for new and reconstructed affected sources at clay ceramics manufacturing facilities, as well as for the following affected sources that would be considered reconstructed but for 40 CFR 63.8540(f): Existing tunnel kilns with design capacities less than 9.07 Mg/hr (10 tph) of fired product whose design capacities are increased such that they are equal to or greater than 9.07 Mg/hr (10 tph) of fired product, and existing DLAcontrolled tunnel kilns with design capacities equal to or greater than 9.07 Mg/hr (10 tph) of fired product.

If you own or operate a new or reconstructed tunnel kiln with a design capacity less than 9.07 Mg/hr (10 tph) of fired product or a tunnel kiln that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2), you are required to meet an HF emission limit of 0.029 kg/Mg (0.057 lb/ton) of fired product or reduce uncontrolled HF emissions by at least 90 percent. You also are required to meet an HCl emission limit of 0.13 kg/ Mg (0.26 lb/ton) of fired product or reduce uncontrolled HCl emissions by at least 30 percent. Finally, you are required to meet a PM emission limit of 0.21 kg/Mg (0.42 lb/ton) of fired product.

If you own or operate a new or reconstructed tunnel kiln with a design capacity equal to or greater than 9.07 Mg/hr (10 tph) of fired product, you are required to meet an HF emission limit of 0.029 kg/Mg (0.057 lb/ton) of fired product or reduce uncontrolled HF emissions by at least 90 percent. You also are required to meet an HCl emission limit of 0.028 kg/Mg (0.056 lb/ton) of fired product or reduce uncontrolled HCl emissions by at least 35 percent. Finally, you are required to meet a PM emission limit of 0.06 kg/Mg (0.12 lb/ton) of fired product.

#### E. What Are the Operating Limits?

The operating limits for new and reconstructed day detained tunnel kilos and tunnel kilos that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2) are

the same as those for new and reconstructed BSCP tunnel kilns. These operating limits are presented in section III.E of this preamble.

# F. What Are the Work Practice Standards?

If you have an existing, new, or reconstructed clay ceramics periodic kiln. tunnel kiln, or roller kiln, or a tunnel kiln that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2), you must use natural gas, or an equivalent fuel, as the kiln fuel at all times except during periods of natural gas curtailment or other periods when natural gas is not available.

#### G. What Are the Performance Test and Initial Compliance Requirements for Sources Subject to Emission Limits?

The performance test and initial compliance requirements for new and reconstructed clay ceramics tunnel kilns and tunnel kilns that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2) are the same as those for new and reconstructed BSCP tunnel kilns. These requirements are presented in section III.F of this preamble.

#### H. What Are the Initial Gompliance Requirements for Sources Subject to a Work Practice Standard?

For each existing, new, or reconstructed clay ceramics periodic kiln, tunnel kiln, or roller kiln, and each tunnel kiln that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2), you must indicate, in your initial notification, that you use natural gas, or an equivalent fuel, as the kiln fuel, and certify that such information is true, accurate, and complete.

#### I. What Are the Continuous Compliance Requirements for Sources Subject to Emission Limits?

The continuous compliance requirements for new and reconstructed clay ceramics tunnel kilns and tunnel kilns that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2) are the same as those for new and reconstructed BSCP tunnel kilns. These requirements are presented in section III.G of this preamble.

#### J. What Are the Continuous Compliance Requirements for Sources Subject to a Work Practice Standard?

For each existing, new, or reconstructed clay ceramics periodic with, turnel kiln, or roller kiln, and each turnel kiln that would be considered.

reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2), you must use natural gas, or an equivalent fuel, as the kiln fuel, and document the type of fuel used. The type of fuel used, along with other compliance information, must be certified as part of your compliance reports. During periods of natural gas curtailment or other periods when natural gas is unavailable, you are allowed to use an alternative fuel. However, if you use an alternative fuel, you must meet the notification requirements specified in 40 CFR 63.8630(g) and the reporting requirements specified in 40 GFR 63.8635(g).

#### K. What Are the Notification, Recordkeeping, and Reporting Requirements for Sources Subject to Emission Limits?

The notification, recordkeeping, and reporting requirements for new and reconstructed clay ceramics tunnel kilns and tunnel kilns that would be considered reconstructed but for 40 GFR 63.8540(f)(1) or 40 GFR 63.8540(f)(2) are the same as those for new and teconstructed BSCP tunnel kilns. These requirements are presented in section III.H of this preamble.

#### L. What Are the Notification, Recordkeeping, and Reporting Requirements for Sources Subject to a Work Practice Standard?

If you operate an existing, new, or reconstructed clay ceramics periodic kiln, tunnel kiln, or roller kiln, or a tunnel kiln that would be considered reconstructed but for 40 CFR 63.8540(f)(1) or 40 CFR 63.8540(f)(2). you must submit an initial notification that indicates that you use natural gas, or an equivalent fuel, as the kiln fuel. You must keep records that document your kiln fuel, and if you must use an alternative fuel due to a natural gas curtailment or other interruption of natural gas supply, you must submit a notification of alternative fuel use that includes the information specified in 40 CFR 63.8630(g). You must submit a report of alternative fuel use within 10 working days after terminating the use of the alternative fuel. The report must include the information specified in 40 CFR 63.8635(g).

#### VII. Summary of Environmental, Energy, and Economic Impacts for the Final Clay Ceramics Manufacturing NESHAP

#### A. What Are the Air Quality Impacts?

Because the only requirements for existing sources under today's final rule

are work practice standards that we believe that all facilities are already meeting, no air quality impacts are projected for existing sources. To project air quality impacts for new sources, we assumed that one samtaryware tunnel Lib (3.6 Mg/hr (4 tph) capacity) equipped with a DLA will begin operation at the beginning of the first year following promulgation of the rule. We estimate that by implementing the rule. HF emissions from this new source will be reduced by 4.9 Mg/yr (5.4 tpy). HCl emissions will be reduced by 1.0 Mg/yr (1.1 tpy), and HAP metals emissions will be reduced by 0.028 Mg/ ут (0.031 tpy). We also estimate that PM and SCI, emissions from the new kiln will be reduced by 3.9 Mg/yr (4.3 tpy) and 13 Mg/yr (14 tpv), respectively.

Secondary air impacts associated with today's final clay ceramics rule are direct impacts that result from the operation of any new APCD. The generation of electricity required to operate the control device on the projected new kiln will result in 0.09 the of NO<sub>X</sub> emissions in the first year following promulgation of the rule. The electricity was assumed to be generated by natural gas-fired turbines.

# B. What Are the Water and Solid Waste Impacts?

Because the only requirements for existing sources under today's final rule are work practice standards that we believe that all facilities are already meeting, no water and solid waste. impacts are projected for existing sources. Our analyses are based on the use of DLA for controlling new hilms. and, therefore, no water impacts are projected for new sources. To project solid waste impacts for new sources, we assumed that one sanitaryware tunnel. hiln equipped with a DLA will begin operation at the beginning of the first vear following promulgation of the rule. The solid waste disposal impacts that result from the use of DLA will include the disposal of spent limestone. We calculated the solid waste by taking the difference between the amount of limestone charged into the DLA and the amiount of reacted limestons and then adding the amount of maction products. and PM captured. We estimate that implementing the rule will result in the generation of 290 Mg vr 6320 ip: Fof solid waste from the new source.

#### C. What Are the Energy Impects?

Records the only requirements for existing contags under today's final rule are work practice standards that we prince that all faithful are atready meeting on onergy impact to projects the existing sources. To project

energy impacts for new sources, we

Liln equipped with a DLA will begin operation at the beginning of the first year following promulgation of the rule. Energy impacts consist of the electricity needed to operate the DLA. Electricity requirements are driven primarily by the size of the fan needed in the control device. We estimate the increase in energy consumption that would result from implementation of the rule to be T10 gigajoules per year (670 million Bru per year)

#### D. Are There Any Additional Environmental and Health Impacts?

Reducing HAP emissions under today's final rule will lower occupational HAP exposure levels. The operation of APCD may increase occupational noise levels.

#### E. What Are the Cost Impacts?

Because the only requirements for existing sources under today's final rule are work practice standards that we believe that all facilities are already meeting, cost impacts projected for existing sources are based only on recordkeeping and reporting requirements associated with the work practice standard. These costs are \$1,193 per year for each of the eight major source facilities, and the total annual cost to the industry for existing sources is \$9,533. To project costs for new sources, we assumed that one sanitaryware tunnel kiln, equipped with a DLA, will be built during the first year following promulgation. We estimate the capital costs associated with implementation of the rule to be \$510,000 for new sources. The capital costs include the purchase and installation of I/LA and monitoring equipment. We estimate the annualized posts associated with implementation of the rule to be \$170,000 per year for new sources. The armualized costs include: annualized capital costs of the control and monitoring equipment, operation and maintenance expenses, emusion, testing costs, and record leeping and reporting cost, associated with installing and operating the DLA.

We calculated the cost estimates using cost algorithms that are based on procedures from EPA's OAOPS Control Cost Idanual (EPA 450/0+90+006). Ianuary 1990) and cost information provided by the EDOF industry and control device ventions. We estimated costs by developing model process units that correspond to the various size of hims found at the ceramic: manual turing mediates.

F. What Are the Economic Impacts?

We did not prepare a revised economic impact analysis for the clay ceramics industry because the requirements of the final rule will result in a decrease in cost impacts on the industry. Specifically, new and reconstructed roller kilns, which would have been subject to emission limits in the rule as proposed are not subject to emission limits in the final rule. In addition, the requirements for clay ceramics tunnel fallns with design capacities less than 9.07 Mg/hr (10 tph) are based on control with a DLA rather than the more costly DIFF, DLS'FF, or WS systems on which the proposed rule was based.

The goal of the economic impact analysis is to estimate the market response of clay ceramics. manufacturing producers to today's final rule and to determine the economic effects that may result due to the final rule. Because the MACT floor for existing clay ceramics kilns is based on firing natural gas, or an equivalent fuel, and all clay ceramics kilns for which we have data are fired by natural gas or propane, the compliance costs for existing sources associated with today's final rule consist only of recordkeeping and reporting costs and are minimal. The aggregate price of ceramic products is, therefore, expected to remain the same. Because the prices of ceramic products are not expected to change due to today's final rule, there are no projected changes in domestic production, domestic consumption, or foreign trade. Therefore, no economic impacts on existing major sources are expected from today's final rule.

Unlike existing sources, new and reconstructed tunnel lains used to produce clay ceramics will face positive compliance costs associated with the installation and operation of APCD, Weesumate that one new 3.6 Mg/lu (4 tph) capacity tunnel itiln will be constructed in the sanitaryware industry during the first 5 years after the rule is promulgated. Industry compliance costs associated with this full are expected to be less than 0.1 percent of industry. value of shipments for the sanitaryware industry. No level of cost-to-sale: for sanitaryware kilns could be developed. due to the diversity of product types. that they produce.

# VIII. Statutory and Executive Order Reviews

A Executive Order 12866, Regulatory Planning and Review

Under Executive Order 12506-158 FR 51755, October 4 1960 EFF, must determine whether the regulatory action is "significant" and, therefore, subject to review by the OMB and the requirements of the Executive Order. The Executive Order defines "significant regulatory action" as one that is likely to result in a rule that may:

(1) Have an annual effect on the economy of \$100 million or more or adversely affect in a material way the economy, a sector of the economy. productivity, competition, jobs, the environment, public health or safety, or State, local, or tribal governments or communities:

(2) Create a serious inconsistency or otherwise interfere with an action taken or planned by another agency;

(3) Materially alter the budgetary impact of entitlements, grants, user fees, or loan programs, or the rights and obligations of recipients thereof; or

(4) Raise novel legal or policy issues arising out of legal mandates, the President's priorities, or the principles set forth in the Executive Order.

Pursuant to the terms of Executive Order 12866, it has been determined that today's BSCP final rule is a "significant regulatory action" because it raises novel legal or policy issues within the meaning of paragraph (4) above. Consequently, today's final BSCP rule was submitted to OMB for review under Executive Order 12866. Any written comments from OMB and written EPA responses are available in the docket (see ADDRESSES section of this preamble).

Pursuant to the terms of Executive Order 12866, it has been determined that the clay ceramics final rule does not constitute a "significant regulatory action" because it does not meet any of the above criteria. Consequently, today's final clay ceramics rule was not submitted to OMB for review under Executive Order 12866.

### B. Paperwork Reduction Act

The information collection requirements in today's final rules will be submitted for approval to OMB under the requirements of the Paperwork Reduction Act, 44 U.S.C. 3501 et seq. The EPA has prepared an Information Collection Request (ICR) document for each of the rules (ICR No. 2022.01 for BSCP manufacturing and ICR No. 2023.01 for clay ceramics manufacturing), and a copy of either document may be obtained from Susan Auby by mail at Office of Environmental Information, Collection Strategies Division (2822T), U.S. EFA, 1200 Pennsylvania Avenue, NW, Washington. DC 20460; by e-mail at *auby.susan@epa.gov*; or by calling (202) 566-1672. You may also download a copy off the Internet at http://

www.epa.gov/icr. The information requirements are not enforceable until

OMB approves them.

The information requirements are based on notification, recordkeeping, and reporting requirements in the NESHAP General Provisions (40 CFR part 63, subpart A), which are mandatory for all operators subject to national emission standards. These recordkeeping and reporting requirements are specifically authorized by section 114 of the CAA (42 U.S.C. 7414). All information submitted to EPA pursuant to the recordkeeping and reporting requirements for which a claim of confidentiality is made is safeguarded according to EPA's policies set forth in 40 CFR part 2, subpart B. Today's final BSCP rule will not

require any notifications or reports beyond those required by the NESHAP General Provisions. The recordkeeping requirements require only the specific information needed to assure

compliance.

With one exception, today's final clay ceramics rule will not require any notifications or reports beyond those required by the NESHAP General Provisions. The exception applies to affected sources that are subject to limits on the type of fuel used. In such cases, the owner or operator may use an alternative fuel under certain conditions but must submit a notification before using the alternative fuel and must report on alternative fuel use after terminating use of the alternative fuel. The recordkeeping requirements require only the specific information needed to assure compliance.

The annual monitoring, reporting, and recordkeeping burden for the collection of information required by today's final BSCP manufacturing rule (averaged over the first 3 years after the effective date of the final rule) is estimated to be 17,471 labor hours per year at a total annual labor cost of \$900,328. This burden estimate includes a one-time submission of an OM&M plan; one-time submission of a SSMP, with immediate reports for any event when the procedures in the plan were not followed; semiannual compliance reports; maintenance inspections; notifications; and recordkeeping. Total annualized capital/startup costs associated with the monitoring requirements over the 3-year period of the ICR are estimated at \$115,111, with operation and maintenance costs of \$4.853/yr.

The annual monitoring, reporting, and recordkeeping burden for the collection of information required by today's final clay ceramics manufacturing rule coveraged over the first 3 years after the

effective date of the final rule) is estimated to be 185 labor hours per year at a total annual labor cost of \$9,533. This burden estimate includes a onetime submission of an OM&M plan; onetime submission of a SSMP, with immediate reports for any event when the procedures in the plan were not followed; semiannual compliance reports; maintenance inspections; notifications; and recordkeeping. Total annualized capital/startup costs associated with the monitoring requirements over the 3-year period of the ICR are estimated at \$1,824, with operation and maintenance costs of \$358/yr.

Burden means the total time, effort, or financial resources expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to a collection of information; search data sources; complete and review the collection of information; and transmit or otherwise disclose the information.

An Agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. The OMB control numbers for EPA's regulations are listed in 40 CFR part 9 and 48 CFR chapter 15. The OMB control numbers for the information collection requirements in the final rules will be listed in an amendment to 40 CFR part 9 in a subsequent Federal Register document

after OMB approves the ICRs.

#### C. Regulatory Flexibility Act

The EPA has determined that it is not necessary to prepare a regulatory flexibility analysis in connection with this action. After considering the economic impacts of today's final rule on small entities in the two source categories, the EPA has determined that this action will not have a significant economic impact on a substantial number of small entities. Although today's final rule will not have a significant economic impact on a substantial number of small entities, we have nonetheless tried to minimize the impact of the final rule on small entities. For both the BSCP manufacturing and clay ceramics.

manufacturing source categories, we exercised flexibility in minimizing impacts on small entities through subcategorization of tunnel kilns by size, which still benefits the environment by requiring greater emissions reductions from the larger kilns. In addition, for the BSCP manufacturing source category, we contacted the small entities estimated to incur impacts in excess of 1 percent of sales to explain the rule's regulatory

Facilities with existing tunnel kilns operating at or near 10 tph could accept a permit condition that restricts kiln production to less than 10 tph and, therefore, places the kiln in the subcategory unaffected by the standards for existing kilns.

For purposes of assessing the impact of today's action on small entities, small entities are defined as: (1) A small business according to Small Business Administration (SBA) size standards; (2) a small governmental jurisdiction that is a government of a city, county, town, school district or special district with a population of less than 50,000; and (3) a small organization that is any not-forprofit enterprise which is independently owned and operated and is not dominant in its field. The following two sections provide descriptions of the small business assessments for the two categories of sources addressed by today's action.

1. Brick and Structural Clay Products (BSCP) Manufacturing

Small Business Administration size standards for BSCP manufacturing, by NAICS code, are shown in Table 2 of this preamble.

Business SIZE TABLE 2.—SMALL **BSCP** FOR: STANDARDS: MANUFACTURING

NAIOS code	Size stand ard, number of employees
027121	500
327122	500
027123	500
327125	750
327126	750

We have determined that 16 of the 89. companies owning BSCP manufacturing tacilities are small businesses. Although small businesses represent 86 percent of the combanies within the source calegory, they are expected to becurabout D percent of the total industry engineering compliance costs of \$14 million Haditiohalm, CI or the 76 smelt

businesses will mour no costs. Under the final rule, we estimate that three small firms in this source category may experience an impact less 1 percent of sales, nine small firms in this source category may experience an impact between 1 percent and 3 percent of salec, and 3 small businesses (or 20 percent) may experience an impact greater than 3 percent of sales.

We also conducted an economic impact analysis that accounted for firm behavior to provide an estimate of the facility and market impacts of the proposed rule. The analysis projected that of the 189 facilities in this source category, two facilities are at risk of closure. Neither of these facilities is owned by a small business. The median compliance cost is below 1 percent of sales for both small and large firms affected by the proposed rule (0.0 and 0.1 percent for small and large firms.

respectively).

Fifteen new BSCP manufacturing sources are projected to be constructed during the five years after promulgation of the rule. Industry compliance costs associated with these sources are anticipated to be less than 0.6 percent of the BSCP manufacturing industry's value of shipments. According to the new source economic impact analysis, three to six of these new sources may be delayed in coming on-line due to the compliance costs they would face. We cannot determine with certainty whether these new sources will be built by large or small companies. Regardless, impacts at the company level are not expected to be significant for a substantial number of small entities.

### Clay Ceramics Manufacturing 5mall standards for clay ceramics. manufacturing, by ITAICS code, are

shown in Table 3 of this preamble.

TABLE 3.—SMALL BUSINESS SIZE STARDARDS FOR CLAY CERAMICS MANUFACTURING

HAICS ontie	Size stand- ard, number of emplovees	
326191		
327711	T50	
*· <b>=</b>		
227112	500	
327100	500	
527123	500	
327125	750	
	500	
- ??5521		
401000	ار الله الله الله الله الله الله الله ال	
451526	100	

The EP7 identified 12 of the 29. companies, owning classic ramics manufacturing facilities as small businesses. Because the clay ceramics manufacturing final rule does not include emissions limits for existing kilns and includes only a work practice standard that requires that existing kilms. are fired with natural gas, a firm's existing kilns will be minimally impacted by the final rule. One new sanitaryware manufacturing source is projected to be constructed in the first five years following promulgation of the rule. Industry compliance costs associated with this source are expected to be less than 0.1 percent of industry value of shipments for the sanitaryware industry segments. No level of cost-tosales for the new sanitaryware manufacturing source could be developed due to the diversity of product types produced. Thus, new clayceramics manufacturing sources are expected to face positive compliance costs; however, we cannot determine with certainty whether these sources will be built by large or small companies. Regardless, impacts at the company level are not expected to be significant for a substantial number of small entities.

#### D. Unrunded Mandates Reform Act

Title II of the Unfunded Mandates Reform Act of 1995 (UMRA), Pub. L. 104-4, establishes requirements for Federal agencies to assess the effects of their regulatory actions on State, local and tribal governments and the private sector. Under section 202 of the UMRA, the EPA generally must prepare a written statement, including a costbenefit analysis, for proposed and final rules with "Federal mandates" that may result in expenditures by State, local, and tribal governments, in the aggregate, or by the private sector, of \$100 million or more in any 1 year. Before promulgating an EPA rule for which a written statement is needed, section 205. of the UNITA generally requires EFA to identih and consider a reasonable number of regulatory alternatives and adopt the least costly, most costeffective, or least burdensome alternative that achieves the objectives of the rule. The provisions of section. 205 dc not apply when they are inconsistent with applicable law. Moreover, section 205 allows EPA to adopt ar, alternative other than the loast costly, most cost-effective or least burdensome alternative if the Administrator published with the final rule ar, explanation why that alternative was not adopted. Before EFA establishes any regulatory requirements that may significantly or uniquely aftect small governments including tribal gor eranies is must have neveloped.

under section 203 of the UMRA, a small government agency plan. The plan must provide for notifying potentially affected small governments, enabling officials of affected small governments to have meaningful and timely input in the development of EPA's regulatory proposals with significant Federal intergovernmental mandates, and informing, educating, and advising small governments on compliance with the regulatory requirements.

The EPA has determined that today's final rules do not contain a Federal mandate that may result in expenditures of \$100 million or more for State, local, and tribal governments, in the aggregate, or the private sector in any 1 year. The total annual cost for today's final BSCP rule for any 1 year is estimated at \$24 million. The total annual cost for today's final clay ceramics rule for any 1 year is estimated at \$9,500. Thus, today's final rules are not subject to the requirements of sections 202 and 205 of the UMRA. In addition, the EPA has determined that today's final rules contain no regulatory requirements that might significantly or uniquely affect small governments because they contain no regulatory requirements that apply to such governments or impose obligations upon them. Therefore, today's final rules are not subject to the requirements of section 203 of the UMRA.

### E. Executive Order 13132, Federalism

Executive Order 13132 (64 FR 43255, August 10, 1999) requires EPA to develop an accountable process to ensure "meaningful and timely input by State and local officials in the development of regulatory policies that have federalism implications." "Policies that have federalism implications" is defined in the Executive Order to include regulations that have "substantial direct effects on the States, on the relationship between the national government and the States, or on the distribution of power and responsibilities among the various levels of government." Under Executive Order 13132, the EPA may not issue a regulation that has federalism implications, that imposes substantial direct compliance costs, and that is not required by statute, unless the Federal government provides the funds necessary to pay the direct compliance costs incurred by State and local governments, or EPA consults with State and local officials early in the process of developing the proposed regulation. The EPA also may not issue a regulation that has federalism implications and that preempts State Law unless EPA consults with State and

local officials early in the process of developing the proposed regulation.

If EPA complies by consulting, Executive Order 13132 requires EPA to provide to OMB, in a separately identified section of the preamble to the rule, a federalism summary impact statement (FSIS). The FSIS must include a description of the extent of EPA's prior consultation with State and local officials, a summary of the nature of their concerns and EPA's position supporting the need to issue the regulation, and a statement of the extent to which the concerns of State and local officials have been met. Also, when EPA transmits a draft final rule with federalism implications to OMB for review pursuant to Executive Order 12866, it must include a certification from EPA's Federalism Official stating that EPA has met the requirements of Executive Order 13132 in a meaningful and timely manner.

Today's final rules do not have lederalism implications. They will not have substantial direct effects on the States, on the relationship between the national government and the States, or on the distribution of power and responsibilities among the various levels of government, as specified in Executive Order 13132. None of the affected facilities are owned or operated by State governments, and the final rule requirements will not supercede State regulations that are more stringent. Thus, the requirements of Executive Order 13132 do not apply to the final rules.

## F. Executive Order 13175. Consultation and Coordination With Indian Tribal Governments

Executive Order 13175 (65 FR 67249, November 6, 2000) requires EPA to develop an accountable process to unsure "meaningful and timely input by tribal officials in the development of regulatory policies that have tribal implications." "Policies that have tribal implications" are defined in the Executive Order to include regulations that have "substantial direct effects on one or more Indian tribes, on the relationship between the Federal government and the Indian tribes, or on the distribution of power and responsibilities between the Federal government and Indian tribes."

Today's final rules do not have tribal implications. They will not have substantial direct effects on tribal governments, on the relationship between the Federal government and Indian tribes, or on the distribution of power and responsibilities between the Federal government and Indian tribes, a specified in Executive Order 13175.

No tribal governments are known to own or operate BSCP or clay ceramics manufacturing facilities. Thus, Executive Order 13175 does not apply to the final rules.

### G. Executive Order 13045, Protection of Children From Environmental Health & Safety Risks

Executive Order 13045 (62 FR 19885, April 23, 1997) applies to any rule that: (1) Is determined to be "economically significant" as defined under Executive Order 12866, and (2) concerns the environmental health or safety risk that EPA has reason to believe may have a disproportionate effect on children. If the regulatory action meets both criteria. the EPA must evaluate the environmental health or safety effects of the planned rule on children, and explain why the planned regulation is preferable to other potentially effective and reasonably feasible alternatives considered by EPA.

The EPA interprets Executive Order 13045 as applying only to those regulatory actions that are based on health or safety risks, such that the analysis required under section 5-501 of the Executive Order has the potential to influence the rule. Today's final rules are not subject to Executive Order 13045 because they are based on technology performance and not on health or safety

H. Executive Order 13211, Actions Concerning Regulations That Significantly Affect Energy Supply, Distribution, or Use

Executive Order 13211 (66 FR 28355, May 22, 2001) provides that agencies shall prepare and submit to the Administrator of the Office of Information and Regulatory Affairs, OMB, a Statement of Energy Effects for certain actions identified as "significant energy actions." Section 4(b) of Executive Order 13211 defines "significant energy actions" as "any action by an agency (normally published in the Federal Register) that promulgates or is expected to lead to the promulgation of a final rule or regulation, including notices of inquiry, advance notices of proposed rulemaking, and notices of proposed rulemaking: (1)(i) That is a significant regulatory action under Executive Order 12866 or any successor order, and (ii) is likely to have a significant adverse effect on the supply, distribution, or use of energy; or (2) that is designated by the Administrator of the Office of Information and Regulatory Affair, as a significant energy action." Today's tinal alay ceramics manufacturing rule is not subject to Executive Order 132 FF

because it is not a significant regulatory action under Executive Order 12866. Although today's final BSCP rule is considered to be a significant regulatory action under Executive Order 12866, it is not a "significant energy action" because it is not likely to have a significant adverse effect on the supply, distribution, or use of energy. The basis for the determination is as follows.

Today's final BSCP rule affects manufacturers in the BSCP (NAICS 327121), extruded tile (NAICS 327122). and other structural clay products (NAICS 327123) industries. There is no crude oil, fuel, or coal production from these industries. Hence, there is no direct effect on such energy production related to implementation of the BSCP rule. In fact, as previously mentioned in this preamble, there will be an increase in energy consumption, and hence an increase in energy production, resulting from installation of APCD likely needed for sources to meet the requirements of the final BSCF rule. This increase in energy consumption is equal to approximately 27 million kilowatthours vear (kWb/vr) for electricity. The electricity increase is considered negligible, equivalent to 0.0007 percent of 1999 U.S. electricity production.4 There is no expected increase in natural gas consumption. It should be noted, however that the estimated decrease in BSCP production resulting from producer's and consumer's reactions to the final BSCP rule will offset this effect on such energy production. It is likely that the output reduction in the industries will lead to less energy use by: these industries and thus some reduction in overall energy production.

Given the negligible change in energy consumption resulting from the final BSCF rule, we do not expect any price increase for any energy type. The cost of energy distribution should not be affected by the final BSCF rule at all since the final rule does not affect energy distribution facilities. Finally, with changes in her exports being a minimal percentage of domestic output from the affected industries, there will he only a negligible change in international trade, and bence in dependence on foreign energy supplies. Ho other adverse outcomes are expected. to occur with regards to energy supplies.

Therefore, we conclude that today's final BSCP rule is not likely to have a significant adverse effect on the sumply, distribution, or use of energy

I National Technology Transfer and Advancement Act

Section 12(d) of the National Technology Transfer and Advancement Act (NTTAA) of 1995 (Pub. L. No. 104-113; 15 U.S.C. 272 note: directs EPA to use voluntary consensus standards in their regulatory and procurement activities unless to do so would be inconsistent with applicable law or otherwise impractical. Voluntary consensus standards are technical standards (e.g., materials specifications, test methods, sampling procedures. business practices) developed or adopted by one or more voluntary consensus hodies. The NTTAA directs CPA to provide Congress, through annual reports to OMB, with explanations when an agency does not use available and applicable voluntary consensus standards.

The final rules involve technical standards. The EPA cites the following standards in the final rules: EPA Methods 1, 1A, 2, 2A, 2C, 2D, 2F, 2G, 3, 4, 5, 22, 26, 26A, and 320 of 40 CFR part 60, appendix A. Consistent with the NTTAA, EPA conducted searches to identify voluntary consensus standards in addition to these EPA methods. No applicable voluntary consensus standards were identified for EPA Methods 1A, 2A, 2D, 2F, 2G, and 22. The search and review results have been documented and are in the dockets for the final rules.

The search for emissions measurement procedures identified 11 voluntary consensus standards. The EPA determined that eight of these 11 standards identified for measuring emissions of the HAPs or surrogates subject to emission standards in the final rules were impractical alternatives to EPA, test methods for the purposes of the final rules. Therefore, EPA does not intend to adopt these standards at this time. The reasons for this determination for the 11 methods are discussed in the dockets for the final rules.

Two of the 11 voluntary consensus standards identified in this search were not available at the time the review was conducted for the purposes of the final rules because they are under development by a voluntary consensus body "LOWETEST MFC 15M, "Flow Measurement by Velocity Traverse" for EF's Method 2 land possibly 11; and ASME BSP MFC 12M, "Flow in Closed Conduct Luning Multiport Averaging Plant Frimary Flowmeters," for EF's Method 2

In responde to public comments received, we considered and decided to include High Hellord Latitus an option for me, caping HF and 1001. The

voluntary consensus standard ASTM D6348-98, "Determination of Gaseous Compounds by Extractive Direct Interface Fourier Transform (FTIR) Spectroscopy," has been reviewed by the EPA as a potential alternative to EPA Method 320 Suggested revisions to ASTM D6348–98 that would allow the EPA to accept ASTM D6348-98 as an acceptable alternative were sent to ASTM by the EPA. The ASTM Subcommittee D22-03 is currently undertaking a revision of ASTM D6348-98. Because of this, we are not citing this standard as an acceptable alternative for EPA Method 320 in the final rules today. However, upon successful ASTM balloting and demonstration of technical equivalency with the EPA FTIP, methods, the revised ASTM standard could be incorporated by reference for EPA regulatory applicability. In the interim, facilities have the option to request ASTM D6346-98 as an alternative test method under 40 CFF, 63.7(f) and 40 CFR 63.8(f) on a case-by-case basis.

Table 3 of the final BSCP rule and Table 4 of the final clay ceramics rule list the EPA testing methods included in the rules. Under 40 CFR 63.7(f) and 40 CFR 63.8(f), a source may apply to EPA for permission to use alternative test methods or alternative monitoring requirements in place of any of the EPA testing methods, performance specifications, or procedures

### 1. Congressional Review Act

The Congressional Review Act, 5. U.S.C. 801 et seq., as added by the Small **Business Regulatory Enforcement** Fairness Act of 1996, generally provides that before a rule may take effect, the agency promulgating the rule must submit a rule report, which includes a copy of the rule, to each House of the Congress and to the Comptroller General of the United States. The EPA will submit a report containing today's final rules and other required information to the U.S. Senate, the U.S. House of Representatives, and the Comptroller General of the United States prior to publication of the rules in the Federal Register Heither of today's rules are "major rules" or defined by 5 U.S.C. 804(2). The final rule, will be effective. on May 16, 2003.

### List of Subjects in 40 CFR Part 63

Administrative practice and procedure. Air pollution control. Hazardou: substances, intergovernmental relations. Reporting and records cepting requirements.

Denotational of Energy Theory Information transfer fundamentations. Annual Energy Theory Enough Energy and important for 1998, and attended in the internet at only, which can the gray

Dated: February 28, 2003.

#### Christine Todd Whitman,

Administrator

■ For the reasons stated in the preamble, title 40, chapter I, part 63 of the Code of the Federal Regulations is amended as follows:

### PART 63-[AMENDED]

■ 1. The authority citation for part 63 continues to read as follows:

Authority: 42 U.S.C. 7401, et seq.

2. Part 63 is amended by adding subpart []]][ to read as follows:

### Subpart JJJJJ—National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing

Sec

#### What This Subport Covers

63.8380 What is the purpose of this subpart?

63.8385 Am I subject to this subpart? 63.8390 What parts of my plant does this subpart cover?

63.8395 When do I have to comply with this subpart?

#### **Emission Limitations**

63.8405 What emission limitations must I meet?

63.8410 What are my options for meeting the emission limitations?

### General Compliance Requirements

63,8420 What are my general requirements for complying with this subpart?
63,8425 What do I need to know about

63.8425 What do I need to know about operation, maintenance, and monitoring plans?

### Testing and Initial Compliance Requirements

63.8435 By what date must I conduct performance tests?

63.8440 When must I conduct subsequent performance tests?

63.8445 How do I conduct performance tests and establish operating limits?

C3.8450 What are my monitoring installation, operation, and maintenance requirements?

63.8455 How do I demonstrate initial compliance with the emission limitations?

### Continuous Compliance Requirements

63.8465 How do I monitor and collect data to demonstrate continuous compliance? 63.8470 How do I demonstrate continuous compliance with the emission

limitations"

#### Notifications, Reports, and Records

65,8480 What notifications must I submit and when?

60 8485 What reports must I submit and when?

65.8490 What records must I keep? 65.8495 In what form and for how long must I keep my records?

#### Other Requirements and Information

63.8505 What parts of the General Provisious apply to me?

63.8510 Who implements and enforces this subpart?

63.8515 What definitions apply to this subpart?

### Tables to Subpart JIJI of Part 63

Table 1 to Subpart JJJJJ of Part 63— Emission Limits

Table 2 to Subpart JJJJ of Part 63— Operating Limits

Table 3 to Subpart JJJJ of Part 63— Requirements for Performance Tests Table 4 to Subpart JJJJ of Part 63—

Initial Compliance with Emission Limitations

Table 5 to Subpart JJJJ of Part 63— Continuous Compliance with Emission Limits and Operating Limits

Table 6 to Subpart [JJJ] of Part 63—
Requirements for Reports
Table 7 to Subpart JIJJ] of Part 63—
Applicability of General Provisions
to Subpart JJJJ

#### What This Subpart Covers

### § 63.8380 What is the purpose of this subpart?

This subpart establishes national emission limitations for hazardous air pollutants (HAP) emitted from brick and structural clay products (BSCP) manufacturing facilities. This subpart also establishes requirements to demonstrate initial and continuous compliance with the emission limitations.

### § 63.8385 Am I subject to this subpart?

You are subject to this subpart if you own or operate a BSCP manufacturing facility that is, is located at, or is part of, a major source of HAP emissions according to the criteria in paragraphs (a) and (b) of this section.

(a) A BSCP manufacturing facility is a plant site that manufactures brick (including, but not limited to, face brick, structural brick, and brick pavers); clay pipe; roof tile; extruded floor and wall tile; and/or other extruded, dimensional clay products. Brick and structural clay products manufacturing facilities typically process raw clay and shale, form the processed materials into bricks or shapes, and dry and fire the bricks or shapes.

(b) A major source of HAP emissions is any stationary sources within a contiguous area under common control that emits or has the potential to emit any single HAP at a rate of 9.00 megagrams (10 tons) or more per year or any ombination of HAP at a rate of 20.68 mesagrams (25 tons) or more per year.

### § 63.8390 What parts of my plant does this subpart cover?

(a) This subpart applies to each existing, new, or reconstructed affected source at a BSCP manufacturing facility.

(b) The existing affected source is an existing tunnel kiln with a design capacity equal to or greater than 9.07 megagrams per hour (Mg/hr) (10 tons per hour (tph)) of fired product according to paragraphs (b)(1) through (3) of this section. For the remainder of this subpart, a tunnel kiln with a design capacity equal to or greater than 9.07 Mg/hr (10 tph) of fired product will be called a large tunnel kiln, and a tunnel kiln with a design capacity less than 9.07 Mg/hr (10 tph) of fired product will be called a small tunnel kiln.

(1) For existing tunnel kilns that do not have sawdust dryers, the kiln exhaust process stream (i.e., the only process stream) is subject to the requirements of this subpart.

(2) For existing tunnel kilns that ducted exhaust to sawdust dryers prior to July 22, 2002, only the kiln exhaust process stream (i.e., the process stream that exhausts directly to the atmosphere or to an air pollution control device (APCD)) is subject to the requirements of this subpart. As such, any process stream that is ducted to a sawdust dryer is not subject to these requirements.

(3) For existing tunnel kilns that first ducted exhaust to sawdust dryers on or after July 22, 2002, all of the exhaust ti.e., all process streams) is subject to the requirements of this subpart.

(c) An existing small tunnel kiln whose design capacity is increased such that it is equal to or greater than 9.07 Mg/hr (10 tph) of fired product is subject to the requirements of this subpart.

(d) An existing tunnel kiln with a federally enforceable permit condition that restricts kiln operation to less than 9.07 Mg/hr (10 tph) of fired product on a 12-month rolling average basis is not subject to the requirements of this subpart.

(e) Each new or reconstructed tunnel kiln is an affected source regardless of design capacity. All process streams from each new or reconstructed tunnel kiln are subject to the requirements of this subpart.

(f) Kilns that are used exclusively for research and development (R&D) and are not used to manufacture products for commercial sale, except in a deminimis manner, are not subject to the requirements of this subpart.

(g) Edns that are used exclusively for setting glazes on previously fired products are not subject to the equirements of this subpart.

(b) A source is a new affected source il construction of the affected source began after July 22, 2002, and you met the applicability criteria at the time you began construction.

(i) An affected source is reconstructed if you meet the criteria as defined in  $\S$  63.2, except as provided in paragraphs.

(i)(1) and (i)(2) of this section.

- (1) It is not technologically and economically feasible for an existing small tunnel kiln whose design capacity is increased such that it is equal to or greater than 9.07 Mg/hr (10 tph) of fired product to meet the relevant standards (i.e., new source maximum achievable control technology (MACT)) by retrofitting with a dry lime injection fabric filter (DIFF), dry lime scrubber/ fabric filter (DLS/FF), or wet scrubber (WS).
- (2) It is not technologically and economically feasible for an existing large dry limestone adsorber (DLA)controlled kiln to meet the relevant standards by retrofitting with a DIFF. DLS/FF, or WS.
- (j) An affected source is existing if it is not new or reconstructed.

### § 63.8395 When do I have to comply with this subpart?

(a) If you have a new or reconstructed affected source, you must comply with this subpart according to paragraphs (a)(1) and (2) of this section.

(1) If the initial startup of your affected source is before May 16, 2003. then you must comply with the applicable emission limitations in Tables 1 and 2 to this subpart no later than May 16, 2003.

(2) If the initial startup of your affected source is after May 16, 2003. then you must comply with the applicable emission limitations in Tables 1 and 2 to this subpart upon initial startup of your affected source.

(b) If you have an existing affected source, you must comply with the applicable emission limitations in Tables 1 and 2 to this subpart no later.

than Mar. 16, 2003.

- (c) If you have an existing area source that increases its emissions or its notential to emit such that it becomes a major source of HAP, you must be in compliance with this subpart according to paragraphs (c)(1) and (2) of this section.
- THE Any portion of the elasting facility that it is new affected source of a new reconstructed source must be incompliance with this subpart upon-
- 321. All other parts of the existing facility must be in complian a with this subpart in 3 years after the date the area. source la comes a major source

(d) If you have a new area source (i.e., an area source for which construction or reconstruction commenced after July 22, 2002) that increases its emissions or its potential to emit such that it becomes a major source of HAP, you must be in compliance with this subpart upon initial startup of your affected source as a major source.

(e) You must meet the notification requirements in § 63.8480 according to the schedule in § 63.8480 and in 40 CFR part 63, subpart A. Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

### **Emission Limitations**

### § 63,8405 What emission limitations must I

- (a) You must meet each emission limit in Table 1 to this subpart that applies to vou.
- (b) You must meet each operating limit in Table 2 to this subpart that applies to you.

#### § 63.8410 What are my options for meeting the emission limitations?

To meet the emission limitations in Tables 1 and 2 to this subpart, you must use one or more of the options listed in paragraphs (a) and (b) of this section.

(a) Emussions control system. Use an emissions capture and collection system and an APCD and demonstrate that the resulting emissions or emissions reductions meet the emission limits in Table 1 to this subpart, and that the capture and collection system and APCD meet the applicable operating. limits in Table 2 to this subpart.

(b) Process changes. Use fow-HAP raw materials of implement manufacturing process changes and demonstrate that the resulting emissions. or emissions reductions meet the amission limits in Table 1 to this зибрагі.

### General Compliance Requirements

#### § 63.8420 What are my general requirements for complying with this subpart?

- (a) You must be in compliance with the emission limitations (maluding) operating fimitions, this subpart at all rimes, except during periods of startup. thutdown, and malfunction and during periods of routine control device maintenance as specified in paragraph et of this section.
- The Except as openified in paragraph. et of this section, you must always. operate and mointain your affected source, including air pollution control and in any congrequipment according to the provide on the 563,66-10460 During the period between the compliance date

- specified for your affected source in  $\S$  63.8395 and the date upon which continuous monitoring systems (CMS). te.g., continuous parameter monitoring systems) have been installed and verified and any applicable operating limits have been set, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.
- (c) You must develop and implement a written startup, shutdown, and malfunction plan (SSMP) according to the provisions in  $\S 63.6(e)(3)$ .
- (d) You must prepare and implement a written operation, maintenance, and monitoring (OM&M) plan according to the requirements in § 63.8425.
- (e) If you own or operate an affected kiln and must perform routine maintenance on the control device for that kiln, you may bypass the kiln control device and continue operating the kiln upon approval by the Administrator provided you satisfy the raphs (e)(1)
- (1) You must request a routine control device maintenance exemption from the Administrator. Your request must justify the need for the routine maintenance on the control device and the time required to accomplish the maintenance activities, describe the maintenance activities and the frequency of the maintenance activities, explain why the maintenance cannot be accomplished during kiln shutdowns, describe how you plan to minimize emissions to the greatest extent possible during the maintenance, and provide any other documentation required by the Administrator.
- (2) The routine control device. maintenance exemption must not exceed 4 percent of the annual operating uptime for each luln.
- (3) The request for the routine control. device maintenance exemption if approved by the Administrator must be incorporated by reference in and attached to the affected source's title V permit.
- (4) You must manimize HAP emissions during the period when the kiln is operating and the control device is offline.
- (5) You must minimize the time period during which the lale is operating and the control device is: offline.
- the lou must be in compliance with the provisions of subpart A of this part. except as noted in Table 7 to this នលើវាកាស

§ 63.8425 What do I need to know about operation, maintenance, and monitoring plans?

(a) You must prepare, implement, and revise as necessary an OM&M plan that includes the information in paragraph (b) of this section. Your OM&M plan must be available for inspection by the permitting authority upon request.

(b) Your OM&M plan must include, as a minimum, the information in paragraphs (b)(1) through (13) of this

section.

- (1) Each process and APCD to be monitored, the type of monitoring device that will be used, and the operating parameters that will be monitored.
- (2) A monitoring schedule that specifies the frequency that the parameter values will be determined and recorded.
- (3) The limits for each parameter that represent continuous compliance with the emission limitations in § 63.8405. The limits must be based on values of the monitored parameters recorded during performance tests.

(4) Procedures for the proper operation and routine and long-term maintenance of each APCD, including a maintenance and inspection schedule that is consistent with the manufacturer's recommendations.

(5) Procedures for installing the CMS sampling probe or other interface at a measurement location relative to each affected process unit such that the measurement is representative of control of the exhaust emissions (e.g., on or downstream of the last APCD).

(6) Performance and equipment specifications for the sample interface, the pollutant concentration or parametric signal analyzer, and the data collection and reduction system.

(7) Continuous monitoring system performance evaluation procedures and acceptance criteria (e.g., calibrations).

- (8) Procedures for the proper operation and maintenance of monitoring equipment consistent with the requirements in §§ 63.8450 and 63.8(c)(1), (3), (4)(ii), (7), and (8).
- (9) Continuous monitoring system data quality assurance procedures consistent with the requirements in § 63.8(d).
- (10) Continuous monitoring system recordkeeping and reporting procedures consistent with the requirements in § 63.10(c), (e)(1), and (e)(2)(i).

(11) Procedures for responding to operating parameter deviations, including the procedures in paragraphs (b)(11)(i) through (iii) of this section.

 (i) Procedures for determining the cause of the operating parameter deviation. (ii) Actions for correcting the deviation and returning the operating parameters to the allowable limits.

(iii) Procedures for recording the times that the deviation began and ended and corrective actions were initiated and completed.

(12) Procedures for keeping records to

document compliance.

(13) If you operate an affected kiln and you plan to take the kiln control device out of service for routine maintenance, as specified in § 63.8420(e), the procedures specified in paragraphs (b)(13)(i) and (ii) of this section.

(i) Procedures for minimizing HAP emissions from the kiln during periods of routine maintenance of the kiln control device when the kiln is operating and the control device is offline.

(ii) Procedures for minimizing the duration of any period of routine maintenance on the kiln control device when the kiln is operating and the

control device is offline.

(c) Changes to the operating limits in your OM&M plan require a new performance test. If you are revising an operating limit parameter value, you must meet the requirements in paragraphs (c)(1) and (2) of this section.

(1) Submit a notification of performance test to the Administrator as

specified in § 63.7(b).

(2) After completing the performance tests to demonstrate that compliance with the emission limits can be achieved at the revised operating limit parameter value, you must submit the performance test results and the revised operating limits as part of the Notification of Compliance Status required under § 63.9(h).

(d) If you are revising the inspection and maintenance procedures in your OM&M plan, you do not need to conduct a new performance test.

### Testing and Initial Compliance Requirements

### §63.8435 By what date must I conduct performance tests?

You must conduct performance tests within 180 calendar days after the compliance date that is specified for your source in § 63.8395 and according to the provisions in § 63.7(a)(2).

### § 63.8440 When must I conduct subsequent performance tests?

(a) You must conduct a performance test before renewing your 40 CFR part 70 operating permit or at least every 5 years following the initial performance test

the You must conduct a performance test when you want to change the parameter value for any operating limit specified in your OM&M plan.

### § 63.8445 How do I conduct performance tests and establish operating limits?

(a) You must conduct each performance test in Table 3 to this subpart that applies to you.

(b) Before conducting the performance test, you must install and calibrate all

monitoring equipment.

(c) Each performance test must be conducted according to the requirements in § 63.7 and under the specific conditions in Table 3 to this subpart.

(d) You must test while operating at

the maximum production level.

(e) You may not conduct performance tests during periods of startup, shutdown, or malfunction, as specified in § 63.7(e)(1).

(f) You must conduct at least three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.

(g) You must use the data gathered during the performance test and the equations in paragraphs (g)(1) and (2) of this section to determine compliance with the emission limitations.

(1) To determine compliance with the production-based hydrogen fluoride (HF), hydrogen chloride (HCl), and particulate matter (PM) emission limits in Table 1 to this subpart, you must calculate your mass emissions per unit of production for each test run using Equation 1 of this section:

$$MP = \frac{ER}{P} \qquad (Eq. 1)$$

Where:

MP=mass per unit of production, kilograms (pounds) of pollutant per megagram (ton) of fired product ER=mass emission rate of pollutant (HF, HCl, or PM) during each performance test run, kilograms (pounds) per hour

P=production rate during each performance test run, megagrams (tons) of fired product per hour.

(2) To determine compliance with the percent reduction HF and HCl emission limits in Table 1 to this subpart, you must calculate the percent reduction for each test run using Equation 2 of this section:

$$PR = \frac{ER_i - ER_n}{ER_i}$$
 (100) (Eq. 2)

Where

PE=percent reduction, percent ER;=mass emission rate of specific HAP (FIF or HCl) entering the APCD, kilograms (pounds) per hour ER,=mass emission rate of specific HAP (HF or HCl) exiting the APCD, kilograms (pounds) per hour

(h) You must establish each sitespecific operating limit in Table 2 to this subpart that applies to you as specified in Table 3 to this subpart.

(i) For each affected kiln that is equipped with an APCD that is not addressed in Table 2 to this subpart or that is using process changes as a means of meeting the emission limits in Table 1 to this subpart, you must meet the requirements in § 63.8(f) and paragraphs (i)(1) and (2) of this section.

(1) Submit a request for approval of alternative monitoring procedures to the Administrator no later than the notification of intent to conduct a performance test. The request must contain the information specified in paragraphs (i)(1)(i) through (iv) of this section.

(i) A description of the alternative APCD or process changes.

(ii) The type of monitoring device or procedure that will be used.

(iii) The operating parameters that will be monitored.

(iv) The frequency that the operating parameter values will be determined and recorded to establish continuous compliance with the operating limits.

(2) Establish site-specific operating limits during the performance test based on the information included in the approved alternative monitoring procedures request and, as applicable, as specified in Table 3 to this subpart.

## § 63.8450 What are my monitoring installation, operation, and maintenance requirements?

- (a) You must install, operate and maintain each CMS according to your Oblam plan and the requirements in paragraphs (a)(1) through (5) of this section.
- 41) Conduct a performance evaluation of each CMS according to your OM&M roan.
- (2) The CMS must complete a minimum of one cycle of operation for each successive 15-minute period. To have a valid hour of data, you must have at least three of four equally spaced data values for at least 75 percent if you collect more than four data values per hour for that how thot including startup is hutdown, malfunction out-of-control periods, or periods of routine control device maintenance rovered by a routine control device maintenance exemption as specified in { to: 6420(e)}
- (2) Postermine and record the 5-hour block, averaged or all reserved readings, calculated given every 5 hours of opening at the average of the previous

3 operating hours. To calculate the average for each 3-hour average period, you must have at least 75 percent of the recorded readings for that period (not including startup, shutdown, malfunction, out-of-control periods, or periods of routine control device maintenance covered by a routine control device maintenance exemption an specified in § 63.84201e)1.

(4) Record the results of each inspection, calibration, and validation

спеск.

(5) At all times, maintain the monitoring equipment including, but not limited to, maintaining necessary parts for routine repairs of the monitoring equipment.

(b) For each liquid flow measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (b)(1) through (3) of this section

(1) Locate the flow sensor in a position that provides a representative flowrate.

(2) Use a flow sensor with a minimum measurement sensitivity of 2 percent of the liquid flowrate.

(3) At least semiannually, conduct a flow sensor calibration check.

- (c) For each pressure measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (c)(1) through (7) of this section
- (1) Locate the pressure sensor(s) in or as close to a position that provides a representative measurement of the pressure.
- 12) Minimuze or eliminate pulsating pressure, vibration, and internal and emernal corrosion.
- (3) Use a gauge with a minimum measurement sensitivity of 0.5 inch of water or a transducer with a minimum measurement sensitivity of 1 percent of the pressure range.

 (4) Check the pressure tap daily to ensure that it is not plugged.

- (5) Using a manometer, check gauge calibration quarterly and transducer calibration monthly.
- (6) Any time the sensor exceeds the manufacturer's specified maximum operating pressure range, conduct palibration checks or install a new pressure sensor.

17) At least monthly, inspect all component: for integrity, all electrical connections for continuity, and all mechanical connections for leal age.

- (d) For each pH measurement device, you must meet the requirements in paragraphs (d)(1) through (4) of this section.
- 13: Locate the pH sensor in a position that provides a representative measurement of pH.

- (2) Ensure the sample is properly mixed and representative of the fluid to be measured
- (3) Check the pH meter's calibration on at least two points every 8 hours of process operation.
- (4) At least monthly, inspect all components for integrity and all electrical connections for continuity.
- tel For each bag leal, detection system, you must meet the requirements in paragraphs (el(1) through (11) of this section.
- (1) Each triboelectric bag leak detection system must be installed, calibrated, operated, and maintained according to the "Fabric Filter Bag Leak Detection Guidance," (EPA-454/R-98-015, September 1997). This document is available from the U.S. Environmental Protection Agency (U.S. EPA); Office of Air Quality Planning and Standards: Emissions, Monitoring and Analysis Division; Emission Measurement Center (MD-19), Research Triangle Park, NC 27711. This document is also available on the Technology Transfer Network (TTN) under Emission Measurement Center Continuous Emission: Monitoring. Other types of bag leak detection systems must be installed, operated, calibrated, and maintained in a manner consistent with the manufacturer's written specifications and recommendations.
- (2) The bag leak detection system must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.
- (3) The bag leal, detection system sensor must provide an output of relative PM loadings.
- (4) The hag leah detection system must be equipped with a device to continuously record the output signal from the sensor.
- 15) The bag leak detection system must be equipped with an audible alarm system that will sound automatically when an increase in relative PM emissions over a preset level is detected. The alarm must be located where it is easily heard by plant operating personnel.
- 16) For positive pressure fabric filter systems, a bag leaf detector must be installed in each bagliouse compartment or cell.
- (1) For negative pressure or induced air fabric filters, the bag leaf detector must be insighted downstream of the fabric filter.
- (a) Where multiple detectors are required, the system is instrumentation and alarm may be shared among detectors.

- (9) The baseline output must be established by adjusting the range and the averaging period of the device and establishing the alarm set points and the alarm delay time according to section 5.0 of the "Fabric Filter Bag Leak Detection Guidance."
- (10) Following initial adjustment of the system, the sensitivity or range, averaging period, alarm set points, or alarm delay time may not be adjusted except as detailed in your OM&M plan. In no case may the sensitivity be increased by more than 100 percent or decreased more than 50 percent over a 365-day period unless such adjustment follows a complete fabric filter inspection that demonstrates that the fabric filter is in good operating condition. Record each adjustment.
- (11) Record the results of each inspection, calibration, and validation check.
- (f) For each lime or chemical feed rate measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and paragraphs (f)(1) and (2) of this section.
- (1) Locate the measurement device in a position that provides a representative feed rate measurement.
- (2) At least semiannually, conduct a calibration check.
- (g) For each limestone feed system on a DLA, you must meet the requirements in paragraphs (a)(1),(4), and (5) of this section and must ensure on a monthly basis that the feed system replaces limestone at least as frequently as the schedule set during the performance test
- (h) Requests for approval of alternate monitoring procedures must meet the requirements in §§ 63.8445(i) and 63.8(f).

### § 63.8455 How do I demonstrate initial compliance with the emission limitations?

- (a) You must demonstrate initial compliance with each emission limitation that applies to you according to Table 4 to this subpart.
- (b) You must establish each sitespecific operating limit in Table 2 to this subpart that applies to you according to the requirements in § 63.8445 and Table 3 to this subpart.
- (c) You must submit the Notification of Compliance Status containing the results of the initial compliance demonstration according to the requirements in § 63.8480(e).

### Continuous Compliance Requirements

## § 63.8465 How do I monitor and collect data to demonstrate continuous compliance?

 (a) You must monitor and collect data according to this section.

- (b) Except for periods of monitor malfunctions, associated repairs, and required quality assurance or control activities (including, as applicable, calibration checks and required zero and span adjustments), you must monitor continuously (or collect data at all required intervals) at all times that the affected source is operating. This includes periods of startup, shutdown, malfunction, and routine control device maintenance as specified in § 63.8420(e) when the affected source is operating.
- (c) You may not use data recorded during monitoring mulfunctions, associated repairs, out-of-control periods, or required quality assurance or control activities for purposes of calculating data averages. A monitoring malfunction is any sudden, infrequent, not reasonably preventable failure of the monitoring system to provide valid data. Monitoring failures that are caused in part by poor maintenance or careless operation are not malfunctions. You must use all the valid data collected during all other periods in assessing compliance. Any averaging period for which you do not have valid monitoring data and such data are required constitutes a deviation from the monitoring requirements.

## § 63.8470 How do I demonstrate continuous compliance with the emission limitations?

- (a) You must demonstrate continuous compliance with each emission limit and operating limit in Tables 1 and 2 to this subpart that applies to you according to the methods specified in Table 5 to this subpart.
- (b) For each affected kiln that is equipped with an APCD that is not addressed in Table 2 to this subpart, or that is using process changes as a means of meeting the emission limits in Table 1 to this subpart, you must demonstrate continuous compliance with each emission limit in Table 1 to this subpart, and each operating limit established as required in § 63.8445(i)(2) according to the methods specified in your approved alternative monitoring procedures request, as described in §§ 63.8445(i)(1) and 63.8(f).
- (c) You must report each instance in which you did not meet each emission limit and each operating limit in this subpart that applies to you. This includes periods of startup, shutdown, malfunction, and routine control device maintenance. These instances are deviations from the emission limitations in this subpart. These deviations must be reported according to the requirements in § 63.8465.

- (d) During periods of startup, shutdown, and malfunction, you must operate according to your SSMP.
- (e) Consistent with §§ 63.6(e) and 63.7(e)(1), deviations that occur during a period of startup, shutdown, or malfunction are not violations if you demonstrate to the Administrator's satisfaction that you were operating according to an SSMP that satisfies the requirements of § 63.6(e) and your OM&M plan. The Administrator will determine whether deviations that occur during a period of startup, shutdown, or malfunction are violations, according to the provisions in § 63.6(e).
- (f) Deviations that occur during periods of control device maintenance covered by an approved routine control device maintenance exemption according to § 63.8420(e) are not violations if you demonstrate to the Administrator's satisfaction that you were operating in accordance with the approved routine control device maintenance exemption.
- (g) You must demonstrate continuous compliance with the operating limits in Table 2 to this subpart for visible emissions (VE) from tunnel kilns equipped with DLA, DIFF, or DLS/FF by monitoring VE at each kiln stack according to the requirements in paragraphs (g)(1) through (3) of this section.
- (1) Perform daily VE observations of each kiln stack according to the procedures of Method 22 of 40 GFR part 60, appendix A. You must conduct the Method 22 test while the affected source is operating under normal conditions. The duration of each Method 22 test must be at least 15 minutes.
- (2) If VE are observed during any daily test conducted using Method 22 of 40 CFR part 60, appendix A, you must promptly initiate and complete corrective actions according to your OM&M plan. If no VE are observed in 30 consecutive daily Method 22 tests for any kiln stack, you may decrease the frequency of Method 22 testing from daily to weekly for that kiln stack. If VE are observed during any weekly test, you must promptly initiate and complete corrective actions according to your OM&M plan, resume Method 22 testing of that kiln stack on a daily basis, and maintain that schedule until no VE are observed in 30 consecutive daily tests, at which time you may again decrease the frequency of Method 22 tenting to a weekly basis.
- (3) If VE are observed during any test conducted using Method 22 of 40 CFR part 60, appendix A, you must report these deviations by following the requirements in §63.8485.

# Notifications, Reports, and Records § 63.8480 What notifications must I submit and when?

- (a) You must submit all of the notifications in §§ 63.7(b) and (c), 63.8(f)(4), and 63.9 (b) through (e), (g)(1), and (b) that apply to vou, by the dates specified.
- (b) As specified in § 63.9(b)(2) and (3), if you start up your affected source before May 16, 2003, you must submit an Initial Notification not later than 120 calendar days after May 16, 2003.
- (c) As specified in § 63.9(b)(3), if you start up your new or reconstructed affected source on or after May 16, 2003, you must submit an Initia! Notification not later than 120 calendar days after you become subject to this subpart.
- (d) If you are required to conduct a performance test, you must submit a notification of intent to conduct a performance test at least 60 calendar days before the performance test is scheduled to begin, as required in § 63.7(b)(1).
- (e) If you are required to conduct a performance test as specified in Table 3 to this subpart, you must submit a Notification of Compliance Status as specified in § 63.9(h) and paragraphs (e)(1) and (2) of this section.
- (1) For each compliance demonstration that includes a performance test conducted according to the requirements in Table 3 to this subpart you must submit the Notification of Compliance Status, including the performance test results, before the close of business on the 60th calendar day following the completion of the performance test, according to § 62.10(d)(2)
- (2) In addition to the requirements in § 63.9(h)(2)(i), you must include the information in paragraphs (e)(2)(i) and (ii) of this section in your Notification of Compliance Status.
- (i) The operating limit parameter values established for each affected source with supporting documentation and a description of the procedure used to establish the values.
- iii) For each APCII that includes a rabril filter, if a bag leaf detection system is used, analysis and supporting documentation demonstrating conformance with EPA guidance and specifications for bag leak detection systems in 5.61.8450ter.
- If If you request a routine control device maintenance exemption a conding to U.C., 64.20(e), you must submit your read sit for the exemption no face that, 30 days before the compliance rate.

### § 63.8485 What reports must I submit and when?

- (a) You must submit each report in Table 6 to this subpart that applies to you.
- (b) Unless the Administrator has approved a different schedule for submission of reports under § 63.10(a), you must submit each report by the date in Table 6 to this subpart and as specified in paragraphs (b)(1) through (5) of this section.
- (1) The first compliance report must cover the period beginning on the compliance date that is specified for your affected source in § 63.8395 and ending on June 30 or December 31, and lasting at least 6 months, but less than 12 months. For example, if your compliance date is March 1, then the first semiannual reporting period would begin on March 1 and end on December 21.
- (2) The first compliance report must be postmarked or delivered no later than July 31 or January 31 for compliance periods ending on lune 30 and December 31, respectively.
- (3) Each subsequent comphance report must cover the semiannual reporting period from January 1 through June 30 or the semiannual reporting period from July 1 through December 31.
- (4) Each subsequent compliance report must be postmarked or delivered no later than July 31 or January 31 for compliance periods ending on June 30 and December 31, respectively.
- (5) For each affected source that is subject to permitting regulations pursuant to 40 CFR part 70 or 40 CFR part 71, if the permitting authority has established dates for submitting semiannual reports pursuant to 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR
- 71.6(a)(3)(iii)(A), you may submit the first and subsequent compliance reports according to the dates the permitting authority has established instead of according to the dates in paragraphs (b)(1) through (4) of this section
- (c) The comphance report must contain the information in paragraphs (c) I) through (7) of this section
  - 11) Company name and address
- (2) Statement by a responsible official with that official's name, title, and signature certifying that, based on information and belief formed after reasonable inquiry, the statements and information in the report are true as curate, and complete.
- (3) Dure of report and beginning and ending dates of the reporting period.
- (4) If you had a startup, shutdown or mathematical during the reporting period and you took actions consistent with your ISMF and DRAM plan, the

- compliance report must include the information specified in §63.10(d)(5)(i).
- (5) A description of control device maintenance performed while the control device was offline and the kiln controlled by the control device was operating, including the information specified in paragraphs (c)(5)(i) through (iii) of this section.
- (i) The date and time when the control device was shutdown and restarted.
- (ii) Identification of the kiln that was operating and the number of hours that the kiln operated while the control device was offline.
- (iii) A statement of whether or not the control device maintenance was included in your approved routine control device maintenance exemption developed as specified in § 63.8420(e). If the control device maintenance was included in your approved routine control device maintenance exemption, then you must report the information in paragraphs (c)(5)(iii)(A) through (C) of this section.
- (A) The total amount of time that the kiln controlled by the control device operated during the current semiannual compliance period and during the previous semiannual compliance period.
- (B) The amount of time that each kiln controlled by the control device operated while the control device was offline for maintenance covered under the routine control device maintenance exemption during the current semiannual compliance period and during the previous semiannual compliance period.
- (C) Based on the information recorded under paragraphs (c)(5)(iii)(A) and (B) of this section, compute the annual percent of kiln operating uptime during which the control device was offline for routine maintenance using Equation 1 of this section.

$$EM = \frac{DT_p + DT_c}{EU_b + EU_c} \quad (100)$$
 (Eq. 1)

Where:

- RM=Annual percentage of kiln uptime during which control device was offline for routine control device maintenance
- UTn=Control device downtime claimed under the routine control device maintenance exemption for the previous semiannual compliance period
- IT.=Control device downtime chimed under the routine control device maintenance exemption for the current semiannual compliance period.

KUp=Kiln uptime for the previous semiannual compliance period KUp=Kiln uptime for the current semiannual compliance period

(6) If there are no deviations from any emission limitations (emission limits or operating limits) that apply to you, the compliance report must contain a statement that there were no deviations from the emission limitations during the reporting period.

(7) If there were no periods during which the CMS was out-of-control as specified in your OM&M plan, the compliance report must contain a statement that there were no periods during which the CMS was out-of-control during the reporting period.

- (d) For each deviation from an emission limitation (emission limit or operating limit) that occurs at an affected source where you are not using a CMS to comply with the emission limitations in this subpart, the compliance report must contain the information in paragraphs (c)(1) through (5) and paragraphs (d)(1) and (2) of this section. This includes periods of startup, shutdown, malfunction, and routine control device maintenance.
- (1) The total operating time of each affected source during the reporting period.
- (2) Information on the number, duration, and cause of deviations (including unknown cause, if applicable), as applicable, and the corrective action taken.
- (e) For each deviation from an emission limitation (emission limit or operating limit) occurring at an affected source where you are using a GMS to comply with the emission limitations in this subpart, you must include the information in paragraphs (c)(1) through (5) and paragraphs (e)(1) through (13) of this section. This includes periods of startup, shutdown, malfunction, and routine control device maintenance.
- The total operating time of each affected source during the reporting period.
- (2) The date and time that each malfunction started and stopped.
- (3) The date and time that each CMS was inoperative, except for zero (lowlevel) and high-level checks.
- (4) The date, time, and duration that each CMS was out-of-control, including the pertinent information in your OM&M plan.
- (5) The date and time that each deviation started and stopped, and whether each deviation occurred during a period of startup, shutdown, or malfunction; during routine control device maintenance covered in your approved mutine control device.

maintenance exemption; or during another period.

- (6) A description of corrective action taken in response to a deviation.
- (7) A summary of the total duration of the deviation during the reporting period and the total duration as a percent of the total source operating time during that reporting period.
- (8) A breakdown of the total duration of the deviations during the reporting period into those that were due to startup, shutdown, control equipment problems, process problems, other known causes, and other unknown causes.
- (9) A summary of the total duration of CMS downtime during the reporting period and the total duration of CMS downtime as a percent of the total source operating time during that reporting period.
- (10) A brief description of the process units.
  - (11) A brief description of the CMS.
- (12) The date of the latest CMS certification or audit.
- (13) A description of any changes in CMS, processes, or control equipment since the last reporting period.
- (f) If you have obtained a title V operating permit according to 40 CFR part 70 or 40 CFR part 71, you must report all deviations as defined in this subpart in the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A). If you submit a compliance report according to Table 6. to this subpart along with, or as part of, the semiannual monitoring report required by 40 CFR 70.6(a)(3)(iii)(A) or 40 CFR 71.6(a)(3)(iii)(A), and the compliance report includes all required information concerning deviations from any emission limitation (including any operating limit), then submitting the compliance report will satisfy any obligation to report the same deviations in the semiannual monitoring report. However, submitting a compliance report will not otherwise affect any obligation you may have to report deviations from permit requirements to the permitting authority.

#### § 63.8490 What records must I keep?

- (a) You must keep the records listed in paragraphs (a)(1) through (4) of this section.
- (1) A copy of each notification and report that you submitted to comply with this subpart, including all documentation supporting any Initial Notification or Notification of Compliance Status that you submitted, according to the requirements in § 63,10(b)(2)(viv)

- (2) The records in § 63.6(e)(3)(iii) through (v) related to startup, shutdown, and malfunction.
- (3) Records of performance tests as required in § 63.10(b)(2)(viii).
- (4) Records relating to control device maintenance and documentation of your approved routine control device maintenance exemption, if you request such an exemption under § 63.8420(e).
- (b) You must keep the records required in Table 5 to this subpart to show continuous compliance with each emission limitation that applies to you.
- (c) You must also maintain the records listed in paragraphs (c)(1) through (6) of this section.
- (1) For each bag leak detection system, records of each alarm, the time of the alarm, the time corrective action was initiated and completed, and a brief description of the cause of the alarm and the corrective action taken.
- (2) For each deviation of an operating limit parameter value, the date, time, and duration of the deviation, a brief explanation of the cause of the deviation and the corrective action taken, and whether the deviation occurred during a period of startup, shutdown, or malfunction.
- (3) For each affected source, records of production rates on a fired-product hasis
- (4) Records for any approved alternative monitoring or test procedures.
- (5) Records of maintenance and inspections performed on the APCD.
- (6) Current copies of your SSMP and OM&M plan, including any revisions, with records documenting conformance.

### § 63.8495 In what form and for how long must I keep my records?

- (a) Your records must be in a form suitable and readily available for expeditious review, according to § 63.10(b)(1).
- (b) As specified in § 63.10(b)(1), you must keep each record for 5 years following the date of each occurrence, measurement, maintenance, corrective action, report, or record.
- (c) You must keep each record onsite for at least 2 years after the date of each occurrence, measurement, maintenance, corrective action, report, or record, according to § 63.10(b)(1). You may keep the records offsite for the remaining 3 years.

### Other Requirements and Information

### § 63.8505 What parts of the General Provisions apply to me?

Table 7 to this subpart shows which parts of the General Provisions in §§ 63.1 through 63.15 apply to you.

### § 63,8510 Who implements and enforces this subpart?

(a) This subpart can be implemented and enforced by us, the U.S. EPA, or a delegated authority such as your State, local, or tribal agency. If the U.S. EPA Administrator has delegated authority to your State, local, or tribal agency, then that agency, in addition to the U.S. EPA, has the authority to implement and enforce this subpart. You should contact your U.S. EPA Regional Office to find out if implementation and enforcement of this subpart is delegated to your State, local, or tribal agency.

(b) In delegating implementation and enforcement authority of this subpart to a State, local, or tribal agency under section 40 CFF; part 63, subpart E, the authorities contained in paragraph (c) of this section are retained by the Administrator of the U.S. EPA and are not transferred to the State, local, or

tribal agency.

(c) The authorities that cannot be delegated to State, local, or tribal agencies are as specified in paragraphs (c)(1) through (4) of this section.

- (1) Approval of alternatives to the applicability requirements in §§ 63.8385 and 63.8390, the compliance date requirements in § 63.8395, and the non-opacity emission limitations in § 63.8405.
- (2) Approval of major changes to test methods under § 63.7(e)(2)(ii) and (f) and as defined in § 63.90.
- (3) Approval of major changes to monitoring under § 63.8(f) and as defined in § 63.90.
- (4) Approval of major changes to recordkeeping and reporting under § 63.10(f) and as defined in § 63.90.

### $\S$ 63.8515 What definitions apply to this subpart?

Terms used in this subpart are defined in the Clean Air Act, in § 63.2, and in this section as follows:

Air pollution control device (APCE) means any equipment that reduces the quantity of a pollutant that is emitted to the air.

Rog leaf, detection system means an instrument that is capable of monitoring PM loadings in the exhaust of a labric filter in order to detect bag failures. A bag leaf detection system includes, but is not limited to, an instrument that operates on triboelectric, light-scattering, light-transmittance, or other effects to monitor relative PM loadings.

Brial: and structural clay products (USCP) manufacturing facility means a plant site that manufactures brief (including but not limited to, race brief) structural briek, and brick pavers to clay pipe, roof tide entruded floor and wall that and or other extruded, dimensional

clay products. Brick and structural clay products manufacturing facilities typically process raw clay and shale, form the processed materials into bricks or shapes, and dry and fire the bricks or shapes

Deviation means any instance in which an affected source subject to this subpart, or an owner or operator of such a source:

(1) Fails to meet any requirement or obligation established by this subpart including, but not limited to, any emission limitation (including any operating limit) or work practice standard;

(2) Fails to meet any term or condition that is adopted to implement an applicable requirement in this subpart for any affected source required to obtain such a permit; or

(3) Fails to meet any emission limitation (including any operating limit) or work practice standard in this subpart during startup, shutdown, or malfunction, regardless of whether or not such failure is permitted by this subpart.

Dry lime injection fabric filter (DIFF) means an APCD that includes continuous injection of hydrated lime or other sorbent into a duct or reaction chamber followed by a fabric filter.

Dry lime scrubber fabric filter (DLS/ FF) means an APCD that includes continuous injection of humidified nydrated time or other sorbent into a reaction chamber followed by a fabric filter. These systems typically include recirculation of some of the sorbent.

Dry limestone adsorber (DLA) means an APCD that includes a limestone storage bin, a reaction chamber that is essentially a packed tower filled with limestone and may or may not include a peeling drum that mechanically scrapes reacted limestone to regenerate the stone for reuse.

Emission limitation means any emission limit or operating limit.

Fabric filter means an APCD used to capture PM by filtering a gas stream through filter media: also known as a baghouse.

Initial startup means:

11) For a new or reconstructed turnel hilo controlled with a DLA, and for a tunnel hilo that would be considered reconstructed but for § 63.83900011 or § 63.83900012), the time at which the temperature in the Filh, first reaches 260 °C (500 °C) and the filh contains product, or

(2) For a new or reconstructed tunnel fall controlled with a DIFF, DI SeFF or WS, the time at which the Jala first reacher a level of production that is equal to TS percent of the Jala design capacity or 32 months after the affected source begins firing BSCP, whichever is earlier.

Liln exhaust process stream means the portion of the exhaust from a tunnel kiln that exhausts directly to the atmosphere (or to an APCD), rather than to a sawdust dryer.

Large tunnel kiln means a tunnel kiln (existing, new, or reconstructed) with a design capacity equal to or greater than 9.07 Mg/hr (10 tph) of fired product.

Particulate matter (PM) means, for purposes of this subpart, emissions of PM that serve as a measure of total particulate emissions, as measured by Method 5 140 CFR part 60, appendix A), and as a surrogate for metal HAP contained in the particulates including, but not limited to, antimony, arsenic, beryllium, cadmium, chromium, cobalt, lead, manganese, mercury, nickel, and selenium.

Plant site means all contiguous or adjoining property that is under common control, including properties that are separated only by a road or other public right-of-way. Common control includes properties that are owned, leased, or operated by the same entity, parent entity, subsidiary, or any combination thereof.

Research and development kiln means any kiln whose purpose is to conduct research and development for new processes and products and is not engaged in the manufacture of products for commercial sale, except in a deminimis manner.

Responsible official means responsible official as defined in 40 CFR 70.2.

Small tunne! Juln means a tunnel kiln (existing, new, or reconstructed) with a design capacity less than 9.07 Mg/hr (10 tph) of fired product.

Startup means the setting in operation of an affected source and starting the production process

Tunnel idin means any continuous liln that is used to fire BSCP. Some tunnel kilns have two process streams, including a process stream that exhausts directly to the atmosphere or to an APCD, and a process stream in which the kiln exhaust is ducted to a sawdust dryer where it is used to dry sawdust before being emitted to the atmosphere.

Tunnel little design cupacity means the maximum amount of brick in fulgitions), that a kiln is designed to produce in one year directed by the number of hours in a year (8.760 hours). If a kiln is modified to increase the capacity, the design capacity is considered to be the capacity following modifications.

Wet scrubber (WS) income an APCD that user water which may include caustic additives or other chemicals as the sorbent. Wet scrubbers may use any

of various design mechanisms to increase the contact between exhaust gases and the sorbent.

### Tables to Subpart [JJJ] of Part 63

As stated in § 63.8405, you must meet each emission limit in the following table that applies to you:

For each	You must meet the foll limits	owing emission	Or you must comply with the following
Existing large tunnel kiln (design capacity10 tph of fired product), excluding any process stream that is ducted to a sawdust dryer.	a. HF emissions must not exceed 0.029 kilograms per megagram (kg/Mg) (0.057 pounds per ton (lb/ton)) of fired product.		Reduce uncontrolled HF emissions by at leas 90 percent.
prior to July 22, 2002; or including any process stream that exhausts directly to the almosphere or to an APCD and any process stream that is first ducted to a sawdust on or after July 22, 2002; each new or reconstructed small tunnel kiln (design capacity <10 tph of fired product), including all process streams; each tunnel kiln that would be considered reconstructed but for § 63.8390(i)(1), including all process streams; and each large tunnel kiln previously equipped with a DLA that would be considered reconstructed but for § 63.8390(i)(2), in-	<ul> <li>b. HCl emissions must (0.26 lb/ton) of fired</li> </ul>	not exceed 0.13 kg/Mg product, not exceed 0.21 kg/Mg	Reduce uncontrolled HCI emissions by a least 30 percent.  Not applicable.
cluding all process streams.  2. New or reconstructed large tunnel klin, including all process streams.	Mg (0.057 lb/ton) of b. HCl emissions mus Mg (0.056 lb/ton) of	t not exceed 0.028 kg/ fired product. t not exceed 0.060 kg/	Reduce uncontrolled HF emissions by at leas 90 percent. Reduce uncontrolled HC! emissions by a least 85 percent. Not applicable.
As stated in § 63.8405, you must meet ea	ich operating limit in	the following table th	nat applies to you:
TABLE 2 TO	SUBPART JJJJJ OF	PART 63.—OPERAT	ING LIMITS
For each		You must	
1. Kiin equipped with a DLA		block period at or ab- ing the performance of the p	e amount of limestone in the limestone hopper, at the top of the DLA), and DLA at all times; ne feeder setting at or above the level estabormance test; and e of limestone from the same source as was formance test; maintain records of the source se; and the DLA stack.
2. Kiln equipped with a DIFF or DLS/FF		a. If you use a bag to within 1 hour of a bacteristic actions in maintain the fabric fill than 5 percent of the ing period; or maintain b. Maintain free-flowing APCD at all times fill.	eak detection system, initiate corrective action ag leak detection system alarm and complete accordance with your OM&M plan; operate and ter such that the alarm is not engaged for more total operating time in a 6-month block report- n no VE from the DIFF or DLS/FF stack; and g lime in the feed hopper or silo and to the or continuous injection systems; maintain the above the level established during the perform-
3. Kiln equipped with a WS		Maintain the average period at or above th performance test; and b. Maintain the average	e scrubber pressure drop for each 3-hour block e average pressure drop established during the

riod at or above the average scrubber liquid pH established during

c. Maintain the average scrubber liquid flow rate for each 3 hour block period at or above the average scrubber liquid flow rate established

d. If chemicals are added to the sorubber water, maintain the average scrubber chemical feed rate for each 3-hour block period at or above the average scrubber chemical feed rate established during the per-

the performance test; and

tournance test.

during the performance lest; and

As stated in § 63.8445, you must conduct each performance test in the following table that applies to you:

### TABLE 3 TO SUBPART JUJUJU OF PART 63.—REQUIREMENTS FOR PERFORMANCE TESTS

For each	You must	Using .	According to the following requirements .
1. Kiln	Select locations of sampling ports and the number of traverse points	Method 1 or 1A of 40 CFR part 60, appendix A.	Sampling sites must be located at the outlet of the APCD and prior to any releases to the atmosphere for all affected sources. If you choose to meet the percent emission reduction requirements for HF or HCl, a sampling site must also be located at the APCD mist.
	b Determine velocities and volu- metric flow rate.	Method 2 of 40 CFR part 60, appendix A.	You may use Method 2A, 2C, 2D, 2F, or 2G of 40 CFR part 60, appendix A, as appropriate, as an alternative to using Method 2 of 40 CFR part 60, appendix A.
	<ul> <li>c. Conduct gas molecular weight analysis.</li> </ul>	Method 3 of 40 CFR рап 60, ар- pendix A.	You may use Method 3A or 3B or 40 CFR part 60, appendix A, as appropriate, as an alternative to using Method 3 of 40 CFR part 60, appendix A.
		Method 4 of 40 CFR part 60, appendix A.	
	the stack gas. e Measure HF and HCI emissions.	Method 26A of 40 CFR part 60, appendix A; or	Conduct the test while operating at the maximum production level You may use Method 26 of 40 CFR part 60, appendix A as an alternative to using Method 26A of 40 CFR part 60, appendix A, when no acid PM (e.g., HF or HCI dissolved in water droplets emitted by sources controlled by a WS) is present.
		Method 320 of 40 CFR part 63, appendix A	Conduct the test while operating at the maximum production tevel. When using Method 320 of 40 CFR part 63, appendix A you must follow the analyte spiking procedures of section 13 of Method 320 of 40 CFR part 63, appendix A, unless you can demonstrate that the complete spiking procedure has been conducted at a similal source.
	! Measure PM emissions	Method 5 of 40 CFR part 60 ap- pendo A	
Kith that is complying with pro- duction-based emission limits	Determine the production rate during each test run in order to determine compliance with production-based emission limits.	the performance tests (e.g., no	production rate, on a fired-prod- uct basis of the affected source
3. Filn equipped with a DLA	a Establish the operating limit for the average pressure drop acrost the DLA.		

### TABLE 3 TO SUBPART JJJJJ OF PART 63.—REQUIREMENTS FOR PERFORMANCE TESTS—Continued

For each	You must	Using	According to the following requirements
	b. Establish the operating limit for the limestone feeder setting.	Data from the limestone feeder during the performance test.	You must ensure that you maintain an adequate amount of limestone in the limestone hopper, storage bin (located at the top of the DLA), and DLA at all times during the performance test. You must establish your limestone feeder setting one week prior to the performance test and maintain the feeder setting for the one-week period that precedes the performance test and during the performance test.
	<ul> <li>c. Document the source and grade of limestone used.</li> </ul>	Records of limestone purchase.	
<ol> <li>Kiln equipped with a DIFF or DLS/FF.</li> </ol>	the lime feeder setting.	the periormance test.	For continuous lime injection systems, you must ensure that lime in the feed hopper or silo and to the APCD is free-flowing at all times during the performance test and record the feeder setting for the three test runs. If the feed rate setting varies during the three test runs, determine and record the average feed rate from the three test runs.
5. Kiln equipped with a WS	Establish the operating limit for the average scrubber pressure drop.	Data from the pressure drop measurement device during the performance test.	You must continuously measure the scrubber pressure drop, determine and record the block average pressure drop values for the three test runs, and determine and record the 3-hour block average of the recorded pressure drop measurements for the three test runs.
	b. Establish the operating limit for the average scrubber liquid pH.	Data from the pH measurement device during the performace test.	
	c. Establish the operating limit for the average scrubber liquid flow rate.	Data from the flow rate measure- ment device during the perform- ance test.	You must continuously measure the scrubber liquid flow rate, determine and record the block average flow rate values for the three test runs, and determine and record the 3-hour block average of the recorded flow rate measurements for the three test runs.
Kiln equipped with a WS that includes chemical addition to the water.	Establish the operating limit for the average scrubber chemical feed rate.	Data from the chemical feed rate measurement device during the performance test.	You must continuously measure the scrubber chemical feed rate, determine and record the block average chemical feed rate values for the three test runs, and determine and record the 3-hour block average of the recorded chemical feed rate measurements for the three test runs.

As stated in  $\S$  63.8455, you must demonstrate initial compliance with each emission limitation that applies to you according to the following table:

### TABLE 4 TO SUBPART JUJUJ OF PART 63.—INITIAL COMPLIANCE WITH EMISSION LIMITATIONS

You have demonstrated initial compliance if For the following emission limitation . . For each . . Existing large tunnel kiln (design capacity a. HF emissions must not exceed 0.029 kg/ i. The HF emissions measured using Method Mg (0.057 lb/ton) of fired product, or uncon-26A of 40 CFR part 60, appendix A or \_10 tph of fired product), excluding any proc-Method 320 of 40 CFR part 63, appendix A trolled HF emissions must be reduced by at ess stream that is ducted to a sawdust dryer over the period of the initial performance least 90 percent; and prior to July 22, 2002; or including any proctest, according to the calculations in ess stream that exhausts directly to the at-§ 63.8445(g)(1), do not exceed 0.029 kg/Mg mosphere or to an APCD and any process (0.057 lb/ton); or uncontrolled HF emissions stream that is first ducted to a sawdust dryer measured using Method 26A of 40 CFR on or after July 22, 2002; each new or reconpart 60, appendix A or Method 320 of 40 structed small tunnel kiln (design capacity CFR part 63, appendix A over the period of <10 tph of fired product), including all procthe initial performance test are reduced by ess streams; each tunnel kiln that would be at least 90 percent, according to the calreconstructed but considered culations in § 63.8445(g)(2); and § 63.8390(i)(1), including all process streams: ii. You establish and have a record of the opand each large tunnel kiln previously erating limits listed in Table 2 to this subequipped with a DLA that would be considpart over the 3-hour performance test durered reconstructed but for § 63.8390(i)(2), ining which HF emissions did not exceed cluding all process streams. 0.029 kg/Mg (0.057 lb/ton) or uncontrolled HF emissions were reduced by at least 90 nercent. b. HCI emissions must not exceed 0.13 kg/Mg The HCI emissions measured using Method 26A of 40 CFR part 60, appendix A or (0.26 lb/ton) of fired product; or uncontrolled HCI emissions must be reduced by at least Method 320 of 40 CFR part 63, appendix A over the period of the initial performance 30 percent; and test, according to the calculations in §63.8445(g)(1), do not exceed 0.13 kg/Mg (0.26 lb/ton); or uncontrolled HCI emissions measured using Method 26A of 40 CFR part 60, appendix A or Method 320 of 40 CFR part 63, appendix A over the period of the initial performance test are reduced by at least 30 percent, according to the calculations in  $\S 63.8445(g)(2)$ ; and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the 3-hour performance test during which HCI emissions did not exceed 0.13 kg/Mg (0.26 lb/ton) or uncontrolled HCI emissions were reduced by at least 30 percent. The PM emissions measured using Method c PM emissions must not exceed 0.21 kg/Mg ii 5 of 40 CFR part 60, appendix A lover the (0.42 (b/ton) of fired product period of the initial performance test, accordina to the calculations §63.8445(g)(1) do not exceed 0.21 kg/Mg (0.40 lb/ton); and ii. You establish and have a record of the operating limits listed in Table 2 to this subpart over the 5-hour performance test during which PM emissions did not exceed 0.21 Fg/Mg (0.42 lb/ton). The HF emissions measured using Method a. HF emissions must not exceed 0.029 Fg' 2. New or reconstructed large tunnel kiln, in-26A of 40 CFR part 60 appendix A or Mg (6.057 (bitton) of fired product, at unconpluding all process streams. Method 320 of 40 GFR part 63, appendix A trolled HF emissions must be reduced by at over the period of the initial performance least 90 percent, and test, according to the calculations in 4,63,8445(g)(1), do not exceed 0.029 kg/Mg. (0.057 lb/lon); or uncontrolled HF emissions measured using Method 26A of 46 GFR part 60 appendu A or Method 320 of 40 GFR part 63, appendix A over the period of the initial performance test are reduced by at least 90 percent, according to the calculations in § 60.8445 gi(2), and

For each	For the following emission limitation	You have demonstrated initial compliance if
		ii. You establish and have a record of the op- erating limits listed in Table 2 to this sub- part over the 3-hour performance test dur- ing which HF emissions did not exceed 0.029 kg/Mg (0.057 lb/ton) or uncontrolled HF emissions were reduced by at least 90 percent.
	b. HCI emissions must not exceed 0.028 kg/ Mg (0.056 lb/ton) of fired product; or uncon- trolled HCI emissions must be reduced by at least 85 percent; and	i. The HCI emissions measured using Method 26A of 40 CFR part 60, appendix A or Method 320 of 40 CFR part 63, appendix A over the period of the initial performance test, according to the calculations in § 63.8445(g)(1), do not exceed 0.028 kg/Mg (0.056 lb/ton); or uncontrolled HCI emissions measured using Method 26A of 40 CFR part 60, appendix A or Method 320 of the initial performance test are reduced by at least 85 percent, according to the calculations in § 63.8445(g)(2); and
		ii. You establish and have a record of the op- erating limits listed in Table 2 to this sub- part over the 3-hour performance test dur- ing which HCl emissions did not exceed 0.028 kg/Mg (0.056 lb/ton) or uncontrolled HCl emissions were reduced by at least 85 percent.
	c. PM emissions must not exceed 0.060 kg/ Mg (0.12 lb/ton) of fired product	<ol> <li>The PM emissions measured using Method 5 of 40 CFR part 60, appendix A, over the period of the initial performance test, ac- cording to the calculations in § 63.8445(g)(1), do not exceed 0.060 kg/Mg (0.12 lb/ton); and</li> </ol>
		ii. You establish and have a record of the op- erating limits listed in Table 2 to this sub- part over the 3-hour performance test dur- ing which PM emissions did not exceed 0.060 kg/Mg (0.12 lb/ton).

As stated in § 63.8470, you must demonstrate continuous compliance with each emission limit and operating limit that applies to you according to the following table:

For each	For the following emission limits and operating limits	You must demonstrate continuous compliance by
Kiln equipped with a DLA  , , , , , , , , , , , , , , , ,	Each emission limit in Table 1 to this subpart and each operating limit in Item 1 of Table 2 to this subpart for kilns equipped with a DLA.	<ol> <li>Collecting the DLA pressure drop data according to §63.8450(a); reducing the DLA pressure drop data to 3 hour block averages according to §63.8450(a); maintaining the average pressure drop across the DLA for each 3-hour block period at or above the average pressure drop established during the performance test, and</li> <li>Verifying that the limestone hopper and storage bin (located at the top of the DLA) contain adequate limestone by performing a daily visual check; and</li> <li>Recording the limestone feeder setting daily to verify that the feeder setting is being maintained at or above the level established during the performance test; and</li> <li>Using the same grade of limestone from the same source as was used during the performance test; maintaining records of the source and type of limestone; and</li> <li>Performing VE observations of the DLA stack at the tracquency specified in §63.8470(g) using Method 22 of 40 CEB part 60, appendix A; maintaining no VE from the DLA otack.</li> </ol>

## TABLE 5 TO SUBPART JUJUJ OF PART 63.—CONTINUOUS COMPLIANCE WITH EMISSION LIMITS AND OPERATING LIMITS—Continued

For each .	For the following emission limits and operating limits $$	You must demonstrate continuous compliance by
2 Kiln equipped with a DIFF or DLS/FF.	Each emission limit in Table 1 to this subpart and each operating limit in Item 2 of Table 2 to this subpart for kilns equipped with DIFF or DLS/FF.	If you use a bag leak detection system, initiating corrective action within 1 hour of a bag leak detection system alarm and completing corrective actions in accordance with your OM&M plan; operating and maintaining the fabric filter such that the alarm is not engaged for more than 5 percent of the total operating time in a 6-month block reporting period, in calculating this operating time fraction, if inspection of the fabric filter demonstrates that no corrective action is required, no alarm time is counted; if corrective action is required, each alarm is counted as a minimum of 1 hour; if you take longer than 1 hour to initiate corrective action, the alarm time is counted as the actual amount of time taken by you to initiate corrective action; or performing VE observations of the DIFF or DLS/FF stack at the frequency specified in §63.8470(g) using Method 22 of 40 CFR part 60, appendix A; maintaining no VE from the DIFF or DLS/FF stack; and  iii. Verifying that time is free-flowing via a toad cell, carrier gas/lime flow indicator, carrier gas pressure drop measurement system, or other system; recording all monitor or sensor output, and if time is found not to be free flowing, promptly initiating and completing corrective actions in accordance with your OM&M plan; recording the teeder setting once during each shift of operation to verify that the feeder setting is being maintained at or above the level estimation.
3. Kiln equipped with a WS	Each emission limit in Table 1 to this subpart and each operating limit in Item 3 of Table 2 to this subpart for kilns equipped with WS.	tablished during the performance test.  i. Collecting the scrubber pressure drop data according to § 63.8450(a); reducing the scrubber pressure drop data to 3-hour block averages according to § 63.8450(a); maintaining the average scrubber pressure drop for each 3-hour block period at or above the average pressure drop established during the performance test; and  ii. Collecting the scrubber liquid pH data according to § 63.8450(a); reducing the scrubber fiquid pH data to 3-hour block averages according to § 63.8450(a); maintaining the average scrubber liquid pH for each 3-hour block period at or above the average scrubber liquid pH established during the performance test; and  iii. Collecting the scrubber liquid flow rate data according to § 63.8450(a); reducing the scrubber liquid flow rate data to 3-hour block, averages according to § 63.8450(a); maintaining the average scrubber liquid flow rate established during the performance test, and  iv. If chemicals are added to the scrubber water, collecting the scrubber chemical feed rate data according to § 63.8450(a); reducing the scrubber chemical feed rate data according to § 63.8450(a); reducing the scrubber chemical feed rate data according to § 63.8450(a); reducing the scrubber chemical feed rate for each 3-hour block, averages according to § 63.8450(a); maintaining the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3-hour block, period at or above the average scrubber chemical feed rate for each 3

As stated in § 63.8485, you must submit each report that applies to you according to the following table:

### TABLE 6 TO SUBPART JUJUJ OF PART 63.—REQUIREMENTS FOR REPORTS

Tou must submit	The report must contain	nou must submit the report
1 4 compliance report	a If there are no deviations from any emission limitations remission limits operating limits; that apply to you, a statement that there were no deviations from the emission limitations during the reporting period. If there were no periods during which the CMS was out-of-control as specified in your OM&M plan, a statement that there were no periods during which the CMS was out-of-control during the reporting period.	

TABLE 6 TO SUBPART JJJJJ OF PART 63.—REQUIREMENTS FOR REPORTS—Continued			
You must submit	The report must contain	You must submit the report	
	b. If you have a deviation from any emission limitation (emission limit, operating limit) during the reporting period, the report must contain the information in §63.8485(d) or (e). If there were periods during which the CMS was out-of-control, as specified in your OM&M plan, the report must contain the information in §63.8485(e).	Semiannually according to the requirements in §63.8485(b).	
	c. If you had a startup, shutdown or malfunction during the reporting period and you took actions consistent with your SSMP, the com- pliance report must include the information in §63.10(d)(5)(i).	Semiannually according to the requirements in § 63.8485(b).	
<ol> <li>An immediate startup, shutdown, and malfunction report if you took actions during a startup, shut- down, or malfunction during the reporting period that are not con- sistent with your SSMP.</li> </ol>		By fax or telephone within 2 working days after starting actions inconsistent with the plan.	
	b. The information in § 63.10(d)(5)(ii)	By letter within 7 working days after the end of the event unless you have made alternative arrangements with the permitting authority.	

As stated in § 63.8505, you must comply with the General Provisions in §§ 63.1 through 63.15 that apply to you according to the following table:

TABLE 7 TO SUBPART JJJJJ OF PART 63.---APPLICABILITY OF GENERAL PROVISIONS TO SUBPART JJJJJ

Citation	Subject	Brief description	Applies to subpart
§ 63.1	Applicability	Initial applicability determination; applicability after standard established; permit requirements; extensions, notifications.	Yes.
§ 63.2	Definitions	Definitions for part 63 standards	Yes.
§ 63.3	Units and Abbreviations	Units and abbreviations for part 63 standards	Yes.
§ 63.4	Prohibited Activities	Compliance date; circumvention; severability	Yes.
§ 63.5	Construction/Reconstruction	Applicability; applications; approvals	Yes.
§ 63.6(a)	Applicability	General Provisions (GP) apply unless compliance extension; GP apply to area sources that become major.	Yes.
§ 63.6(b)(1)–(4)	Compliance Dates for New and Reconstructed sources.	Standards apply at effective date; 3 years after effective date; upon startup; 10 years after construction or reconstruction commences for section 112(f).	Yes.
§ 63.6(b)(5)	Notification	Must notify if commenced construction or reconstruction after proposal.	Yes.
§ 63.6(b)(6)	[Reserved].		
§ 63.6(b)(7)	Compliance Dates for New and Re- constructed area Sources That Be- come Major.	Area sources that become major must comply with major source standards immediately upon becoming major, regardless of whether required to comply when they were area sources.	Yes.
§ 63.6(c)(1)-(2)	Compliance Dates for Existing Sources	Comply according to date in subpart, which must be no later than 3 years after effective date; for section 112(f) standards, comply within 90 days of effective date unless compliance extension.	Yes.
§ 63.6(c)(3)-(4)	[Reserved]		
§ 63.6(c)(5)	Compliance Dates for Existing area Sources That Become Major.	Area sources that become major must comply with major source standards by date indicated in subpart or by equivalent time period (for example, 3 years).	Yes.
§ 63.6(d)	[Reserved].		
§ 63.6(e)(1)–(2)	Operation & Maintenance	Operate to minimize emissions at all times; correct mal- functions as soon as practicable; requirements inde- pendently entorceable; information Administrator will use to determine it operation and maintenance require- ments were met.	Yes.
§ 63.6(e)(3)	Startup, Shuldown, and Malfunction Plan (SSMP).	(SSM) and SSMP; content of SSMP.	
§ 03.6(I)(1)		You must comply with emission standards at all limes except during SSM.	1 #3.
§ 63.6(l)(2)–(3)	Methods for Determining Compliance .	Compliance based on performance test, operation and maintenance plans, records, inspection.	Yes.
§ 63.6(g)	Alternative Standard	Procedures for getting an afternative standard	řes.
§ 63.6(h)	Opacity/VE Standards	Requirements for opacity and VE standards	No, not applicable.

TABLE 7 TO SUBPART JJJJJ OF PART €3.—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART JJJJJ—Continued

Citation	Subject	Brief description	Applies to subpart JJJJJ
§ 63.6(i)	Compliance Extension	Procedures and criteria for Administrator to grant compliance extension.	Yes.
§ 63.6(j)	Presidential Compliance Exemption	President may exempt source category	Yes
§ 63.7(a)(1)−(2)	Performance Test Dates	Dates for conducting initial performance testing and other compliance demonstrations; must conduct 180 days after first subject to rule.	Υes.
§ 63.7(a)(3)	Section 114 Authority	Administrator may require a performance test under CAA section 114 at any time.	Yes.
§ 63.7(b)(1)	Notification of Performance Test	Must notify Administrator 60 days before the test	Yes.
§ 63.7(b)(2)	Notification of Rescheduling	Must notify Administrator 5 days before scheduled date of rescheduled date.	Yes.
§ 63.7(c)	Quality Assurance(QA)/Test Plan	Requirements; test plan approval procedures; perform- ance audit requirements; internal and external QA pro- cedures for testing.	Yes.
§ 63.7(d)	Testing Facilities	Requirements for testing facilities	Yes.
§63 7(e)(1)	Conditions for Conducting Performance Tests.	Performance tests must be conducted under representa- tive conditions.	No, § 63.8445 specifies require- ments.
		Cannot conduct performance tests during SSM: not a vio- lation to exceed standard during SSM.	Yes.
§ 63.7(e)(2)-(3)	Conditions for Conducting Performance Tests.	Must conduct according to subpart and EPA test methods unless Administrator approves afternative; must have at least three test runs of at least 1 hour each; compliance is based on arithmetic mean of three runs; conditions	Yes.
§ 63.7(f)	Alternative Test Method	when data from an additional test run can be used.  Procedures by which Administrator can grant approval to use an alternative test method.	Yes.
§63.7(g)	Performance Test Data Analysis	Must include raw data in performance test report, must submit performance test data 60 days after end of test with the notification of compliance status.	Yes.
	Waiver of Tests	Procedures for Administrator to waive performance test Subject to all monitoring requirements in subpart	Yes. Yes.
§ 63.8(a)(2)	Performance Specifications	Performance Specifications in appendix B of 40 CFR part 60 apply.	Yes.
§ 63.8(a)(3)	[Reserved]		
§ 63.8(a)(4) § 63.8(b)(1)	Monitoring with Flares	Requirements for flares in § 63.11 apply	No, ποι applicable. Yes.
§ 63.8(b)(2)-(3)	Multiple Effluents and Multiple Moni- toring Systems.	ministrator approves alternative.  Specific requirements for installing and reporting on monitoring systems.	Yes.
§ 63.8(c)(1)	Monitoring System Operation and Maintenance.		Yes
	Routine and Predictable SSM	Reporting requirements for SSM when action is described in SSMP.	Yes.
	SSM not in SSMP	Reporting requirements for SSM when action is not de- scribed in SSMP.	Yes.
	tenance Requirements.	How Administrator determines if source complying with operation and maintenance requirements.	n'es
	Monitoring System Installation	Must install to get representative emission and parameter measurements.	Yes.
\$ 63.8(c)(4)	CMS Requirements	Requirements for CMS	tvo §§ 63.8425 and 63.8465 specify
§ 63.8(c)(5)	Continuous Opacity Monitoring System (COMS) Minimum Procedures	COMS minimum procedures	requirements. No. not applicable
\$ 63.8(c)(6)	CMS Requirements	Dero and high level calibration check requirements	No. § 63.8425 specifies require-
<sup>1</sup> <sub>8</sub> 63 8(c),7.—(8) ,)	GMS Requirements	Out-of control periods	ments. No. § 63.8425 specifies require-
		Requirements for CMS quality control	ments No. § 63.8425 specifies require- ments.
(j. 63. 8re)	GMS Performance Evaluation	Requirements for CMS performance evaluation	f4r. (163.8425 specifies require-
(,63.8/fr.1)=/51	Alternative Monitoring Method	Procedures for Administrator to approve alternative monotoring	nients Nes

TABLE 7 TO SUBPART JJJJJ OF PART 63.—APPLICABILITY OF GENERAL PROVISIONS TO SUBPART JJJJJ—Continued

Citation	Subject	Brief description	Applies to subpart JJJJJ
§ 63.8(f)(6)	Alternative to Relative Accuracy Test	Procedures for Administrator to approve alternative rel- ative accuracy test for continuous emissions monitoring systems (CEMS).	No, not applicable.
§ 63,8(g)	Data Reduction	COMS and CEMS data reduction requirements	No, not applicable.
§ 63.9(a)	Notification Requirements	Applicability; State delegation	Yes.
§ 63.9(b)	Initial Notifications	Requirements for initial notifications	Yes.
§ 63.9(c)	Request for Compliance Extension	Can request if cannot comply by date or if installed BACT/ LAER.	Yes.
§ 63.9(d)	Notification of Special Compliance Requirements for New Source.	For sources that commence construction between pro- posal and promulgation and want to comply 3 years after effective date.	Yes.
\$63.9(e)	Notification of Performance Test	Notify Administrator 60 days prior	Yes.
§ 63.9(f)	Notification of VE/Opacity Test	Notify Administrator 30 days prior	No, not applicable.
§ 63.9(g)(1)	Additional Notifications When Using CMS.	Notification of performance evaluation	Yes.
§ 63.9(g)(2)-(3)	Additional Notifications When Using CMS.	Notification of COMS data use; notification that relative accuracy alternative criterion were exceeded.	No, not applicable.
§ 63.9(h)	Notification of Compliance Status	Contents; submittal requirements	Yes.
§ 63.9(i)	Adjustment of Submittal Deadlines	Procedures for Administrator to approve change in when notifications must be submitted.	Yes.
§ 63.9(j)	Change in Previous Information	Must submit within 15 days after the change	Yes.
§ 63.10(a)	Recordkeeping/Reporting	Applicability; general information	Yes.
§ 63.10(b)(1)	General Recordkeeping Requirements	General requirements	Yes.
§ 63.10(b)(2)(i)-(v)	Records Related to SSM	Requirements for SSM records	Yes.
§ 63.10(b)(2)(vi)— (xii) and (xiv).	CMS Records	Records when CMS is malfunctioning, inoperative or out- of-control.	Yes.
§ 63.10(b)(2)(xiii)	Records	Records when using alternative to relative accuracy test	
§ 63.10(b)(3)	Records	Applicability Determinations	
§ 63.10(c)(1)-(15)	Records	Additional records for CMS	No, §§ 63.8425 and 63.8490 specify requirements.
§ 63.10(d)(1) and (2).	General Reporting Requirements	Requirements for and reporting; performance test results reporting.	Yes.
§ 63,10(d)(3)	Reporting Opacity or VE Observations	Requirements for reporting opacity and VE	No, not applicable.
§ 63.10(d)(4)	Progress Reports	Must submit progress reports on schedule if under compli- ance extension.	Yes.
§ 63.10(d)(5)	SSM Reports	Contents and submission	
§ 63.10(e)(1)-(3)	Additional CMS Reports	Requirements for CMS reporting	No, §§ 63.8425 and 63.8485 specify requirements.
§ 63.10(e)(4)	Reporting COMS data	Requirements for reporting COMS data with performance test data.	
§ 63,10(f)	Waiver for Recordkeeping/Reporting	Procedures for Administrator to waive	
§ 63,11	Flares	Requirement for flares	No, not applicable.
§ 63.12	Delegation	State authority to enforce standards	
§ 63.13	Addresses	Addresses for reports, notifications, requests	
§ 63.14	Incorporation by Reference	Materials incorporated by reference	
§ 63.15	Availability of Information	Information availability; confidential information	Yes.

Part 63 is amended by adding subpart KKKKK to read as follows:

### Subpart KKKKK—National Emission Standards for Hazardous Air Pollutants for Clay Ceramics Manufacturing

Sec.

### What This Subpart Covers

63.8530 What is the purpose of this subpart?

63.8535 Am I subject to this subpart? 63.8540 What parts of my plant does this subpart cover?

63.8545 When do I have to comply with this subpart?

### Emission Limitations and Work Practice Standards

63.8555 What emission limitations and work practice standards must I meet?
 63.8560 What are my options for meeting the emission limitations and work practice standards?

### General Compliance Requirements

63.8570 What are my general requirements for complying with this subpart? 63.8575 What do I need to know about

operation, maintenance, and monitoring plans?

### Testing and Initial Compliance Requirements

63,8585 By what date must I conduct performance least

- 63.8590 When must I conduct subsequent performance tests?
- 63 8595 How do I conduct performance tests and establish operating limits?
- 63.8600 What are my monitoring installation, operation, and maintenance requirements?
- 63.8605 How do I demonstrate initial compliance with the emission limitations and work practice standards?

### **Continuous Compliance Requirements**

63.8615 How do I monitor and collect data to demonstrate continuous compliance?

65.8620 How do I demonstrate continuous compliance with the emission limitations and work practice standards?

### Corrections

Federal Register

Vol. 68, No. 102

Wednesday, May 28, 2003

This section of the FEDERAL REGISTER contains editorial corrections of previously published Presidential, Aule, Proposed Rule, and Notice documents. These corrections are prepared by the Office of the Federal Register. Agency prepared corrections are issued as signed documents and appear in the appropriate document categories elsewhere in the issue.

### ENVIRONMENTAL PROTECTION AGENCY

#### 40 CFR Part 63

[OAR-2002-0054 and OAR-2002-0055, FRL-7459-9]

RIN 2060-A167 and 2060-A168

National Emission Standards for Hazardous Air Pollutants for Brick and Structural Clay Products Manufacturing; and National Emission Standards for Hazardous Air Pollutants for Clay Ceramics Manufacturing

#### Correction

In rule document 03-5739 beginning on page 26690 in the issue of Friday,

May 16, 2003, make the following corrections:

#### §63.8395 [Corrected]

On page 26723, in the first column, in \$63.8395(b), in the last line "May 16, 2003" should read "May 16, 2006".

### §63.8545 [Corrected]

On page 26739, in the third column, in §63.8545(b), in the last line "May 16, 2003" should read "May 16, 2006".

IFR Doc. C3-5739 Filed 5-27-03; 8:45 am] BILLING CODE 1505-01-0

### **Environmental Protection Agency**

Chemical hame	CAS No.
Unear sicohols, ethoxylated, and sultated so-	
dium se:si	
Linear alcohols, sulfated sodium sett, mixed	:23-0:-3
Linear sixylbanzana	142-72-2
Magnesium acetate	106-31-5
Malamine	105-76-1
Masityl Dride	141-7:∵
Metheoryantinie	125-96-7
Methanol	67-56-1 74-89-5
Mathylaminear-Mathylbanzanadamine	25376-45-9
Memyl chiange	74-67-3
Methylene chlonde	75-09-2
Metnyi etnyi ketone	78 <del>3</del> 33 74 <b>-88-</b> 4
Mathyl Igdiae	108-10-1
Menyi mehacryele	B0636
2-Mathylpartane	107-83-5
1-Mathyl-2-pyrrohoone	572-5(-4
Matnyl ten-butyl einer	91-20-3
Nationalization	96-95-3
1-Nonehe	( 27215 <del>-95-</del> 8 -
Nonvi Biodhol	145-05-8
Nonvipnenoi	25154-52-3 9015-45-6
Nonylpheno, elnoxylated	25377-83-7
Он-зогоры рыговит випольть, сысции вы	
Oil-soluble permiauti sultonate sodium sall	
Pentserythmol	115-77-5
n-Pentane	105-66-6 4635-87-4
Fertenes, m.x85	105671
Perchiometrylene	127-18-4
Phenol	106-25-0
1-Phenylethyl hydroperoxide	3071-32-7 103-65-1
Phenylprobane	75-44-5
Phihaic annyone	e:ac_5
рюдале	7# <b>-9</b> F
Propionalgenyge	123-3t-6
Propionic Boid	7(05: 71-25-8
Propvi alcohol	135-07-1
ը-քիչիչը էսյնոնրոնսս	7t-8:7
Propylene glyco!	5"-5:-6
Propviena oxide	14;-3;-6
Saratio:	5'-7(
Siyrene	5;-7(
Terephinalic acid	100-21-0
t 1,2,2 Teirachiorpethane	75-34-5
Terraeinvi isad	1 "8-0(-1 1()-9-9
Terranyarower	1
Tetrametry, Isab	75-14-1
Toluene	106-06-3
Totuene-1 4-diameter	05-B(⊢_3
Piguane 1.4-tend. 1.5 r disocyanaie 189/20	
Tipogramshare	75-25-2
; 1.1-Thenlorgelhane	71-5:
1.1.2-Thenierobihane	7:-5:-5
Therefore	75-01-6 75-64-6
Thankskaltubromathant	7(-1
Thethangiaming	101-7:-6
Treinvione gives	1,2-21-6
Vinyi Bosiali	106-05-4
Vinylidene chioride	7:-3:-
Ti kylehe	106-36-3
C NoiPrit	

Chemice name	CAS No."
p-Xylenes Yylenes (mixet) m-Xylenei	106-42-3 1330-26-7 576-26-1

CAS numbers refer to the Chemical Abstracts Registry numbers assigned to specific chamicals, isomers, or mixtures of chemicals. Some isomers or mixtures that are covered by the standards do not have CAS numbers assigned to them, The standards apply to all of the chemicals listed whether CAS numbers have been assigned or not.

[55 FR 26942, June 29, 1990, as amended at 65 FR 58237, 58236, Nov 27, 1995]

#### \$ 60,668 Delegation of authority.

(a) In delegating implementation and enforcement authority to a State under §111(c) of the Act, the authorities contained in paragraph (b) of this section shall be retained by the Administrator and not transferred to a State.

(b) Authorities which will not be delegated to States: \$60.863(e).

### Subpart 000—Standards of Performance for Nonmetallic Mineral Processing Plants

SCIRCE: E) FR 31337, Aug. 1, 1985, unless otherwise noted.

### § 60.670 Applicability and designation of affected facility.

(a)(1) Except as provided in paragraphs (a)(2), (b), (c), and (d) of this section, the provisions of this subpart are applicable to the following affected facilities in fixed or portable nonmetallic minetal processing plants: each crusher, grinding mill, screening operation, bucket elevator, belt conveyor bagging operation, storage bin, enclosed truck or railcar loading station. Flee, crushers and granding mills at no: nam asphalt facilities that reduce the size of nonmetallic minerals embedued in recycled asphalt pavenient and sucsequent affected facilities ut to, but not abeliading, the first storage sile of him are subject to the provisions of this suppart.

Do The provisions of this subpart of not apply to the following operations: All facilities located in underground mines: and stand-clone servening operaations of plants without ornshers of princing mills

to Ar affected facility that is subject to the provisions of subpart P or I or that follows in the Plant process any facility subject to the provisions of subparts F or I of this part is not subject to the provisions of this subpart.

(c) Facilities at the following plants are not subject to the provisions of this subpart:

(I) Fixed sand and gravel plants and crushed stone plants with capacities, as defined in §60.671, of 23 megagrams per hour (25 tons per hour) or less;

(2) Portable sand and gravel plants and crushed stone plants with capacities, as defined in \$60.671, of 136 megagrams per hour (150 tons per hour) or less; and

(3) Common clay plants and pumice plants with capacities, as defined in §60.671, of 9 megagrams per hour (10 tons per hour) or less.

(d)(1) When an existing facility is replaced by a piece of equipment of equal or smaller size, as defined in §60.671, having the same function as the existing facility, the new facility is exempt from the provisions of §§60.672, 60.674,

and 60.6% except as provided for in paragraph (d)(3) of this section.

- (2) An owner or operator complying with paragraph (d)(1) of this section shall submit the information required in § 60.676(a).
- (3) An owner or operator replacing all existing facilities in a production line with new facilities does not qualify for the exemption described in paragraph (d)(1) of this section and must comply with the provisions of §§ 60.672, 60.674 and 60.675.
- (e) An affected facility under paragraph (a) of this section that commences construction, reconstruction, or modification after August 31, 1983 is subject to the requirements of this part.
- (f) Table 1 of this subpart specifies the provisions of subpart A of this part 60 that apply and those that do not apply to owners and operators of affected facilities subject to this subpart.

TABLE 1---APPLICABILITY OF SUBPART A TO SUBPART OOO

Subpert A reference	Applies to Subpert OOO	Comment
60.1, Applicability	Yes.	
60.2, Delinitions	Yes.	
60.3, Units and abbreviations	Yes.	
(8)	Yes.	
(b)	Yes.	
60.5, Determination of construction or modification.	Yes.	
60.6, Review of plans	Yes.	
60.7, Notification and recordkeeping	Yes	Except in (a)(2) report of enticipated date of initial startup is not required (§ 60.678(h)).
60.8, Performence tests	Yes ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Except in (d), exter 30 days notice for an initially achained performance test, any rescheduled performance test requires 7 days notice, not 30 days (§ 60.675(g)).
60.9, Availability of information	Yea.	
60.10, State authority	Yes.	
80.11, Compliance with standards and maintenance requirements.	Yes	Except in (b) under certain conditions (§§ 80.575 (c)(3) and (b)(4)), Mainod 9 observation may be reduced from 3 hours to 1 hour. Some affected facilities exempted from Method 9 tests (§ 60.675(n)).
60,12, Circumventlon	Yes.	
80.13, Monitoring requirements	Yes.	
80.14, Modification	Yes.	
60.15, Reconstruction	Yes.	
60.16, Priority list	Yes.	
60.17, Incorporations by reference	Yes.	
60.18, General control device	No	Flares will not be used to comply with the emission limits.
<ol> <li>General notification and reporting requirements.</li> </ol>	Yes.	

[51 FR 31337, Aug. 1, 1985, as amended at 62 FR 31359, June 9, 1997]

### § 60.671 Definitions.

All terms used in this subpart, but not specifically defined in this section, shall have the meaning given them in the Act and in subpart A of this part.

### **Environmental Protection Agency**

Eagoing operation means the mechanical process by which bags are filled with nonmetallic minerals.

Belt conveyor means a conveying device that transports material from one location to another by means of an endless belt that is carried on a series of idlers and routed around a pulley at each end.

Hucket elevator means a conveying device of nonmetallic minerals consisting of a head and foot assembly which supports and drives an endless single or double strand chain or belt to which buckets are attached.

Building means any frame structure with a roof.

Capacity means the cumulative rated capacity of all initial crushers that are part of the plant.

Capture system means the equipment (including enclosures, hoods, ducts, fans, dampers, etc.) used to capture and transport particulate matter generated by one or more process operations to a control device.

Control device means the air pollution control equipment used to reduce particulate matter emissions released to the atmosphere from one or more process operations at a nonmetallic mineral processing plant.

Conveying system means a device for transporting materials from one piece of equipment or location to another location within a plant. Conveying systems include but are not limited to the following. Feeders belt conveyors, bushet elevators and pneumatic systems.

Crusher means a machine used to crush any nonmetallic minerals, and includes, but is not limited to, the following types: jaw. gyratory, cone. roll. rod null, hammermill, and impactor.

Enclosed truck or railtan loading runtion means that portion of a hopmetallic mineral processing plant where normstallic minerals are loaded by an enclosed copreging system, into enclosed trucks or railcars

Fired plant means any commetallic mineral processing plant at which the processing equipment specified in §60.070 at is attached by a cable chain, numbucile, bolt or other means except electrical connections: to any ancord, slab, or structure including bedrace.

Fugitive emission means particulate matter that is not collected by a capture system and is released to the atmosphere at the point of generation.

Grinding mill means a machine used for the wet or dry fine crushing of any normetallic mineral. Grinding mills include, but are not limited to, the following types hammer, roller, rod, pebble and ball, and fluid energy. The grinding mill includes the air conveying system, air separator, or air classifier, where such systems are used.

Initial crusher means any crusher into which nonmetallic minerals can be fed without prior crushing in the plant.

Nonmetallic mineral means any of the following minerals or any mixture of which the majority is any of the following minerals:

- (a) Crushed and Broken Stone, including Limestone, Dolomite, Granite, Traprock, Sandstone, Quartz, Quartzite, Marl. Marble, Slate, Shale, Dil Shale, and Shell.
  - (b) Sand and Gravel.
- (c) Clay including Kaolin, Fireclay, Bentonite, Fuller's Earth, Ball Clay, and Common Clay.
  - (d) Rock Salt.
  - re, Gypsum.
- (f) Sodium Compounds, including Scdium Carbonate, Sodium Chloride, and Sodium Sulfate.
  - (g) Pumice.
  - h Gilsomte.
  - (i) Tale and Pyrophyllite.
- (j. Boron, including Borax, Rernits, and Colemanits.
  - The Barite.
  - (I.F) acrospar.
  - ımı Feldspar.
  - m) Diatomite.
  - ·c Perlite.
  - (p) Yermiculite.
  - iqiMica.
- iri Hyanite, including Andalusite, Sillimanite, Topas, and Dumortierite.

Nonmetallic mineral processing plant means any combination of equipment that is used to crush or grind any non-metallic mineral wherever located, including lime plants power plants steel mills, asphalt concrete plants, portland cement plants, or any other facility processing pennietallic minerals except as provided in §80.676 (b) and c).

Fartable plant nields aby homma tallic mineral processing plant that is

mounted on any chassis or skids and may be moved by the application of a lifting or pulling force. In addition, there shall be no cable, chain, turn-buckle, bolt or other means (except electrical connections) by which any piece of equipment is attached or clamped to any anchor, slab, or structure, including bedrock that must be removed prior to the application of a lifting or pulling force for the purpose of transporting the unit.

Production line means all affected facilities (crushers, grinding mills, screening operations, bucket elevators, belt conveyors, bagging operations, storage bins, and enclosed truck and railcar loading stations) which are directly connected or are connected together by a conveying system.

Screening operation means a device for separating material according to size by passing undersize material through one or more mesh surfaces (screens) in series, and retaining oversize material on the mesh surfaces (screens).

Size means the rated capacity in tons per hour of a crusher, grinding mill, bucket elevator, bagging operation, or enclosed truck or railcar loading station; the total surface area of the ton screen of a screening operation; the width of a conveyor belt; and the rated capacity in tons of a storage bin.

Stack emission means the particulate matter that is released to the atmosphere from a capture system.

Storage bin means a facility for storage (including surge bins) or non-metallic minerals prior to further processing or loading.

Transfer point means a point in a conveying operation where the non-metallic mineral is transferred to or from a belt conveyor except where the nonmetallic mineral is being transferred to a stockpile.

Truck dumping means the unloading of nonmetallic minerals from movable vehicles designed to transport nonmetallic minerals from one location to another. Movable vehicles include but are not limited to: trucks, front end loaders, skip hoists, and railcars.

Vent means an opening through which there is mechanically induced air flow for the purpose of exhausting from a building air carrying particulate matter emissions from one or

more affected facilities.

Wet mining operation means a mining or dredging operation designed and operated to extract any nonmetallic mineral regulated under this subpart from deposits existing at or below the water table, where the nonmetallic mineral is

saturated with water.

Wet screening operation means a screening operation at a nonmetallic mineral processing plant which removes unwanted material or which separates marketable fines from the product by a washing process which is designed and operated at all times such that the product is saturated with water.

[51 FR 31337, Aug. 1, 1985, as amended at 62 FR 31359, June 9, 1997]

#### § 60.672 Standard for particulate matter.

- (a) On and after the date on which the performance test required to be conducted by \$60.8 is completed, no owner or operator subject to the provisions of this subpart shall cause to be discharged into the atmosphere from any transfer point on belt conveyors or from any other affected facility any stack emissions which:
- Contain particulate matter in excess of 0.05 g/dscm (0.022 gr/dscf); and
- (2) Exhibit greater than 7 percent opacity, unless the stack emissions are discharged from an affected facility using a wet scrubbing control device. Facilities using a wet scrubber must comply with the reporting provisions of §60.676 (c), (d), and (e).
- (b) On and after the sixtieth day after achieving the maximum production rate at which the affected facility will be operated, but not later than 180 days after initial startup as required under \$60.11 of this part, no owner or operator subject to the provisions of this subpart shall cause to be discharged into the atmosphere from any transfer point on belt conveyors or from any other affected facility any fugitive emissions which exhibit greater than 10 percent opacity, except as provided in paragraphs (c), (d), and (e) of this section.
- (c) On and after the sixtieth day after achieving the maximum production rate at which the affected facility will

### **Environmental Protection Agency**

be operated, but not later than 180 days after initial startup as required under §60.11 of this part, no owner or operator shall cause to be discharged into the atmosphere from any crusher, at which a capture system is not used, fugitive emissions which exhibit greater than 15 percent opacity.

- (d) Truck dumping of nonmetallic minerals into any screening operation, feed hopper, or crusher is exempt from the requirements of this section.
- (e) If any transfer point on a conveyor belt or any other affected facility is enclosed in a building, then each enclosed affected facility must comply with the emission limits in paragraphs (a), (b) and (c) of this section, or the building enclosing the affected facility or facilities must comply with the following emission limits:
- (1) No owner or operator shall cause to be discharged into the atmosphere from any building enclosing any transfer point on a conveyor belt or any other affected facility any visible fugitive emissions except emissions from a vent as defined in §60.671.
- (2) No owner or operator shall cause to be discharged into the atmosphere from any vent of any building enclosing any transfer point on a conveyor belt or any other affected facility emissions which exceed the stack emissions limits in paragraph (a) of this section.
- (f) On and after the sixtieth day after achieving the maximum production rate at which the affected facility will be operated, but not later than 180 days after initial startup as required under § 60.11 of this part, no owner or operator shall cause to be discharged into the atmosphere from any baghouse that controls emissions from only ab individual, enclosed storage bin, stack emissions which exhibit greater than ? percent opacity.
- (g. liwners or operators of multiple storage bias with combined stack emissions shall comply with the emission limits in paragraph (a)(1) and (a)(2) of this section.
- The On and after the sixtieth day after abmeving the maximum production rate at wince the affected facility will be operated, but not later than 180 days after initial startup, no owner or operator shall cause to be discharged

into the atmosphere any visible emissions from:

- (1) Wet screening operations and subsequent screening operations, bucket elevators, and belt conveyors that process saturated material in the production line up to the next crusher, grinding mill or storage bin.
- (2) Screening operations, bucket elevators, and belt conveyors in the production line downstream of wet mining operations, where such screening operations, bucket elevators, and belt conveyors process saturated materials up to the first crusher, grinding mill, or storage bin in the production line.

[51 FR 31337, Aug. 1, 1985, as amended at 62 PFL 31359, June 5, 1997; 65 FR 61778, Cict. 17, 2000)

### § 60.673 Reconstruction.

- (a) The cost of replacement of orecontact surfaces on processing equipment shall not be considered in calculating either the "fixed capital cost of the new components" or the "fixed capital cost that would be required to construct a comparable new facility" under §60.15. Ore-contact surfaces are crushing surfaces, screen meshes, bars, and plates; conveyor belts; and elevator buckets.
- (b) Under §60.15, the "fixed capital cost of the new components" includes the fixed capital cost of all depreciable components (except components specified in paragraph (a) of this section; which are or will be replaced pursuant to all continuous programs of component replacement commenced within any 1-year period following August 31, 199:

#### ! 60.674 Monitoring of operations.

The owner or operator of any affected facility subject to the provisions of this subpart which uses a wet scrabber to control emission; shall install, calibrate, maintain and operate the following monitoring devices:

a. A device for the continuous measurement of the pressure loss of the pas stream through the scrumber. The monitoring device must be certified by the manufacturer to be accurate within 1256 passais all increwater gauge pressure and must be calibrated on an annual hasis in accordance with manufacturer's instructions.

(b) A device for the continuous measurement of the scrubbing liquid flow rate to the wet scrubber. The monitoring device must be certified by the manufacturer to be accurate within ±5 percent of design scrubbing liquid flow rate and must be calibrated on an annual basis in accordance with manufacturer's instructions.

#### § 60.675 Test methods and procedures.

- (a) In conducting the performance tests required in §60.8, the owner or operator shall use as reference methods and procedures the test methods in appendix A of this part or other methods and procedures as specified in this section, except as provided in §60.8(b). Acceptable alternative methods and procedures are given in paragraph (e) of this section.
- (b) The owner or operator shall determine compliance with the particulate matter standards in §60.672(a) as follows:
- (1) Method 5 or Method 17 shall be used to determine the particulate matter concentration. The sample volume shall be at least 1.70 dscm (60 dscf). For Method 5, if the gas stream being sampled is at ambient temperature, the sampling probe and filter may be operated without heaters. If the gas stream is above ambient temperature, the sampling probe and filter may be operated at a temperature high enough, but no higher than 121 °C (250 °F), to prevent water condensation on the filter.
- (2) Method 9 and the procedures in §60.11 shall be used to determine opacity.
- (c)(1) In determining compliance with the particulate matter standards in §60.672 (b) and (c), the owner or operator shall use Method 9 and the procedures in §60.11, with the following additions:
- (i) The minimum distance between the observer and the emission source shall be 4.57 meters (15 feet).
- (ii) The observer shall, when possible, select a position that minimizes interference from other fugitive emission sources (e.g., road dust). The required observer position relative to the sun (Method 9, Section 2.1) must be followed.
- (iii) For affected facilities using wet dust suppression for particulate matter

- control, a visible mist is sometimes generated by the spray. The water mist must not be confused with particulate matter emissions and is not to be considered a visible emission. When a water mist of this nature is present, the observation of emissions is to be made at a point in the plume where the mist is no longer visible.
- (2) In determining compliance with the opacity of stack emissions from any baghouse that controls emissions only from an individual enclosed storage bin under §60.672(f) of this subpart, using Method 9, the duration of the Method 9 observations shall be 1 hour (ten 6-minute averages).
- (3) V ining compliance with the fugitive emissions standard for any affected facility described under § 60.672(b) of this subpart, the duration of the Method 9 observations may be reduced from 3 hours (thirty 6-minute averages) to 1 hour (ten 6-minute averages) only if the following conditions apply:
- There are no individual readings greater than 10 percent opacity; and
- (ii) There are no more than 3 readings of 10 percent for the 1-hour period.
- (4) When determining compliance with the fugitive emissions standard for any crusher at which a capture system is not used as described under §60.672(c) of this subpart, the duration of the Method 9 observations may be reduced from 3 hours (thirty 6-minute averages) to 1 hour (ten 6-minute averages) only if the following conditions apply:
- There are no individual readings greater than 15 percent opacity; and
- (ii) There are no more than 3 readings of 15 percent for the 1-hour period.
- (d) In determining compliance with §60.672(e), the owner or operator shall use Method 22 to determine fugitive emissions. The performance test shall be conducted while all affected facilities inside the building are operating. The performance test for each building shall be at least 75 minutes in duration, with each side of the building and the roof being observed for at least 15 minutes.
- (e) The owner or operator may use the following as alternatives to the reference methods and procedures specified in this section:

### **Environmental Protection Agency**

- (1) For the method and procedure of paragraph (c) of this section, if emissions from two or more facilities continuously interfere so that the opacity of fugitive emissions from an individual affected facility cannot be read, either of the following procedures may be used:
- (i) Use for the combined emission stream the highest fugitive opacity standard applicable to any of the individual affected facilities contributing to the emissions stream.
- (ii) Separate the emissions so that the opacity of emissions from each affected facility can be read.
- (f) To comply with §60.676(d), the owner or operator shall record the measurements as required in §60.676(c) using the monitoring devices in §60.674 (a) and (b) during each particulate matter run and shall determine the averages.
- (g) If, after 30 days notice for an initially scheduled performance test, there is a delay (due to operational problems, etc.) in conducting any rescheduled performance test required in this section, the owner or operator of an affected facility shall submit a notice to the Administrator at least 7 days prior to any rescheduled performance test.
- (h) Initial Method 9 performance tests under \$60.11 of this part and \$60.675 of this subpart are not required for:
- (1) Wet screening operations and subsequent screening operations, bucket elevators, and belt conveyors that process saturated material in the production line up to, but not including the next crusher, grinding mill or storage bin.
- (2) Screening operations, bucket elevators, and belt conveyors in the production line downstream of wet mining operations that process saturated materials up to the first crusher, grinding mill, or storage bin in the production line.

[54 FF. 6880 Feb 14 1989 as amended at 62 FF. 20360, June 9 1997]

### \$60,676 Reporting and recordkeeping.

(a Each owner or operator seeking to comply with \$60,670(d small submit to the Administrator the following information about the emisting facility being replaced and the replacement piece of equipment.

- (1) For a crusher, grinding mill, bucket elevator, bagging operation, or enclosed truck or railcar loading station:
- (i) The rated capacity in megagrams or tons per hour of the existing facility being replaced and
- (ii) The rated capacity in tons per hour of the replacement equipment.
  - (2) For a screening operation:
- (i) The total surface area of the top screen of the existing screening operation being replaced and
- (ii) The total surface area of the top screen of the replacement screening operation.
  - (3) For a conveyor belt:
- (i) The width of the existing belt being replaced and
- (ii) The width of the replacement conveyor belt.
  - (4. For a storage bin:
- (i) The rated capacity in megagrams or tons of the existing storage bin being replaced and
- (ii) The rated capacity in megagrams or tons of replacement storage bins.
  - (b) [Reserved]
- (C) During the initial performance test of a wet scrubber, and daily thereafter, the owner or operator shall record the measurements of both the change in pressure of the gas stream across the scrubber and the scrubbing hould flow rate.
- id: After the initial performance test of a wet scrubber, the owner or operator shall submit semiannual reports to the Administrator of occurrences when the measurements of the scrubber pressure loss for gain; and liquid flow rate differ by more than ±30 percent from the averaged determined during the most recent performance test.
- (e) The reports required under paragraph (d) shall be postmarked within 30 days following end of the second and fourth calendar quarters.
- (f) The owner or operator of any affected facility shall submit written reports of the results of all performance tests conducted to demonstrate compliance with the standards set forth in \$60.671 of this surpart, including reports of opacity observations made

using Method 9 to demonstrate compliance with §60.672(b), (c), and (f), and reports of observations using Method 22 to demonstrate compliance with §60.672(e).

- (g) The owner or operator of any screening operation, bucket elevator, or belt conveyor that processes saturated material and is subject to §60.672(h) and subsequently processes unsaturated materials, shall submit a report of this change within 30 days following such change. This acreening operation, bucket elevator, or belt conveyor is then subject to the 10 percent opacity limit in §60.672(b) and the emission test requirements of §60.11 and this subpart. Likewise a screening operation, bucket elevator, or belt convevor that processes unsaturated material but subsequently processes saturated material shall submit a report of this change within 30 days following such change. This screening operation, bucket elevator, or belt conveyor is then subject to the no visible emission limit in § 60.672(h).
- (h) The subpart A requirement under §60.7(a)(2) for notification of the anticipated date of initial startup of an affected facility shall be waived for owners or operators of affected facilities regulated under this subpart.
- (i) A notification of the actual date of initial startup of each affected facility shall be submitted to the Administrator.
- (1) For a combination of affected facilities in a production line that begin actual initial startup on the same day, a single notification of startup may be submitted by the owner or operator to the Administrator. The notification shall be postmarked within 15 days after such date and shall include a description of each affected facility, equipment manufacturer, and serial number of the equipment, if available.
- (2) For portable aggregate processing plants, the notification of the actual date of initial startup shall include both the home office and the current address or location of the portable plant.
- (j) The requirements of this section remain in force until and unless the Agency, in delegating enforcement authority to a State under section 111(c) of the Act, approves reporting require-

ments or an alternative means of compliance surveillance adopted by such States. In that event, affected facilities within the State will be relieved of the obligation to comply with the reporting requirements of this section, provided that they comply with requirements established by the State.

[51 FR 31337, Aug. 1, 1985, as amended at 54 FR 6680, Feb. 14, 1989; 62 FR 31360, June 9, 1997; 65 FR 51778, Oct. 17, 2000]

### Subpart PPP—Standard of Performance for Wool Fiberglass Insulation Manufacturing Piants

Source: 50 FR 7699, Feb. 25, 1985, unless otherwise noted.

### § 60.680 Applicability and designation of affected facility.

- (a) The affected facility to which the provisions of this subpart apply is each rotary spin wool fiberglass insulation manufacturing line.
- (b) The owner or operator of any facility under paragraph (a) of this section that commences construction, modification, or reconstruction after February 7, 1984, is subject to the requirements of this subpart.

#### § 60.681 Definitions.

As used in this subpart, all terms not defined herein shall have the meaning given them in the Act and in subpart A of this part.

Glass pull rate means the mass of molten glass utilized in the manufacture of wool fiberglass insulation at a single manufacturing line in a specified time period.

Manufacturing line means the manufacturing equipment comprising the forming section, where molten glass is fiberized and a fiberglass mat is formed; the curing section, where the binder resin in the mat is thermally "set;" and the cooling section, where the mat is cooled.

Rotary spin means a process used to produce wool fiberglass insulation by forcing molten glass through numerous small orifices in the side wall of a spinner to form continuous glass fibers that are then broken into discrete lengths by high velocity air flow.